

ONLY CONTRACTORS (EXCEPT FOR CONTRACTORS WHOSE TENDERS ARE TERMINATED) EMPANELLED WITH UCO BANK Z.O JALANDHAR CAN APPLY

ISSUED TO M/S_____

**TENDER DOCUMENT
FOR
FURNISHING WORKS
OF
UCO BANK AT
RAMBAGH AMRITSAR - BRANCH**

ARCHITECTS:

**SHELTER ARCHITECTS & ENGINEERS,
1109/C, BACK SIDE ROYAL BOYS
HOSTEL, GHUMAR MANDI,
LUDHIANA-141001
(M) 98141-05631,
PH. 0161-2410369.**

Date of submission of tender: 21-07-2026 upto 05:00 PM
Date of opening of tender: 22-07-2026 upto 12:00 PM
(Tender to be submitted in the office of AGM, UCO Bank, Z.O Jalandhar)



DETAILS OF TENDER

TENDER FOR FURNISHING OF UCO BANK RAMBAGH AMRITSAR BRANCH

- | | | | |
|-----|---|---|--|
| 1. | Details of work to be done | : | Interior / Furnishing & Allied Electrical Works for UCO Bank, Rambagh, Amritsar Branch |
| 2. | Form of Contact | : | Item wise Rate. |
| 3. | Earnest Money | : | Rs. 14,200/- (Rupees Fourteen Thousand Two Hundred Only)
In form of Demand draft
in Favour of UCO Bank payable at
Jalandhar |
| 4. | Period of Contract/
Time of Completion. | : | 45 Days. |
| 5. | Last Date & Time for receiving
Of sealed tender. | : | 22-July-2026 at 5:00 pm. |
| 6. | Liquidated damages for non-
Completion of work in time | : | 1.0 % of the contract value per week
subject to a max of 10% of the contract
value. |
| 7. | Defect Liability Period | : | 12 months (Twelve Months) from the
Date of virtual completion as certified by
Architect / employer. |
| 8. | Retention Amount for 12 months | : | 8 % of the total bill. |
| 9. | Period of submitting of Final bill | : | 15 Days from the Date of Completion |
| 10. | Mobilization Advance / Secured
Advance | : | No. Mobilization advance / secured
Advance will be given to the contractor. |
| 11. | Place and Date of opening of tender : | | 22-July-2026 at 2:00 pm in the
Office of the Asst General Manager,
UCO Bank, Zonal office, Jalandhar |



TENDER FOR FURNISHING OF UCO BANK RAMBAGH, AMRITSAR

GENERAL CONDITIONS

1. The Contractor shall sign each page of this tender.
2. Payment to the contractor agency shall be made as per actual work done at site.
3. Quantity of work may increase or decrease at site as per requirement, which shall not affect the rates quoted by the contractor.
4. Furnishing works including electrical works etc. shall be done to the complete satisfaction of Bank and Architect-in-charge.
5. All teak / Cedar wood / Rubber wood to be used should be knotless which is to be polished with all background surface preparation courses maintaining the visibility of wood grains.
6. The rates to be quoted shall include the cost of material, labour charges, carriage, sales tax, or any / all other taxes any required hardware etc.
7. The contractor agency shall keep particular vigil on his workers/ carpenters/ painters etc. to maintain very good workmanship of all items, failing which no payment shall be made and no claim of material / labour used shall be made to him in any case, and the same work shall be executed by him again without charging any extra cost.
8. All rates shall be quoted in words & figures & any cutting over writing shall be signed.
9. All items to be executed as per drawings, if any change is required, the same shall be brought to the notice of architect-in-Charge.
10. Any tender / quotation containing clerical or arithmetical mistakes shall be rejected.
11. Any addition, alteration or correction shall be signed and stamped properly.
12. Contractor agencies are advised (before quoting the rates) to inspect the site of the proposed work. He must go through all drawings and specifications and documents.
13. The bank reserves the right to accept / reject any tender / quotation without assigning any reason.
14. The contractor agency should have already executed works of furnishing interiors & exterior, civil works of very good workmanship.
15. Quality of material and workmanship rejected by the architect / concerned authorities shall be removed immediately by the contractor and rectified /replaced.
16. No advance payment shall be made to the contractor on supply of any material supplied at site for execution. Payment shall only be made on execution of any concerned / particular item.



17. The rates include the cost of coat of anti -termite treatment on all wooden frame work and all commercial ply / board used for partitions and paneling, furniture etc. The contractor/s shall have to dismantle & dispose the existing counters, tables & partitions within the quoted cost of the total furnishing works.
18. Rates for partitions, paneling, wall cladding and false ceiling shall include cutting and making good of necessary cut-outs/chiseling to be made for electrical conduits, switch boards etc.
19. Bank shall not be responsible for any lose or damage to the contractor / labour due to any natural calamity during the course of construction. Contractor is liable to make good all the damages if any, till the work is completed and handed over to the bank authorities.
20. Any payment to the contractor on account of execution of work, whether it is running payment or final, shall be verified by the Architect-in-Charge.
21. Unless, otherwise mentioned all materials to be used shall be I.S.I. marked. Failure to do so, the work may be rejected and in that case contractor shall have to remove the defective materials and replace / re-do the work for which no claim shall be entertained.
22. The total work shall be supervised by the architect-in-charge and he/she shall be kept fully informed by the contractor regarding the progress of work.
23. Bank may award the work in part or whole to a single party or any other party.
24. It may please be noted that the bank is not bound to allot the work to the lowest party, and as such, the allotment of work shall be based on workability of rates quoted by the contractor on account of quality work.
25. The bank reserves the right to reject any or all the tenders without assigning any reason whatsoever.
26. The earnest money deposited shall not carry any interest and will be refunded to the unsuccessful renderers.
27. Earnest money paid by the contractor shall be forfeited by the bank if contractor fails to undertake the job if he is communicated about acceptance of his rates / tender.
28. The contractor shall take all the necessary precautions while working and to safe guard adjacent property, Bank's property, Bank's Employees, and traffic persons.
29. All the rates quoted are inclusive of removal of existing counters, partitions, wiring, rubbish / debris collected during the progress of work, rejected materials etc.
30. The contractor shall not directly or indirectly sublet the work to other party without written permission of the bank.



31. The quantities mentioned in schedule are provisional and likely to increase / decrease to any extent or may be omitted thus altering the aggregate value of the contract. No claim for loss of profit / business shall be entertained on this account.
32. The bank reserves the right to distribute the work for which quotations have been called, among more than one parties, if found necessary. No claim in this respect shall be considered and the contractor agrees to cooperate with other agencies appointed by the bank.
33. All the workers of the contractor must be properly covered by an insurance policy under "Workman's Compensation Act" and "Fatal Accidents Act". The contractor at his own expenses arrange to effect and maintain until the virtual completion of the contract, insurance policy in the joint name of bank and the contractor against this risk to be retained by the bank until the virtual completion of the work, and indemnify the bank from all the liabilities arising out of such events, in case of delay, contractor shall arrange to extend insurance policy till work is completed.
34. All the work should be completed within the specified period in the tender. If the work is delayed due to the reasons beyond the control of the contractor, he should keep intimating the bank explaining, therein the reasons for such delays, immediately and if in the opinion of Bank's authorities the delay is justified, the contractor shall be granted extension in time limit.
35. The contractor shall furnish well in time before work commence at his own cost, colour samples, samples of materials or workmanship that may be called by bank's Architect / Engineer for approval. Rates quoted shall cover for such preliminary work.
36. All the glass panes, door handles / hinges, electric fittings, fans, furniture, records, floors etc., are to be thoroughly cleaned after the work is completed.
37. The rates quoted by the contractor shall be firm throughout the duration of contract (including extension of time if any granted) and will not be subject to any fluctuation due to variation in cost of material and labour.
38. Conditional tenders are liable to be rejected.
39. The successful tenderer is bound to carry out any item of work necessary for the completion of the job even those such items are not included in schedule of quantities.
40. If in any case of work required to be abandoned, the contractor shall be entitled for any claims and he will be paid as per the actual work done till that period, if deemed fit.
41. Decision of the bank shall be final and binding on any matter connected with the work. The matter of any dispute shall be decided after mutual discussions based on



the terms and conditions of this contract. However, if the matter cannot be resolved then the same shall be referred to the respected qualified person agreed to both the parties and his opinion shall be binding on both the parties. However, this is precourse to any legal action in this regard.

42. If at any stage during the progress of work, it is observed that the contractor is not progressing the work with due diligence, care of lagging much behind the schedule or fails to gear up the work despite instructions from Bank's Architect, the Employer (Bank) reserves the right to terminate the contract with 7 days-notice. In such case the contractor shall be liable to pay the employer any extra cost involved for the completion of the said work and will not obstruct any way in completing the work through other agency. After completion of entire work the contractor shall be paid for the actual work executed by him at the quoted rates after deducting any claims, damages. In case of such termination the security deposit held by the bank will be forfeited.
43. Contractor shall follow all rules / regulation in force and should posses the license for employing labour and also follow all safety measures, labour bye laws and shall be responsible for any lapse.
44. At any stage i.e. during the execution of work, any kind of change required. Whether it is in design or specification, the same has to be in-corporated by the contractor.

CONTRACTOR

ARCHITECT

UCO BANK



TENDER FOR FURNISHING WORKS OF UCO BANK RAMBAGH, AMRITSAR

FOR FURNISHING WORK TO BE USED

S. No.	DESCRIPTION	BRAND
1)	Board /ply	Century (Sainik), Green Ply (Ecotech), Archid Ply
2)	Laminate	Aica-Sunmica (E761/1761-Bleached teak, G568/1568-electric blue), or equivalent shade in Merino laminates, Centurylam: 1mm th.
3)	Door closer /floor spring	Everite, Doorking, Nitco, Everest.
4)	Drawer & Keyboard, Slide Rails	Becker, Ebco, Ozoe, Hiwin (Telescopic)
5)	Glue for fixing commercial Board/Laminate	Fevicol, Jeevanjor (Pidilite)
6)	Glass	Triveni, Modi float, saint gobain, Asahi. Godrej, Harrison
7)	Mortic Latch & Lock	Godrej, Harrison
8)	Multi-Purpose Locks	Harrison, Godrej
9)	Vertical Blinds	Vista Levelor /Mac
10)	Tapestry/leather foam	Harmony, Vimal, Bhor or as approved
11)	Aluminium Sections	Jindal /Mahavir /Hindalco
12)	False Ceiling	India Gypsum, Saint Gobain, Kingston, Armstrong
13)	Synthetic Enamel	Asian, Nerolac, ICI, Berger
14)	Emulsion Paint/Plastic Paint	Asian, Nerolac, ICI, Berger



SPECIFICATIONS /BRANDS /MAKE OF ITEMS
FOR ELECTRICAL WORK TO BE USED

S. No.	PRODUCTS	MANUFACTURERS
1.	SFU/MCCB/ Change over switch /DB	L&T/Legrand /Anchor/Havells
2.	Voltmeter/Ampere meter	AE/L&T.
3.	Armored Cable	Glaster/CCI/Polycab/Parkash
4.	PVC Insulated Wires	Finolex/R.R Cables/Polycab/Havells
5.	Telephone Cable	Finolex/R.R Cables/Delton/Havells
6.	Data cables & I.O's	Lucent/D-link
7.	Modular switch /socket/call bell/MCB's	North west Havells/Anchor Penta
8.	Light fitting & Lamps LED	Philips /Crompton/Wipro/Syska.
9.	Ceiling fan/Wall Bracket Fan Exhaust Fan	Crompton/Crompton /Orient.



BOQ's UCO BANK BRANCH, RAMBAGH AMRITSAR BRANCH

A	FURNISHING WORKS				
Sr. No.	Particulars	Qty.	Unit	Rate	Amount
1	Providing & fixing False Ceiling at 9'-0" Ht. (as per drg.) of india Gyp sum Ltd. (GMFSC-4.1) using 12.5 mm thick Gyp board, paper tape, jointing compound, G.I. Section marked "Gyp steel to be placed at 4'-0" C/C in one direction and at 1'-6" C/C in other direction. The false ceiling shall be finished properly after cutting / making holes for fixing light fixtures including three coats of oil bound distemper paint etc. complete as per Drgs.	830	Sqft.		
ii	Making Cove in Gypsum Board Ceiling	80	rft		
iii	PPGI Metal sheet False Ceiling: Providing & fixing in position False Ceiling in Armstrong 600x600mm PPGI Metal micro look lay-in standard perforated tiles silhouette 38 made of 120 gsm pre-painted galvanized iron, grade-GPL as per IS277 (2018) with coating durability as per IS 4246 color as approved by Bank/architect with 15mm exposed grid system (Grid frame shall have black groove at bottom) by Armstrong Co. with suspenders. Making necessary framework for A.C. ducting, if any, and necessary cutouts for diffusers an light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A.C. Unit:	580	Sqft.		
2	Toughened Glass Doors & Partition for entry) Providing & fixing 12mm thick toughened glass for door and fixed glazing, with complete patch fittings, such as the job shall also include etching design/film.				
i	Entrance glass	227	Sqft.		
3	Providing and fixing Aluminum frame partition made of internal frame of 1 ½" c/c vertically and horizontally finished with 6mm thick Bison Board /6 mm thick commercial ply on both sides finally finished with 1.00 mm thick laminate on both sides with horizontal grooves. These partitions shall have 5.00 mm thick glass (etching as per design) above 2'-6" ht. or 4'-0" ht. with beading ½"x 1½". The rate of partition shall include providing & fixing door in partition made as per the specifications of partition, but with complete hardware required such as latches, stopper. The low ht. partition shall have rubber -wood /teak -wood gola of size 3"x¾" which shall be polished as per shade reqd.				
3(i)	Low Ht. partitions with 12 mm thick glass.	95	sqft.		
ii	Full Ht. partition with /without 5mm thick glass	418	sqft.		
iii	a) cash -cabin's pts (7'-6" High)	78	sqft.		
iv	b) Cash cabins as well as single window's front ptn. With 12 mm th. Glass	35	sqft.		
v	Partition in Strong room (7'-0" high)	66.5	sqft.		
vi	Rear Partition (In Hilux Calcium Silicate Board) in record room	152.1	sqft.		



vii	Cost of Mortice locks (with handles)	4	No		
viii	Cost of multipurpose locks for storages, drawers etc.	25	No		
ix	Cost of door closers ,	4	No		
x	Cost of floor springs. S.S. handle (18" long) and lock	2	No		
xi	Cost of Knight Latches	1	No		
4 (i)	Providing and fixing Wall Paneling on soft Aluminium Frame sections 1"x2" placed @ 2'-0" C/C horizontally & vertically finishing with 6mm thick commercial ply/Bison board finished with 1.00 mm thick laminate as per design, the paneling shall be closed with 2"x1" teak /nu-wood beading	652	sqft.		
(ii)	Pin - up Board Finished with cotton cloth & rubber wood beading.	30	sqft.		
5	Providing and fixing 3.0mm thick pvdf coated Exterior grade A.C.P. Sheet - tray type paneling over Anodised Aluminium frame work of size 1'-1/2" x 1'-1/2" @ 2'-0" c/c bothways. including openable shutter where required. the work shall include the cost of all necessary hardware e.g m.s hinges. magnetic catcher, aluminium tower bolts-6" long long etc.,	140	sqft.		
6(i)	Banking (Cerical) Counters with 1½" thick post-form factory made tops: Providing & fixing Banking Counters (SW) as per design, 2'-6" ht. & 3'-3" ht. (2heights). The banking counters shall have the provision to adjust the key board, drawer, storage complete (full length & width) shelf for CPU at bottom and foot rest. the baking counters shall be made of 19mm thick commercial board, with rubber-wood Gola of size 1½"/3/4", which is to be polished as per color scheme. The counter shall be finished externally and internally with 1mm thick laminate of approved shade/colour, handles, magnet catchers, hinges. Inside of drawers, storage cabinet portion shall also be finished with 8mm thick laminate of approved color.	22	rft		
7	Officers Tables with 1½" thick post -form factory made tops: Providing & fixing office tables with /without drawer and storage below of size 2'-4½" (wide or as mentioned, 2'-6" (high) with the provision of key board, with sliding channels of Ebco, complete (full length & width) shell for CPU at bottom and foot rest. The table shall be made of 19 mm thick commercial board: 1mm thick laminate on (inside & outside) with rubber -wood Gola of size 1½" x 3/4" polish , side golas etc. , with hardware such as hinges, catchers and handles. Inside of tables, drawers, storage cabinets shall be finished with 8mm thick laminate of approved color.	22	rft		
8.i	Side Rack with 1½" thick post form factory made Tops: Providing and fixing side rack, 2-3" ht. as per design. These racks shall have two drawers with storage below and be made of 19 mm thick commercial board: 1mm thick laminate (inside & outside) with rubber-wood gola of size 1½"x 3/4" polish , side golas handles, catchers, hinges etc. inside of drawers storage cabinet portion shall also be finished iwth 8 mm thick laminate of approved color.	3.5	rft		
ii	Storage with 1½" thick post-form factory made tops: Providing & fixing storage along wall 1'-6" made of 19mm th. Comm. Board 1mm th. Laminate, (inside & outside) complete finished with golas/margins, handles, hinges and catchers, front operable shutters, as per requirements /design/drg. Inside of drawers, storage cabinet portion shall also be finished with 8mm thick laminate of approved color.	62	sft		
iii	Providing & fixing G.I. sheet on backside of storage cabinets.	62	sqft.		

9	Cash Counters with 1½" thick post-form factory made Tops: Providing & Fixing cash -counters 2'-9" wide, with two levels i.e. 2'-6" & 4'-0" ht. The lower portions top & all other exposed surface shall have 1mm thick laminate (inside & outside) and golas /margins. The lower portion on cashier side there will be provision of 3 nos. drawers with sliding channels of Ebco. for cash , stationery, key board, etc. rubber wood beading/gola etc. inside of drawers, storage cabinet portion shall also be finished with 8mm thick laminate of approved color.	5	Rft		
10	Manager Table with 1½" thck post-form factory made Tops: Providing & fixing branch manager table 2'-6" ht. with rubber wood gola of size 1½" x 3/4" as per drgs. Having drawers, storage cabinet key board, with sliding channels of Ebco, foot rest, space for CPU & monitor, all as per drg. /design, the table shall be made with 19mm thick comm. board finished with 1mm thick laminate (inside & outside) hardware, such as handles, catchers, hinges etc. shall be provided as per requirement. Inside of drawers, storage cabinet portion shall also be finished with 8mm thick laminate of approved color.	6	Rft		
11	Providing & fixing writing stand of size 3'-0" x 1'-0" x 1'-7½" high (face area) as per design drg. Made of 19mm th. Comm. Board, 1mm th. Laminate with rubber wood lipping etc.	3	Rft		
12(i)	Providing & fixing notice board of size 2'-6"x 4'-0" finished with ivory colour 1mm th. Laminate , 1"x1" th rubber wood beading on all sides.	1	No		
(ii)	Providing & fixing soft board of size 3'-6" x 2'-0" (covered with operable glass shutters) on 10mm th . Comm. Ply 12mm th. Soft board finished with cotton fabric , 1"x2" rubber wood lipping etc.	1	No		
13	Providing & fixing cheque drop box and complaint box of size 18" x 27" as per detail.	1	No		
14	Painting work on walls & cemented ceiling (in ground floor) with oil bound distemper paint.	Landlord			
15	Providing & laying Texture Paint.	409.2	sqft.		
16	Providing & fixing vertical blinds of vista /Mac of approved shade / colour.	0	sqft.		
17	Providing & supplying dressing table with mirror of size 1'-0"x5'-0" including sitting desk for lockers room.	1	No		
18	Providing & supplying small tables /stools 18"x18" made of hard wood frames and having top made of 19mm th. Commercial board/ply and finished with 1mm th laminate , painting polishing complete.	1	Nos		
19	Providing & supplying wooden planters made of 19mm th commerical board nad finished with 1mm th. Laminate internally and externally.	2	Nos		
20	UCO Bank LOGO: Providing , making to shape and size (as per the design provided) and fixing to position UCO Bank logo made out ACP/Acrylic sheet of bank color (preapproved) fixed to position with aluminium framework with required screws, nutts bolts and hooks etc. of size 2'-0"x2'-0" including outer frame finished with teak wood vinear ply with cove for lighting as LED, strip, below logo, the bank's name shall be written in golden /orange ACP sheet letters as per design.	8	sqft.		

21	Providing and fixing golden coloured 12"x12" beveled mirror wall panel on base frame of alumn. Sections & 9mm thick base ply as per design including cove & laminate finish on sides of the frame.	6	sq.ft.		
22	Acrylic Emulsion Paint: Providing and applying with brush, roller Acrylic Emulsion paint to walls, ceiling, etc.in two or more coats of approved paint over necessary putty work, sand papering, primer, scaffolding etc. complete. Old paint shall be removed, scraped, cleaned and coat of water resistant chemical applied where dampness / Seepage is observed as found necessary and as directed by the Bank or its Architect.	910	sq.ft.		
23	Enamel Paint: Providing and applying oil paint with two or more coats of synthetic enamel paint with spray gun and / or brush and roller over necessary putty work, sand papering, primer etc. Old paint shall be removed, scraped, cleaned and coat of water resistant applied where dampness / Seepage is observed as found necessary and as directed by the Bank or its Architect.	300	sq.ft.		
24	Fire Door				
	Door to System room - Fire rated steel door including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC. a). Frame - Providing and Refixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) all-round the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fasteners). b)Shutter - Providing and refixing Metal Door Shutter 46 mm thk. made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge, with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make, provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge. The work includes providing and fixing following hardware for fixing to above door Hinges 4 X 3 X 3 (Min. 3Nos), Pull Handle 19 X 250mm -Pair, Dead Lock,(GODREJ Night Latch Lock) Fasteners Hilti 10 X 92mm - (Min - 10Nos.)	17.5	sq.ft.		



25	Providing and fixing at site Aluminium Partition for the electrical panel as per the design and drawing. The carcass frame shall be made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections , and clad with cemented board 6 mm thick on one side. All stiles and rails for the openable shutters shall be made of 83 mm X 40 mm X 16 Gauge aluminium extruded sections and clad with cemented board 6 mm thick .The shutters shall be mounted on the hinges .The cabinet shall be complete with all necessary hardware like locks, handles, catchers, tower bolts etc. The cemented board shall be finished with 2 coats of primer putty filling to desired smoothness and finished with two coats of plastic paint of desired shade and colour on all internal surface. All the outer visible surface shall be finished with 1.0 mm thick laminate of approved color and shade using the recommended adhesive.	32	sq.ft.		
	Sub Total				
	LESS CREDIT FOR OLD MATERIAL				
26	iii) buy back of old material from existing branch premises(inclusive of Aluminum glazed partition,gypsum board and grid ceiling, wooden tables, furniture etc.etc. the contractor shall visit the existing premises of branch to get a fair evaluation of all the existing material for buy back in his own interest . the rates are inclusive of labour for dismantling , cartage and any other charges as may be incurred on removal of existing material from site	1	job		
27	Removal of malba , debris during the progress of work so as to allow smooth functioning of branch during the course of work to maintain cleanliness in branch during renovation period	1	job		
	Sub Total				



Sr. No.	Description	Qty.	Unit	Rate	Amount
B	Electrical works				
1	Providing & fixing 2'-0" x 2'-0" recessed /or panel model mounted LED Luminaire LCTLR-36-CDL of Crompton.	19	No		
2 (i)	Providing & fixing 15W LED Round Downlighter LCND-15-CDL of Crompton.	32	No		
(ii)	Providing & fixing LED tube lights 1x 20W of Philips.	6	No		
3 (i)	Providing & fixing Wall Fans: Kaitan/Crompton Greaves/Orient.	6	No		
(ii)	Exhaust Fans 12" Dia: 1400 rpm (Double ball bearing) Heavy duty crompton Greaves/Philips.	3	No		
(iii)	Providing & Fixing Ceiling Fans: Khaitan /Crompton Greaves/Orient 4'-0" dia.	1	No		
(iv)	Cost of modular regulators of Havells /Anchor ROMA makes:	1	No		
(v)	Supply Installation, testing & commissioning of LED Strip Light with driver and Accessories complete as required (MS Crompton or equivalent of Wipro, Phillips, Bajaj etc. White Cat 38389 (M/S Philips)	0	Mtr.		
4	Electrical Point wiring:				
a)	Providing laying, fixing & testing of electrical points including 2 x 1.5 sqmm wiring from MCB's to switches, plate type switches, socket & M.S. Modular boxes with rust proof treatment size to accommodate the required nos. of Switches & sockets plus circuit wiring (2 x 2.5 sq mm) from switches to lights /fan/fixtures etc. wherever required complete with earthing wire 1sq.mm- multi strand wire in 25mm dia. Unbreakable PVC conduit ISI marked with specials under floor /wall & above false ceiling or making truff under /along work stations including chase cutting, disposal fo melba away from the site and repair of the same with cement mortar, copper conductor wires only will be used of approved make:	50	No		
b)	Electrical wiring for Air-Conditioning: Providing & fixing air-conditioning wiring from D/B to site of indoor AC unit, indoor to outdoor units i.e. circuit wiring with 2 x 4 sq mm + 1 x 2.5 sq mm earth wire mm sq. multi -strand PVC copper wire, including earth wire including 32 A metal clad socket with MCB.	5	No		
(c)	Air-Conditioning control cable (AC indoor unit to outdoor unit): Providing & fixing air-conditioning wiring from D/B to site of outdoor and indoor AC unit, indoor to outdoor units i.e. circuit wiring with 4 x2.5 sq mm + 1 x 2.5 sq mm earth wire mm sq. multi -strand PVC copper wire, including earth wire including metal clab socket with MCB.	80	metre		
c)	Electrical wiring for UPS (Charging point for UPS): P/F 2 x 4mm sq. mm and 1 x 1.5 sq.mm as earth wire multi strand PVC copper wires from D/B to the location of UPS room for input to UPS in PVC pipe with 32A DP's or 15 AMP. Power plugs and sockets (2 sets: one for input and the other for output).	2	No		
d)	15 Amp wiring with 2 x2.5 sq.mm + 1 x 1.5 sq.mm multi strand PVC copper wire & metal clad enclosure sockets & plugs.	7	No		



e)	5 Amp plug point wiring with 2 x 1.5 mm + 1 x 1.0 sq.mm as earth wire , multi stand PVC copper wire inc. plate switches, sockets, plugs. Etc.	8	No		
f)	Call -bell point wiring including Ding-dong bell with 2x1.0 sq.mm multi strand PVC copper wire including plate switches, sockets, etc.	1	No		
g)	Wall fan points with 3-pin socket and switch, lights & exhaust fan point wiring with 2x 1. sq.mm +1 x 1.0 sq mm earth wire from D/B to switches & fittings multi strand PVC copper wire including plate switches, sockets, etc. (For payment no. of switches shall be counted).	6	No		
h)	Signage wiring (material & labour) P& F of 3x4mm & copper (flexible wire & PVC conduign of ISI make complete with all accessories like saddles, bends modular switches etc.	1	No		
5	UPS POINT WIRING :Supply all materials receiving, storing, handling, fixing & laying of 3 x 2.5 Sq.mm. PVC insulated copper conductor armoured cable and fixing of cable on wall with suitable size of clamps / saddles or laid in floor or recess wall including cutting of floor / wall for computer points with suitable size GI box with modular plate and cover in front including providing and fixing 3 No. 5 amp 3 pin modular socket controlled by 1 No. 5 amp modular switch with indicator , including making connections, end terminations with suitable size of glands etc. complete as reqd.(On UPS Power)	14	Set		
6.i	GEL TYPE CHEMICAL EARTHING (Distance between earth pit shall be min 1.5 meter) Supplying and installation of copper electrode 50 mm dia , Gel Earthing station having length 3000 mm including bore-well, chamber with cover and all required allied civil works . each earth pit to filled with 2 bags in 30 kg pack of "Black -Fill Compound" (BFC)	2	No		
ii	EARTHING CONDUCTORS: Wiring with 1x 4 sqmm PVC insultated copper conductor wrie of 650/1100 volts grade (Finolex make flame guard quality) as earth wire with concealed /exposed PVC pipe including making all the connections.	60	metre		
7	Providing and fixing of PVC conduit in wall floor including Telephone wire, M.S. Box and two pin telephone sockets or R.J. -11 plates out let incl. testign and commissioning etc. as required.	6	No		
	Communication and Networking				
8(i)	Providing , laying , tsting and commissioning data point complete with CAT-6 / Cucent /D-link computer networking cable in PVC conduit in floor or wall from server room to each tableincluding the cost of I.O.'s (Socket) rj-11/rj-45 connectors and SURFACE MPOUNTED PVC GANG BOX	10	No		
8(II)	PAROVIDINGCAT -6 PATCH CABLES				
	(a) 1 mtr. long	10	No		
	(b) 2 mtr. long	8	no		
9	Installation, testing and commissioning of 24-port unmanaged switch 10/100 (DGS-1024 C) full duplex complete as reqd.	1	Bank supply		

10	SUPPLY, Installation, testing and commissioning of 24-port Patch Panel	1	no.		
11	Supply Installation, testing and commissioning of mounted rack 15" height made of powder coated MS sheet for dismantling & re-fixing)	1	no.		
	Main Electrical Panel				
12	Elect D/B with all internal connections for electrical and genrator connections with 10 sq.mm multi strand copper wire, which shall include the followign items.	1	L.S.		
(i)	Amp Meter and voltment set	1	Set		
(ii)	Kit-Kats 100 Amp. With neutral link.	3	No		
(iii)	Neutral link.	1	No		
(iv)	Aluminum bus bar 100 Amp proper tinned.	1	No		
(v)	100 Amp Main switch MCCB type.	1	No		
(vi)	Change over switch 63 Amp. 3-Phase of Havells make:	1	No		
(vii)	providing and fixing different ratedSP MCB,s (6-32 amp) for lights, fans, and power supply of Havells make:	24	No		
(viii)	Providing and fixing TPN MCCB (tripping type) of 100 Amp of havells make: (one for lights and one for power supply)	2	No		
(ix)	Making double -door power coated M.S. Distribution board 3'x4' to accommodate the above noted electrical items.	12	sqft.		
(x)	P/F 3 phase 4-way D/B (Quote the cost of Box only)	2	Nos		
	UPS SUPPLY				
(xi)	Providing and fixing different rated (MCB type) DP MCB 63 Amp of Havells make for UPS supply:	8	No		
(xii)	Providing and fixing 6-32a MCB's for UPS supply of Havells make:	10	No		
(xiii)	P/F single phase 8-way & 6- way D/Bs (Quote the cost of Box only) for UPS supply for MCB's	2	No		
12	Making double -door wooden laminated electrical almirah 3'x8' to accommodate the above noted electrical items.	40	sqft.		
13 (i)	Providing & fixing main electrical cable (from elect. Pole to meter) : 4 core 35 sqmm mm armored aluminium conductor cable	20	Mtr.		
(ii)	P/F 4- core 16mm armoured Aluminium conductor Cable (from genset to panel)	30	Mtr.		
(iii)	Providing and fixing 4-core 16 sq. mm flexible pvc insulated Aluminium conductor Cable from bus bar to ATM.	3	Mtr.		
14	Connectivity for the VSAT/leaselines (Matrial & labour) P&F of 40 mm PVC conduit of ISI make including data cable of D-link & RJ-45, complete for connectivity.	2	No.		
15	Providing , fixing testing and commissioning computers 24-Ports networking switch with racks	1	lusum		

16(i)	P/L copper pipe (1/2" , 1/4" dia) with complete insulation required for 1.5 Ton split type A.C's from the place of external units upto the location of inside units.	80	Mtr.		
(ii)	Providing and laying 25mm dia. PVC pipe heavy duty Diplast make for drainage of water of inside units.	25	Mtr.		
	Sub Total				
	LESS Credit For Old Material				
17	Less buy-back of old material e.g. Old DB,Electrical and UPS panels,wires,cables,light fixtures etc in consultation with Branch Manager. the rates are inclusive of labour for dismantling , cartage and ony other charges as may be incurred on removal of existing material from site.	1	job		
18	providing temporary connections (electrical and data cabling) including wiring, switches, pvc conduits etc. during the duration of the work as per required by branch for smooth functioning of branch during renovation	1	job		
	Sub Total				



C	ATM (Furnishing Works)	Qty.	Unit	Rate	Amount
1	Providing & fixing in position false ceiling in Armstrong 600x600mm x 15/16 mm Dune Supreme RH 99 Prima tile as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A.C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A.C unit in 18 mm thick M.R. grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edoes, if any including finishign with white Plastic emulsion paint etc. complete in all respects.	40	sqft.		
2	Toughened Glass Doors, Fixed Glass & Partition: Providing & fixing 12 mm thick toughened glass for door and fixed glazing, with complete patch fittings such as floor spring, handles, lock and L-brackets etc. the job shall also include etchign design.	24	sqft.		
3	Providing & fixing wall paneling on soft Alum. Frame sections 1"x2" placed @2'-0" C/C horizontally & vertically @ 1'-0" C/C finished with 6mm thick commerical ply/Bison board finished with 1.00 mm thick laminate as per design, the panelign shall be closed with 2" x 1" rubber /teak /nu-wood beading		sqft.		
4	Providing and fixing Aluminum frame partition made of internal frame of 1½ " x 2.5" Alum. Sections. Placed at 2'-0" C/C vertically and horizontally finished with 6mm thick Bison Board/commerical ply on both sides finally finished with 1.00 mm thick laminate on both sides with horizontal grooves. These partitios shall have 5.00 mm thick glass (etching as per design) above 2'-6" ht. or 4'-0" ht iwth beading 1/2"x1 1/2" The rate of partition shall include providing & fixing door in partitios made as per the specifcations of partition, but with complete harware required such as latches, stopper. The low ht. partition shall have rubber -wood /teak wood gola of size 3"x3/4" which shall be polished as per shade reqd. (Full Ht. partition with /without 5mm thick glass)	36	sqft.		
5	Providing and fixing 3.0mm thick pvdf coated Interior grade ACP. Sheet - tray type paneling over Anodised Aluminium frame work of size 1'-1/ 2" x 1-1/2" @ 2'-0" c/c bothways. including openable shutter where required.the work shall include the cost of all necessary hardware e.g m.s hinges. magnetic catcher,aluminium tower bolts-6" long long etc.,	160	sqft.		
6	Grouting of ATM Machines with Anchor fastener as per Bank's rules, (including the cost of RCC 12" slab.	0	No		
7	Providing and fixing Flooring with vitrified tiles joint free of minimum 9mm thickness , size 24" x 24" 4" Skirting, all fixed in 1:5 cement mortar complete with cutting and filling joints with white cement make of tiles Johnson /bell /euro /asian /nitco/naveen /somani or equivaletn. Ivory /shade or as specified by the bank:	0	sqft.		
8	P/F cheque drop box-cum writing top having 12mm th glass top.	1	No		
9	P/F acrylic notice board of size 2'x3' with chrome spacers.	1	No		
10	Providing and supplying plastic dust bin and chair	0	Set		

11	P/F Aircon louvers power coated of size 12" long.	2	sqft.		
12	Painting work on walls & cemented ceiling , rolling shutters with oil bound distemper paint/ enamel paint , external walls are to be painted with snowcem with complete preparation of surface with wall putty, grinding.	80	Job		
	Sub Total				
D	Electrical works for ATM:				
S.No.	Description	Qty.	Unit	Rate	Amount
1	P/F air-conditioning & signage wirign from D/B to site of outdoor and indoor AC unit, indoor to outdoor units, i.e. circuit wirign with 4mm sq. multi strand PVC copper wire, including earth wire including metal clad socket with mcb.	2	No		
2	Connectivity from server/dish Antenna: P& F of 40 mm PVC conduit of ISI make including data cable of D-link (Cat-VI) & RJ-45 , complete for connectivity, (to be concealed with openable and lockable box)	3	No		
3	Providing & fixing 2'x2' recessed mounted LED Aura I-LCPL-36 CDL (2x2) of crompton.	1	No		
4	Providing & fixing 15 W LED round downligher LCND-5 CDL of Crompton.	2	No		
5	Providing & fixing ordinary tube lights 1x40 W of philips.	1	No		
6	GEL TYPE CHEMICAL EARTHING: (Distance between each pit shall be min 1.5 meter supplying and installation of copper Gel Earthing station having length 3000 mm including bore-well, chamber with cover and all required civil allied work each earth pit to field with 2 bags in 30 kg pack of "Black-Fill Compound" (BFC) Earthing Conductors: Wiring with 1x10 sqmm PVC insulated copper conductor wire of 650/1100 volts grade (Finolex make flame guard quality) as earth wire with concealed /exposed PVC pipe including making all the connections.	0	No		
7	Lights point wiring from UPS /raw power supply with 1.5 mm sq. from D/B to switches & fittings multi strand PVC copper wire including plate switches, sockets, etc. (For payment no. of switches shall be counted).	3	No		
8	Electrical wiring for UPS input -output: SITC of 2 no. 32 Amp DP MCB's From D/B to the location of UPS room , icluding wiring with 2 x 4 sq. mm +1 x1.5 sq. mm (for earhing) multi strand PVC copper wires	2	No		
9	UPS POINT WIRING : Supply all materials receiving, storing, handling, fixing & laying of 3 x 2.5 Sq.mm. PVC insulated copper conductor armoured cable and fixing of cable on wall with suitable size of clamps / saddles or laid in floor or recess wall including cutting of floor / wall for computer points with suitable size GI box with modular plate and cover in front including providing and fixing 2 Nos. 15 A 5 pin socket controlled by 1 no 15 A switch and indicator.connection end terminations with suitable size of glands etc. complete as reqd. (On UPS Power) (U.P.S and Data Points are to be provided in lock and key arrangement) ,	3	sets		

10	15 Amp wiring with 2.5 mm sq. multi strand PVC copper wire & metal clad enclosure sockets & plus.	1	No		
11	5 Amp plug point wiring with 1.5 mm sq. multi stand PVC copper wire inc. Plate switches, sockets, plugs. Etc.	1	No		
12	P/L copper pipe (1/2" , 1/4" DIA)with complete insulation required for 1.5 ton split type A.C.s from the place of external units upto the location of inside units.	10	Mtr		
13	Providing and laying 25mm dia. PVC pipe heavy duty Diplast make for drainage of water of inside units.	5	Mtr		
14	Supply, erection and commissioning of timer switch 240-volt single phase for AC & Glow sign Board.	1	No		
15(i)	P/F raw power D/B ((8way S/P DB: 1-40ADP MCB , 6- 6-32 A SPMCB's)	1	No		
ii	P/F UPS power D/B (4way S/P DB : 1-40A DP MCB , 2- 6-32 A SP MCB's)	1	No		
16	Providing and fixing 3-core 16 sq mm cable flexible pvc insulated aluminum conductor cable from main panel to the DB of ATM	0	RMT		
	Total				
	SUMMARY				
1	Furnishing Works of Branch				
2	Electrical Works of Branch				
	Electrical & Furnishing Works of Branch				
3	Furnishing Works of ATM				
4	Electrical Works of ATM				
	SUB TOTAL				
	NET TOTAL				
	GST @18% is Extra on above Rates				

