



संदर्भ संख्या /Ref. No: ZO/HGLY/GAD/MISC/2024-25/ 01

दिनांक /Date- 27/05/2024

To,
Furnishing Contractors, B Category,
(Empanelled by Head Office , 01/09/2022 to 31/08/2025).


Sir,

Sub: Invitation of sealed tender for Internal Furnishing Work of Mayapur Branch.

We invite **Sealed Tender** for Internal Furnishing work of **Mayapur Branch** whose tender document is enclosed.

Last date of submission -18/06/2024 till 1:00 pm
Date of opening of tender -19/06/2024 at 12:00 noon

Regards,


उप अंचल प्रमुख / Deputy Zonal Head
हुगली अंचल कार्यालय / Hooghly Zonal Office



BOQ FOR FURNISHING WORKS AT MAYAPUR BRANCH & ATM, UCO BANK

SI No.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Full Height Glazed Partition				
	Providing and fixing in position full height glazed partition 65 mm thk. solid upto 900 mm. & glazed upto 2100 mm. lev. with 6 mm. thk. non toughened clear float glass with aproved quality and pattern as indicated in the drawing excluding the door made out of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make or wooden section (sal/ kapoor) as internal framed structure placed horizontally & vertically in 600mm x 600 mm center to center or as directed by the Architect. The alternate corner vertical members of the partition shall be taken upto the ceiling level and the same shall be anchored to the ceiling securely with help of suitable cleats. Framework shall be fixed with 6 mm thick marine grade ply (IS - 710) of approved make on both sides finished as per following specifications. The Partition shall be finished with 1.0 mm thick laminate. The item does not include the doors.	sq. ft.	160.00		
2	Full Height Solid Partition				
	Providing and fixing in position full height solid partition 65 mm thk. as indicated in the drawing excluding the door made out of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make or wooden section (sal/ kapoor) as internal framed structure placed horizontally & vertically in 550 mm x 550 mm / 600mm x 600 mm center to center or as directed by the Architect. The alternate corner vertical members of the partition shall be taken upto the ceiling level (payment shall be made for the partition measured below the false ceiling level) and the same shall be anchored to the ceiling securely with help of suitable cleats. Framework shall be fixed with 6 mm thick marine grade ply (IS - 710) of approved make on both sides finished as per following specifications. The Partition shall be finished with 1.0 mm thick laminate. The item does not include the doors.	sq. ft.	250.00		
2	7' Height Solid Partition				
	Providing and fixing in position 7' height solid partition 65 mm thk. as indicated in the drawing excluding the door made out of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make or wooden section (sal/ kapoor) as internal framed structure placed horizontally & vertically in 550 mm x 550 mm / 600mm x 600 mm center to center or as directed by the Architect. The alternate corner vertical members of the partition shall be taken upto the ceiling level and the same shall be anchored to the ceiling securely with help of suitable cleats. Framework shall be fixed with 6 mm thick marine grade ply (IS - 710) of approved make on both sides finished as per following specifications. The Partition shall be finished with 1.0 mm thick laminate. The item does not include the doors.	sq. ft.	270.00		
5	Low Height Solid Partition				
	Providing & Fixing double skin low ht. partition (1200 mm. high) with electrical wire management system, 1200 mm. solid, made out of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make or wooden section (sal/ kapoor) as internal framed structure spaced not more than 600 mm. c/c bothways, double skin partition fixed to aluminium frame made of 6 mm. thk. approved marine grade ply (IS:710), finished both side with approved laminate.	sq. ft.	50.00		
5	Low Height Glazed Partition				

Sl No.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing & Fixing double skin low ht. glazed partition (1200 mm. high) with electrical wire management system, 900 mm. solid, then 300 mm. partly glazed (as per drawing), made out of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make or wooden section (sal/ kapoor) as internal framed structure spaced not more than 600 mm. c/c bothways, double skin partition fixed to aluminium frame made of 6 mm. thk. approved marine grade ply (IS:710), finished both side with approved laminate.	sq. ft.	30.00		
6	Solid Core Flush Door Shutter				
	Providing and fixing Solid Core Flush Door Shutter (IS - 2202) of 35 mm thk. finished both side with 1 mm thk. approved colour laminate (IS : 2046) with 1.5 mm. groove design to be fixed to 65 x 75 mm. Wooden frame. One vision panel of size 6"x 10" made out of 6 mm thk. Clear glass with moulding with polished edge to be provided. The rate shall be inclusive of fitting and fixing of hinges, 1 no. Godrej make door closer, 1 no. CP finish door stopper, screws, 1 no. Godrej cylindrical lock, tower bolt of approved make. All edges of the door to be covered with necessary lipping with polish finish. The work should be completed as per specification, design and approval of Architect.				
	Shutter size : 900 mm. x 2100 mm. and above, as per site condition, including vision panel of 6 mm. thk. Glass (600 x 1050 mm.)	sq. ft.	63.00		
	Shutter size : 900 mm. x 2100 mm. including vision panel of 6 mm. thk. Glass (125 x 200 mm.) (optional)	sq. ft.	21.00		
7	Toughened Glass Door				
	Providing & Fixing frameless fully glazed 12 mm. clear Toughened Glass Door (in one / two shutter) with floor mounted pivotted door spring hinges (similar to Godrej D120) to shutters fitted with patch fittings & floors with plate & screws including cutting holes & mending good with cement mortar. Edge of glass to be polished as directed. Shutter to be fitted with 30 mm. dia. 100 mm. X 600 / 900 mm. long stainless pair of 'C' handles (both inside & outside) with all accessories complete as per design & direction. (Location : Branch)				
	Shutter size : 900 mm. x 2100 mm. with 100 mm. x 900 mm. long 'C' handles at Main entrance of the premises, Branch , ATM	sq. ft.	66.00		
9	Full / Low Height Storage cabinet				
	Providing and fixing full / low height storage cabinet 400 mm depth and 900/ 2400 mm high made out of 19mm thick marine grade plywood (IS - 710) of approved make including the fixing of shelves at 400 mm to 425 mm c/c and the shutters shall be in 19 mm thick BWP block board or MDF board and back covered with 6 mm marine grade plywood. The Top surface will be of Modular 25mm thk. ply postform bull nose top with proper edge binder of matching colour. The shutters shall be fixed with S type "L" hinges of approved make so as to get an equal 8 mm groove between all the shutters at the opening and hinged end of every shutter as per the detailed drawing. Shutter shall be fixed with SS chain from inside so as to open the shutter less than 90 degree and to avoid the breaking of laminate at the hinged end. Shutter shall be finished externally with approved quality 1.0 mm thick. laminate of approved shade of frosty white as approved and make and all internal surface would be finished with 0.8 mm thick. balancing white laminate. Rate shall be inclusive of provision of SS "D" type handles 4" or 6" as approved, Godrej locks with 3 keys and all the necessary hardware, fixtures, fittings etc complete in all respects as directed by the Architect.	sq. ft.	100.00		
10	Cash Counter Cabin				

SI No.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Supplying ,fitting and fixing of Cash Counter Cabin (1400 mm. x 2200 mm. x 1650 mm. high) with 65 mm. thk double skin laminated glazed partion at 2 sides & back, with 6 mm BWR ply (IS : 710), 1mm thk laminate of approved make & shade & 6 mm. thk. glass including 1 no. door frame & 35 mm. thk. flush shutter at back partition of each counter. At front, the total ht. will be 1650 mm., upto 750 mm. with working counter and rest with 12 mm thk toughened glass with necesary slit & hole for operation. Locking system of the door would be a Godrej Mortice lock fixed at 900 mm. level. Counter of 900 mm. wide to be made with 19 mm. thk. block board to be completed with drawer unit (3 drawers), keyboard tray, foot rest, cpu trolley etc. as per architects dwg. Rates to be quoted for each counter as per architectural drawing.	unit	2.00		
2	Cash Cage Side Partition				
	Providing and fixing in position Cash Cage Side Partition 65 mm thk. as indicated in the drawing excluding the door made out of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make or wooden section (sal/ kapoor) as internal framed structure placed horizontally & vertically in 550 mm x 550 mm / 600mm x 600 mm center to center or as directed by the Architect. The alternate corner vertical members of the partition shall be taken upto the ceiling level and the same shall be anchored to the ceiling securely with help of suitable cleats. Framework shall be fixed with 6 mm thick marine grade ply (IS - 710) of approved make on both sides finished as per following specifications. The Partition shall be finished with 1.0 mm thick laminate. The item does not include the doors.	sq. ft.	210.00		
11	Gypsum false ceiling				
	Providing and fixing Gypsum false ceiling which includes G.I perimeter channels of size 0.55mm thk. (having one flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling,screw fixed to brick wall/partition with the help of nylon sleeves and screws, at 610mm centres. Then suspending G.I intermediate channels of size 45mm (0.9mm thk. with two flanges of 15mm each) from the soffit at 1220mm centres with flanges of 26mm each with lips of 10.5 mm are then fixed to the intermediate channel with the help of connecting clip and in direction perpendicular to the intermediated channel at 457mm centres.12.5mm tapered edge Gypboard (confirming to IS: 2095 - 1982) is then screw fixed to ceiling section with 25mm drywall screws at 230mm centers. Screw fixing is to be done mechanically either with screw driver or drilling machine with suitable attachment. The boards are to be jointed and and finished so as to have a flush look which includes filling and finishing the tapered and square edges of the boards with jointing compound. No extra payment will be made for the cutting of tight points , stain glass,cove lighting etc. The measurement will be taken in one level, rate should include the drops also, no extra amount will be paid for the drops. The joints to be properly mended with paper tapes and gypsum compound,two coats of Drywall Top Coat all complete. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work to be completed as per specification,drawing and approval of the Architect.	sq. ft.	368.00		
12	Moduler false ceiling				

SI No.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing , fabricating and erecting lay in type tegular or drop type Modular False Ceiling (ARMSTRONG make) of 600 x 600 mm. grid. The rate shall include the additional cost of Tee and L supports and other accessories near the ends/ odd size edges/corners. Provide additional length support from the ceiling to the false ceiling grid wherever necessary, making necessary openings for electrical light fittings, alarm detectors and any other fixtures. No extra payment for making openings in the panel/grids for the purpose of light fittings. Item rate shall include all the taxes, transportation, erection, loading and unloading and any other incidental expenditure for completing the work.	sq. ft.	232.00		
13	Free Standing Table				
	Providing & erecting in position free standing table made of 19 mm. thk. Block board for sides & modesty panel, finished with 1 mm. thk. laminate of approved shade & make. The table top to be made with 19 mm thk. block board. 1 no. Drawer cum cabinet unit of approx. overall size of 400 x 600 x 725 mm. (h) of 19 mm. thk. Block board. The drawer unit shall comprise of 1 no. tea tray, 1 drawer, 1 cabinet with inner faces finished with polish / paint. The drawer unit shall be finished with 1 mm. laminate. The quoted price should include cost of CP teak wood moulding to edges, wood lipping, multi locks of Godrej make & other necessary hardware accessories including SS handles, pvc wire manager, 1 no, keyboard tray, 1 no. mobile CPU trolley etc. of approved quality. The inner surface of the drawer unit to be finished with polish / synthetic enamel painted. All table should have a side credenza which shall be 900 mm. long., 400 mm. wide & 750 mm. high with intermediate 1 no. shelf of 19 mm. BB. The side credenza have sliding shutters of 12 mm. thk. ply with 1 mm. thk. laminate finish on visible side. All the ply edges should be lipped & finished with prescribed shade of polish. The rate also include the cost of hardwares like hinges, tower bolts, handles, magnets, wire manager etc.				
a	size : 1800 mm. x 750 mm. x 750 mm.(h) including side credenza of size : 900 mm. x 400 mm. x 750 mm.(h)	unit	1.00		
b	size : 1500 / 1350 mm. x 750 mm. x 750 mm.(h)	unit	1.00		
c	Front Running Counter for Officer size per counter : 1500 mm. x 600 mm. x 750 mm.(h)	Rft.	10.00		
14	Providing & fixing fully glazed 12 mm. thk., 300 mm. high, non-toughened clear float Glass , with polished edge fitted in front of table top vertically keeping 50 mm. gap with counter top. The glass to be fixed with 50 x 50 x 350 mm. high hard wooden post (@1500 mm. c/c apart) finished with 1mm. approved laminate with polished wooden beading. The same partition will continue in between two workstation also having wooden post at the end of the each table top, complete as per design & direction. (for measurement, 350 mm. height will be considered) (Location : Only 1 tables along cash counter)	sq. ft.	21.00		
14	Wall / column panelling				
	Providing & fixing in position wall / column panelling consisting of 6.0 mm thk. marine grade ply IS:710 with aluminium hat furring channel 22-25 @ 500 mm. both direction. The face of the cladding is to be laminated with 1.0 mm. thk. laminate of approved shade & groove design. The ply surface of the groove is to be melamine polish finished of approved colour. The item is to be completed in all respects as per design & approval of the architect.	sq. ft.	380.00		
15	Drop / Suggestion Box				

Sl No.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing and fixing Drop / Suggestion Box (400 x 600 x 150 mm.) made out of 19mm BWR Ply and finished with 1 mm. laminate and enamel painted inside. A 6" long slit is to be made in the front for inserting letters etc. The shutter with necessary locking arrangement & should have a glass panel at bottom. The work should be completed in all respects as per design specification & approval of the architect.	unit	1.00		
16	Writing ledge				
	Providing & fixing writing ledge 900 mm. long x 300 mm. wide x 150 mm. deep, as per design made out of 19mm MDF board with necessary groove patterns 1.0mm laminate. A divider made of 19mm block board to be provided. White beach / white cedar lipping with natural polish to be used in all exposed areas, inside of writing ledge to be enamel painted. Top of ledge will be of 12 mm. thk. float glass. The work to be completed as per design and approval of the architect.	unit	1.00		
17	Main Panel / DB Encasement				
	Providing and fixing Main Panel / DB Encasement in position fabricated out of marine grade ply (IS-710) with 1 mm laminate finished for top, both sides and front with necessary hardware including locks, hinges and handles. Encasement will be having louver and 6mm thk. Glass for seeing the indicator in both shutters. The exposed surface of 19mm block board will be finished with TW / white cedar lipping with natural polish and inside of the encasement shall be finished with Fire proof paint. The item is to be completed in all respect as per design, specification and approval of the Architect.	sq. ft.	50.00		
18	Rolling Shutters Encasement				
	Providing & fixing Rolling Shutters Encasement with 3mm thick (0.5mm + 2 mm + 0.5mm) ACP in approved colours all complete with approved aluminium sub structure, aluminium brackets, silicon sealants, gaskets, PVDF coating in approved colour etc. all complete including bird/ vermin proof closer at the bottom and flashing at top, complete as per instructions & drawings.	sq. ft.	50.00		
18	Wall Panelling with ACP				
	Providing & fixing Wall Panelling with 3mm thick (0.5mm + 2 mm + 0.5mm) ACP in approved colours all complete with approved aluminium sub structure, aluminium brackets, silicon sealants, gaskets, PVDF coating in approved colour etc. all complete including bird/ vermin proof closer at the bottom and flashing at top, complete as per instructions & drawings.	sq. ft.	256.00		
20	Vertical blinds				
	Providing and fixing vertical blinds of 100 mm wide of approved shade and pattern having handrail made of high strength aluminium alloyed with thickness of 1.2 mm thk handrail to have 25mm decorative insert. Control unit shall be of derlin. The runners are also to be a derlin with anti-flick adhesive. Spacers should be made of stainless steel. Fabric should be polyester viscose/polyester yarn having protective coating with chemicals for stain resistance & soil repellency. The rate shall include necessary Scotch guard treatment on both sides. The overlapping should be uniform and adequate. Necessary operative arrangements frames to be provided. The work to be completed as per specification and approval of the Architect.	sq. ft.	120.00		
22	Pin up notice Board				
	Providing, fitting in position 12mm thick pin-up board made of soft cork board finished with the fabric (base rate Rs.240/- metre) as approved, matching with the colour scheme of the banking hall with a R.W. moulding all around the edges.	no.	1.00		
23	Synthetic enamel paint work				

SI No.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing and painting on wooden, steel or plastered surfaces with two coats of Synthetic Enamel paint of approved shade & brand over a coat of primer of approved quality after sand papering the old/new surface to give an even uniform shade.	sq-ft	700.00		
24	Plastic emulsion paint work				
	Emulsion paint [roller finish]: Finishing the wall with plastic emulsion paint of premium quality of approved make conforming to IS: 5411 of two or more coat over a coat of primer to give a smooth and even shade. If depression or hole is on wall, then same shall be rectified by filling with putty, applying a coat of primer and sand papering etc. all complete. The work should executed as per as per manufacturer's recommendations & as directed by EIC. Cost includes all type of material, labour, necessary staging, tools tackles etc Complete	sq-ft	4200.00		
29	WASTE BIN : Supply and Placeing of Waste Bin	No.	5.00		
30	3M GLASS FILM : Providing & Fixing Birla 3M /Lunar make frosted film fixed on the glass after cleaning and wiping glass surfaces free of any dust or foreign boodles and then fixed plain approved pattern / design film on the glass as per detail drawing inclusive making necessary cutouts, carting away unserviceable materials out of compound, cleaning the site etc. complete as per the site requirements and the instructions of the Architect. (Mode Of Measurement - Length X Height)	Sqft.	180.00		
36	CIVIL REPAIRING WORK : Civil work for installation of AC, Laying of wire etc, complete all respect.	Job.	1.00		
37	FLOOR MAT : Supply and Placeing pvc floor mat	No.	2.00		
	TOTAL				