

BOQ OF FURNISHING WORKS FOR UCO BANK - RAJAGRAM BRANCH INCLUDING ATM

SL NO.	PARTICULARS	UNIT	QTY	RATE	AMOUNT
1	FALSE CEILING (Gypboard)				
	Providing and fixing Gypsum false ceiling which includes G.I perimeter channels of size 0.55mm thk.(having one flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling,screw fixed to brick wall/partition with the help of nylon sleeves and screws, at 610mm centres. Then suspending G.I intermediate channels of size 45mm (0.9mm thk. with two flanges of 15mm each) from the soffit at 1220mm centres with ceiling ange of width 25mm x10mmx0.55mm thk.fixed to soffit with G.I. cleat and steel expansion fastners ceiling section of 0.55 mm thk. having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5 mm are then fixed to the intermediate channel with the help of connecting clip and in direction perpendicular to the intermediated channel at 457mm centres.12.5mm tapered edge Gypboard (confirming to IS: 2095 - 1982) is then screw fixed to ceiling section with 25mm drywall screws at 230mm centers.Screw fixing is to be done mechanically either with screw driver or drilling machine with suitable attachment. The boards are to be jointed and and finished so as to have a flush				
	look which includes filling and finishing the tapered and square edges of the boards with jointing compound. No extra payment will be made for the cutting of light points , stain glass,cove lighting etc. The measurement will be taken in one level, rate should include the drops also, no extra amount will be paid for the drops. The joints to be properly mended with paper tapes and gypsum compound,two coats of Drywall Top Coat all complete. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work to be completed as per specification,drawing and approval of the Architect.No Drop or design(if any)will be considered as extra measurement it will be considered flat ceiling.	Sqmt	64		
a)	GRID CEILING				
	Providing and fixing of Armstrong Acoustical Suspended false ceiling system with " Dune Microlook" tiles.The tiles should have humidity resistance of 99% RH, Average NRC 0.50 and STC of 34dB,Light reflectance > 85%, thermal conductivity k = 0.052 - 0.057 W/M K,colour white with the exposed side finished with Crisp finely granulated with microperforations , Fire Performance class 0/ class 1 (BS - 476) in module size of 600mm x 600mm x 16mm, laid with black silhouette 15mm hot dipped galvanised steel suspension system having rotary stitching. To comprise main runners of length 3000 mm width 15mm and web height 35 mm made out of 0.4 mm hot dippeed galvanised steel spaced at 1200 mm centres securely fixed to the structural soffit by approved hangers at 1200 mm maximum centres and not more than 150mm from spliced joints. The last hanger at the end of each main runner should not be greater than 600 mm from the adjacent wall . 1200 mm long cross tees of web height 35mm and made out of 0.4 mm thick galvanised steel to be interlocked between main runners at 600 mm require independent support. 600 x 600 mm modules to be formed by fitting 600 mm long cross tees centrally between the 1200mm cross tees.				

BOQ OF FURNISHING WORKS FOR UCO BANK - RAJAGRAM BRANCH INCLUDING ATM

SL NO.	PARTICULARS	UNIT	QTY	RATE	AMOUNT
	The 1200 mm cross tees to have central "birdsmouth" notches to facilitate fitting of 600 mm cross tees. Perimeter trim to be Armstrong wall angles secured to walls at 450mm maximum centres. False ceiling will be measured on horizontal plane only. Horizontal plane measurements are to be inclusive of all vertical drops, edge mouldings, facias, etc.				
	Rate quoted to include vertical drops up to 150mm and all cut-outs required for light fixtures, smoke detectors and other services cut-outs complete as directed by Architect.				
	Rate quoted to include cost of providing support framework formed of perimeter channels for fixing light fixtures, AC grills/diffusers etc. Also to provide concealed perimeter channel support as required to support modular grid ceiling sections at junction between gypboard false ceiling and modular grid tile ceiling.	Sqmt	18		
2	PARTITION				
	Providing and fixing partition consisting of 2 " x 2" finished sal wood section without sap and joints at maximum 2'-0"C/C both horizontally and vertically treated with Pentapene pale from STP as antitermite & fire retardant from Viper. To be fixed screwed to the floor and ceiling with M.S. cleats. The frame work will be clad with 6mm thk. BWR plywood both sides and finished with 1.0mm thk. approved shade laminate as per design with approved adhesive. In case of Partly glazed and low ht. (4'-0" & 6'-0") partition 8mm thk. Etched/Frosted glass to be provided fixed with 3"x3/4" white beach/teak wood moulding with natural polished all complete. In case of Low ht. partition (4'-0") approved colour soft board should be embedded in partition with white beach/white cedar wooden beading with natural polish. The work to be completed as per specification, design and approval of the Architects.				
	Note: During joint measurement Partition ht. will be considered upto False ceiling level. In event of difference in false ceiling ht. the partition ht. shall be calculated on average ht.				
a	Low ht. Partly Glazed Cash Side's Partition	Sqmt	9		
b	Low ht. Partly Glazed partition with wicket door	Sqmt	2		
c	Low ht. Partly Glazed Cash Rear Partitions including doors	Sqmt	6		
d	Full ht. Partly Glazed Partition (8'-6" ht.)	Sqmt	8		
e	Full Blocked Partition upto true ceiling ht. with both side laminate	Sqmt	50		
f	Full Blocked Partition upto true ceiling ht. with one side laminate one side paint	Sqmt	10		
g	Full ht. Partly Glazed Partition with 12mm toughened glass with etching (8'-6" ht.)	Sqmt	8		
3	12 mm GLASS PARTITION				
	Providing and fixing in position 12mm thk machine polished glass at top of Cash counter front. Necessary 1 1/2" x 1/2" white beech/white cedar moulding with natural polish to be provided. The work to be completed in all respect as per design, direction and approval of Architect.	Sqmt	3		
4	DOORS				
(a)	Full Ht. Partly Glazed / Full Blocked door				

BOQ OF FURNISHING WORKS FOR UCO BANK - RAJAGRAM BRANCH INCLUDING ATM

SL NO.	PARTICULARS	UNIT	QTY	RATE	AMOUNT
	Providing and fixing solid core flush door of 35 mm thk. Finished with 1mm approved colour laminate .A wooden cover moulding of 3"x3/4" thk.white beech /teak wood with natural polish shall be provided for floor spring fitted door .8mm thk.Modi Guard / Saint Gobain clear float glass with etching (approved design) shall be provided with 1 1/2"x3/4" thk. White beech/teak wood glass moulding (as per approved design) with natural polish for full ht. partly glazed door.In case of vision panel door 18"x9" 8mm thk. clear glass with glass moulding with natural polish to be provided. The rate shall be inclusive of Floor Spring (heavy duty),4" brass hinges,door stopper, screws,10" 'H' shape brass handle (Kitch) ,dead lock of Godrej,key hole cover,night latch, tower bolt,door closer of approved make.All edges of the door to be covered with necessary lipping with natural polish.The work should be completed as per specification ,design and approval of Architect.				
	Note: Wooden door frame fixed to the wall shall have 4" x2 1/2" Teak wood / sal wood (seasoned) section with natural polish.The doors fitted with door clousers shall be provided 3" x 1 1/2" white beech / Teak wood section with natural polish for door frame work.				
i)	Entry to UPS, store Room & entry to toilet area with vision panel (2'-6"/3'-0"x7'-0")	No	3		
ii)	Entry door to cash and Teller counter door without etching (2'-3"/3'-0"x 7'-0")	No	3		
iii)	Full Ht. glazed door with etching at Branch head room (3'-0"x7'-0")	No	1		
(b)	FULL HT BLOCKED DOOR WITH DOOR FRAME				
	Providing and fixing solid core flush door of 35 mm thk. Finished with 1mm approved colour laminate .A wooden cover moulding of 3"x3/4" thk.white beech /white ceader with natural polish shall be provided for floor spring fitted door .8mm thk.Modi Guard / Saint Gobain clear float glass with etching (approved design) shall be provided with 1 1/2"x3/4" thk. White beech/white ceader glass moulding (as per approved design) with natural polish for full ht. partly glazed door.In case of vision panel door 18"x9" 8mm thk. clear glass with glass moulding with natural polish to be provided. The rate shall be inclusive of Floor Spring (heavy duty),4" brass hinges,door stopper, screws, 10" 'H' shape brass handle (Kitch) ,dead lock of Godrej,key hole cover,night latch, tower bolt,door closer of approved make.All edges of the door to be covered with necessary lipping with natural polish.The work should be completed as per specification ,design and approval of Architect.				
	Note: Wooden door frame fixed to the wall shall have 4" x2 1/2" white beech / white ceader (seasoned) section with natural polish.The doors fitted with door clousers shall be provided 3" x 1 1/2" white beech / white ceader section with natural polish for door frame work.				
(i)	Size: 3'-0"/2'-6"x7'-0"	Sqmt	2		
5	MAIN ENTRANCE DOOR (3'-6"x7'-0")				

BOQ OF FURNISHING WORKS FOR UCO BANK - RAJAGRAM BRANCH INCLUDING ATM

SL NO.	PARTICULARS	UNIT	QTY	RATE	AMOUNT
	Providing & fixing fully glazed pivoted door at the main entrance consists of 6"x2"seasoned white beach/ Teak wood section for bottom rail and 4"x2" seasoned white beach/teak wood section for top rail finished with natural polish. 12mm thk.Modi Guard /Saint Gobain clear float glass with sand blasting/etching (as per design) and finish handle(1'-0" long)of Neki/Hasseley make to be fixed on both sides & proper locking arrangement in bottom rail to be done. The rate should include lipping,moulding,beading & heavy duty floorspring of approved make.The work to be completed in all respect as per design, direction and approval of the architect.	No	2		
6	TABLE				
	Providing and fixing tables made out of 19mm thk BWR block board for top,sidis and front of approved make cladded with 1.0mm laminate as per design in all visible areas. All the exposed edges to be covered with white beach/teak wooden lippings and table front fascia will have 1 1/2"x 1" mouldings with natural polish. The drawers to be made out of 19mm thk block board for front ,sides to be made out of 12mm BWR plywood and bottom and back to be made out of 6mm BWR plywood and it should play in telescopic drawer sliding channels. The inside of the drawer and the table to be synthetic enamel painted (approved colour) . A legrest to be provided duly painted made out of 19mm thk BWR blockboard. A shutter to be made by 19mm BWR Block board cladded with 1.0mm laminate .The necessary godrej multipurpose locks (brass),brass hinges,4" matt finished handles (brass) of approved make to be provided in each drawers and shutters.On top of the Branch managers table 10mm thk glass to be placed edges duly machine polished.				
	The table should have black powder coated readymade key board tray and tea traywith laminate finish.The necessary wire managers to be provided on the tabs and the provision for lights to be kept if required in the front of table.Readymade metal CPU trolley to be provided every where with a provision of castors to be provided. 3" raised portion made of 19mm BWR b/b finished with 1.0mm laminate and 1 1/2"raised portion made of 19mm BWR b/b finished with 1.0mm approved colour laminate as per design to be provided on table front. All the exposed areas to be duly enamel painted. The work to be completed as per design and approval of the Architect.				
(a)	Branch Manager (6'-0"x3'-0")	No	1		
(b)	Spcl Asst./officers (4'-9"x2'-6")	No	2		
(c)	Officers (5'-0"x2'-6")	No	1		
(d)	WORKSTATION:				

BOQ OF FURNISHING WORKS FOR UCO BANK - RAJAGRAM BRANCH INCLUDING ATM

SL NO.	PARTICULARS	UNIT	QTY	RATE	AMOUNT
	Providing & fixing top, front & sides of workstation made out of 19mm thk. ply and 6mm ply for back cladded with 1.0mm thk. Laminate & the all exposed edges to be finished with t.w. moulding (as per design), lipping with polish.The work station should have individual pedestral unit having drawer & shutter pallah.The front of the drawer made out of 19mm thk. ply finished with 1.0mm thmk. laminate, sides 12mm thk. ply and bottom to be made out of 6mm plywood. The inside of the drawer to be enamel painted. The drawers and shutters to be provided with necessary drawer sliding channels , S/S finish 4" long handles,hinges,locks etc.A leg rest to be provided made out of 19mm thk. BWP block board duly enamel painted. Inside of the workstation to be enamel painted in the matching tone.Wire manager (approved colour),black powder coated redymade CPU trolly and Key board tray , Mouse pad tray finished with 1.0mm laminate to be provided.The work to be completed as per specification and approval of Architects.	Rmt	1.22		
7	CASH COUNTER / TELLER COUNTER (6'-0"/5'-0"x 2'-9") HT. 3'-8"				
	Providing and fixing top, front & sides of cash / SW counter made out of 19mm BWR block board as per design cladded with 1.0mm thk laminate & the expose edges to be finished with necessary white beach or teak wood lippings, mouldings(as per design), etc. Special 6" drawer to be made for the cash /teller with dividers of 12mm BWR plywood .The front of the drawer made out of 19mm BWR block board finished with 1.0mm laminate, sides 12mm BWR plywood and bottom,back to be made of 6mm BWR plywood . The inside and sides of the drawer to be synthetic enamel painted .The drawers and shutters to be provided with necessary drawer sliding channels,4" matt finished handles,brass hinges, godrej multipurpose locks etc. A leg rest to be provided made out of 19mm thk BWR block board duly enamel painted. Inside of the unit to be enamel painted in the matching tone.All visible areas to be coverd with white beach or teak wood lippings, mouldings with natural polish.Wire manager approved colour, legrest,Readymade CPU trolly,black powder coated readymade keyboard tray, tea tray finished with 1.0mm laminate to be provided.				
	6" raised portion made of 19mm BWR b/b finished with 1.0mm laminate and 3"raised portion made of 19mm BWR b/b finished with 1.0mm approved colour laminate as per design to be provided as shown in drawing.The work should be completed as per specification,design and approval of the Architects.	Rmt	3.05		
8	SIDE AND BACK UNIT				

BOQ OF FURNISHING WORKS FOR UCO BANK - RAJAGRAM BRANCH INCLUDING ATM

SL NO.	PARTICULARS	UNIT	QTY	RATE	AMOUNT
	Providing and fixing Side Unit/ Back unit made out of 19mm BWR block board for top, sides and 6mm thk. BWR ply for back finished with 1.0mm laminate . The drawers to be made out of 19mm BWR block board in the front cladded with 1.0mm laminate. sides to be made out of 12mm plywood and bottom,back made out of 6mm plywood and it should play on drawer sliding channels . Drawer and sliding shutters inside to be synthetic enamel painted.The Sliding shutters to be made out of 19mm block board with 1.0mm laminate finished and should play on alluminium channels all four sides. The necessary godrej multipurpose locks,brass hinges ,4"brass matt finished handle,4"brass matt finished sliding handle etc to be provided . Inside of the unit to be synthetic enamel painted in matching tone . All the exposed edges of the boards/plywoods to be coverd with White beach/teak wood lippings/mouldings with natural polished all complete.side and back unit top will have 1 1/2"x1" white beech/teak wood moulding with natural polish at front facia.The work to be completed as per specification,design and approval of the Architects.	Rmt	7		
9	WRITING LEDGE (3'-0" x 1'-0" x 0'-6")				
	Providing and fixing writing ledge as per design made out 19mm block board with necessary groove patterns ,1.0mm laminate to be cladded. 18mm thk.telephone black granite with bull nosed moulding (double) at facia to be provided on top of the writing ledge.A divider made of 19mm thk.block board to be provided. Whit beach/ White ceader lipping with natural polish to be used in all exposed areas. Inside of writing ledge to be enamel painted.The work to be completed as per design and approval of the architect.	No	2		
10	VERTICAL BLINDS				
	Providing and fixing venitian blinds of 100mm thk (Mac/Annums) of approved shade and pattern having handrail made of high strength alluminium alloyed wall thickness of 1.2mm thk. Headrail to have 25mm decorative insert. Control unit shall be ofderlin. The runners are also to be a derlin with antiflixtion adeshive. Spacers should be made of stainless steel. Fabric should be polyester viscoted/polyester yarn having protective coating with chemicals for stain resistance & soil repalancy. The rate shall include necessary scoch gurd treatment on both sides. The overlaping should be uniform and adequate.Necessary operative arrangements,frames to be provided. The work to be completed as per specification and approval of the architect.	Sqmt	10		
11	STORAGE				

BOQ OF FURNISHING WORKS FOR UCO BANK - RAJAGRAM BRANCH INCLUDING ATM

SL NO.	PARTICULARS	UNIT	QTY	RATE	AMOUNT
	Providing and fixing storage made out of 19mm BWR block board for top,sides& 6mm BWR ply for back finished with 1.0mm laminate . The shutters to be made out of 19mm block board with 1.0mm laminate. The necessary godrej multipurpose locks ,6" SS matt finished handles, auto closing hinges etc to be provided . 3" x1/2" white beach/White ceader wooden skirting to be provided duly natural polished as per matching tone. Inside of the unit to be synthetic enamel painted in matching tone . All the exposed edeges of the boards/plywoods to be coverd with white beach/white ceader wooden lippings/1 1/2"x1"mouldings duly natural polished all complete.For full ht. storage file divider made out of 6mm thk ply to be provided.The work to be completed as per approval and specifaion of the Architect.				
a	Full ht storage (deep 1'-6")	Sqmt	12		
12	SOFT BOARD / NOTICE BOARD				
	Providing and fixing soft board /Notice board fabricated out of 12mm BWR ply covered with 12mm soft board padding and upholsply propylene fabric @ 80/mtr. Edges of soft board should have white beach/whiteceader moulding with natural polished.	Sqmt	3		
	Note: Where pin up board is in a panelled area, the top of the pin up board should be flushed with the panel, keeping the same level. The work should be completed as per specification,design&approval of the Architects.				
13	SUGGESTION BOX				
	Providing and fixing suggestion box made out of 19mm block board and finished with 1.0mm thk laminate & inside to be synthetic enamel painted.A 1" high slit & small door with key and locking arrangement to be done for dropping & taking out the slips.The work to be completed as per design,direction & approval of the architect.	No	2		
14	CHEQUE DEPOSIT BOX				
	Providing and fixing cheque deposit box made out of 19mm thk block board & finished with 1.0mm thk. Laminate & inside to be synthetic enamel painted.a 1" high slit & small door with key and locking arrangement to be done for dropping & taking out the slips.The work to be completed as per the design,direction & approval of the architect.	No	2		
15	FIRST AID BOX				
	Providing & fixing in position first aid box made out of 19mm thk. BWR block board finished with 1.0mm thk. Laminate.Inside to be enamel painted.all exposed edges to be covered with white beach/white cedar lipping with natural polish.Necessary hardware like multipurpose lock,brass hinges and handle to be provided.The work to be completed as per the direction & approval of the architect.	No	1		
16	FIXED GLAZING AT ENTRANCE				

BOQ OF FURNISHING WORKS FOR UCO BANK - RAJAGRAM BRANCH INCLUDING ATM

SL NO.	PARTICULARS	UNIT	QTY	RATE	AMOUNT
	Providing and fixing fixed glazing at entrance consist of 6"x2" white beech/white ceader woden section with natural polish for bottom rail and 4"x2" white beech/white ceader section with natural polish for top rail.12mm thk.modi guard/saint gobain glass with etching to be provided . The work is to be completed as per design, direction and approval of the architect.	Sqmt	6		
17	WALL CLADDING				
	Providing & fixing in position wall cladding consisting of 6mm BWR plywood,1.0mm thk. laminate with salwood ribbing of 1 1/2"x 1" dimension. The item is to be completed in all respects as per design,direction & approval of the architect.	Sqmt	18		
18	CORNICE MOULDING				
	Providing and fixing pop cornice moulding along the periferi wherever the walls/partition meeting the ceiling size 3" x 1 1/2" duly painted as per approval of the architect.	Rmt	69		
19	MAIN PANEL ENCASEMENT				
	Providing & Fixing main panel encasement in position fabricated out of 19mm BWP BB with 1.0mm thk. Laminate for top,both sides&front.Encasement will be having powder coated alluminium louver & 6mm thk. Glass for seeing the indicator in both pallahs.The exposed surface of 19mm BWP BB will be finished with white beach/white ceader lipping & inside to be enamel painted . The item to be completed in all respect as per design , direction and approval of the Architects.	Sqmt	4		
20	PILLAR CLADDING				
	Providing & fixing in position column cladding consisting of 6mm BWR plywood,1.0mm thk. laminate with salwood ribbing of 1 1/2"x 1" dimension. The rest of the column is to be painted.oikas paint area as shown in drawings.The pillar cladding will have 19mm block board plank ,1.0mm bi colour laminate as shown in drawings. The item is to be completed in all respects as per design,direction & approval of the architect.	Sqmt	5		
21	ACP SHUTTER BOXING & PANELLING AT MAIN ENTRANCE				

BOQ OF FURNISHING WORKS FOR UCO BANK - RAJAGRAM BRANCH INCLUDING ATM

SL NO.	PARTICULARS	UNIT	QTY	RATE	AMOUNT
	Providing and fixing wall panelling /facia of entrance including shutter cover by 4mm thk. ACP consisting of 1 1/2" x 1" aluminium box section (1.2mmthk) at maximum 2'-0"C/C both horizontally and vertically. To be fixed screwed on the existing walls.The frame work to be claded with Exterior grade 4.0mm ACP sheet (EXOTIC SILVER) of ALU DECOR make with aluminium foil thickness of 0.50 on both sides and 3.0mm thk. poly ethylene core of approved make and colour to withstand for atleast 15yrs for fading(warranty certificate from manufacturers is to be given for 15yrs against fading,chalking and delaminations etc.).The joint should be finished with silicon based weatherproof sealant of Dow corning 789 make so as to render the panel waterproof.Necessary hardwares like clamp,anchorning bolts,nuts and other fastening materials are to be used of reputed make..The panel should be of PVDF paint coating of bank's approved colourand size. The work to be completed in all respect .	Sqmt	30		
22	Supplying revolving chairs of approved make as per specification below with standard upholstery of approved shade.				
i)	BM'S CHAIR				
	High back chair with tilting mechanism , locking systems , seat with gas lift for height adjustment, Nylon base with castors and armrest. Fire reterdent fabric . UPHOLSTERY : FABRIC BLACK/ BLUE 2923 (MODEL NO: RNW212)	Each	1		
ii)	OFFICER CHAIR				
	Medium back chair with back tilting mechanism with locking systems, seat with gas lift for height adjustment, Nylon base with castors and armrest. UPHOLSTERY : FABRIC BLUE 2923 (MODEL NO: ALM333)	Each	7		
iii)	VISITORS FOR OFFICERS				
	Low back Visitor chair with fabric seat and MS black powder coated fixed type four legs. Firereterdent fabric. UPHOLSTERY : FABRIC BLUE 2923 (MODEL NO: FC72)	Each	11		
iv)	LOBBY CHAIRS (3SEATER)				
	Grey powder coated prforated type 3seatwer lobby chair. (MODEL NO: LWC 114)	Set	1		
	TOTAL				
	Less Discount If Any				
	SUB TOTAL				
	Add GST @ 18%				
	GRAND TOTAL				