

BOQ FOR LAN WORK FOR UCO BANK- RAJAGRAM BRANCH INCLUDING ATM					
NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	Supplying laying of Cat -6 wire through prelaidd PVC regid pipe from HUB to IO box. (D-link/Luncent make)	355	Mts		
2	Supplying laying of 25mm PVC pipe ISI mark in floor/wall/doodem partition for drawing Cat 6 wire from HUB to IO terminal. (AKG / Pecission/ Polycab make)	179	mts		
3	Supply fixing connection of IO box with front plate & RJ 45 socket under table. (D-LINK make) .	11	Nos		
4	Mounting cord 7' 0"make D-Link	11	No		
5	Mounting cord 3' 0"make D-Link	11	No		
6	24 PORT 10/100Mbps Switch	1	No		
7	24 Port Jack Panel Make:-D-Link	1	No.		
8	19" Rack 9U with Glass Door , Locking system Make: APW	1	No		
	GRAND TOTAL - B				