

**Bill of Quantities for : Proposed Supply & Installation of Split typ A. C. unit work at Alternate Premises for Jamnagar Branch for UCO Bank, Ahmedabad Zone.**

Sr. No.	Description	Qty.	Rate	Unit	Amount
<b>1</b>	<b>1.50 ton SPLIT TYPE A.C. UNIT</b>				
	Supplying & providing 1.50 TR split A. C. with high wall mounted unit <b>3 STAR RATING Inverter Type with copper condenser &amp; current year model</b> for Manager cabin & Banking Hall etc. completed as per direction. (HITACHI/CARRIER/DAIKEN/BLUE STAR/MITSHUBISHI)	0		NO	
<b>2</b>	<b>1.00 ton SPLIT TYPE A.C. UNIT</b>				
	Supplying & providing 1.00 TR split A. C. with high wall mounted unit <b>3 STAR RATING Inverter Type with copper condenser &amp; current year model</b> for Manager cabin & Banking Hall etc. completed as per direction. (HITACHI/CARRIER/DAIKEN/BLUE STAR/MITSHUBISHI)	2		NO	
<b>3</b>	<b>REMOVING &amp; RE-FIXING EXISTING A.C. UNIT</b>				
	Removing & re-fixing of existing split A. C. indoor & outdoor unit with water washing servicing, repairing, gas filling etc. completed as per new lay out plan as per direction.	5		NO	
<b>3</b>	Installation charges for above 1.50 & 1.00 TR split A.C. including 3.0 RMT copper tubing per unit with proper insulation tape etc. complete as directed.	2		NO	
<b>4</b>	Supplying & fixing Copper tubing with proper insulation & electrical cable for outdoor unit for additional length after 3.0 RMT of standard length. (For additional length above 3.00 RMT). This item also includes making zari in wall/floor and filling the same with cement mortar and POP as per direction of Architect/ Bank.	85		RMT	
<b>5</b>	Supplying & fixing 15/20mm dia. U-PVC drain pipe concealed in wall, floor with necessary insulation etc.. This item also includes making zari in wall/floor and filling the same with cement mortar and POP as per direction of Architect/Bank.	80		RMT	
<b>6</b>	Providing & fixing powder coated L-shape stand for keeping out door unit of Split A. C. etc. complete.	7		NO	
<b>7</b>	Fabricating & fixing M. S. platform/stand made from Angle, Patti etc. as per design for keeping outdoor unit of split A. C. unit including cage for locking arrangement etc. complete as directed	7		NO	
<b>8</b>	Filling the Gap/hole of wall for A. C. copper & drain piping by cement, brick etc. with line & level etc. complete as per direction.	7		NO	
<b>TOTAL OF AIR CONDITIONING WORK</b>				<b>Rs.</b>	
<b>ADD FOR GST @ ____ % ON RS. A.C. MACHINE</b>			<b>(+)</b>	<b>Rs.</b>	
<b>ADD FOR GST @ ____ % ON RS. LOW SIDE WORK</b>			<b>(+)</b>	<b>Rs.</b>	
<b>FINAL TOTAL OF AIR CONDITIONING WORK</b>				<b>Rs.</b>	

**Rupees**

**Name of Contractor with Seal & Signature**

**Date :**

**Place :**

Note : 1. Above rates includes all transportation charges etc..  
2. Make : Hitachi, Daiken, Blue Star, Carrier  
3. THE VENDOR SHOULD MENTION THE MAKE OF A. C. UNIT CLEARLY. THE A. C. UNIT WILL HAVE 3 STAR RATING INVERTER TYPE  
The vendor will give warranty for one year (1) for the entire A. C. unit and further four (4) years warranty for the compressors of the A. C. units.