

UCO BANK					
NAME OF WORKS: PROPOSED INTERIOR DESIGN FOR ATHWALINES BRANCH, GHOD-DOD RD., SURAT.					
Part-3 -BOQ of Proposed Supply & Installation of HVAC work.					
Item Sr. No.	Qty	Description of Work/ Item	Unit Rate with 1% Cess	Unit	Total Amount
HVAC					
1		Providing and erecting Inverter based approved make split air-conditioning unit consisting of condensing unit with variable speed fan motor, inverter type hermetically sealed rotary compressor with accessories etc. duly connected separately erected evaporating unit and blower motor with its accessories by means of extra supplied proper insulated copper tubing, drain PVC pipes suitable for (cost includes Eco Friendly green gas charging and 15A plug top & Remote Control & MS Stand) with necessary core cutting. Rate is Exclusive of Installation Charges. Voltas / Panasonic / Daikin / Blue Star company make. For 5 Star Rating of current year			
	2.00	(A) for 1.0 ton capacity		Ea.	
	1.00	(B) for 1.5 ton capacity		Ea.	
2		Providing and erecting Inverter based approved make Cassette type split air-conditioning unit consisting of condensing unit with fan motor, hermetically sealed scroll/rotary compressor with accessories etc. duly connected separately erected evaporating unit and blower motor with its accessories by Eco friendly Green gas charging & Internal copper wiring & Remote control (5 star and above of current year) Rate is Exclusive of Installation Charges. Voltas / Panasonic / Daikin / Blue Star company make. For 5 Star Rating of current year			
	1.00	(A) for 2 ton capacity- 4 Way		Ea.	
	2.00	(B) for 3 ton capacity- 4 Way		Ea.	
Total amount of Sr. No.1 to 2=					

Item Sr. No.	Qty	Description of Work/ Item	Unit Rate with 1% Cess	Unit	Total Amount
3	3.00	Spit Ac Installation Charges (Refer Item No.: 1)		Nos.	
4	3.00	Cassatte Ac Installation Charges (Refer Item No.: 2)		Nos.	
5	300.00	Copper Piping of appropriate size with Insulation, Power supply cable of Min. 3 core 2.5 Sq. MM along with proper fitting, finishing, etc...complete.		R. Ft.	
6		Providing laying and jointing in true line and level Rigid UPVC drain pipe of 10 Kg/cm2. rating with 9 mm thick.nitrile rubber insulation for drain water including fittings make PRINCE, ASTRAL, FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall / ceiling with the help of clamp at every 1.5 to 2.0 metre C/C or as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.			
	0.00	(A) 50 mm dia.		R. Ft.	
	0.00	(B) 40 mm dia.		R. Ft.	
	50.00	(C.) 32mm dia.		R. Ft.	
	100.00	(D) 25 mm dia.		R. Ft.	
	5.00	(E) 19 mm dia.		R. Ft.	
	155.00				
7	6.00	Misc. expances- i.e.: Transportation and delivery charges, lifting labour charges, etc... charges		Lum-Sump	

Item Sr. No.	Qty	Description of Work/ Item	Unit Rate with 1% Cess	Unit	Total Amount
8	2.00	Core Cutting in Slab / Beam as per Interior consultant & building structural designer's instruction of 75 mm to 150 mm size dia as per requirement.		Lum-Sump	
9	400.00	M.S. Steel work welded in built up sections, framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint (A) in beams & joists channels angles, tees, flats with connection plates or angle cleats as in main & cross beams,hip & trussed purlins connected to common raffers & the like.		K.G.	
10	150.00	Painting two coat (excluding priming coat) on new steel and other metal surface with synthetic enemal paint, burshing to give an even shade including cleaning the surface of all dirt, dust and other foreign matters.		Sq. Ft.	
		Total amount of Sr. no. 3 to 9=			₹ -
		18% GST on Item No.: 3 to 9=			₹ -
		28% GST on Item No.: 1 & 2=			₹ -
		Total Amount Incl. GST=			₹ -
Amount in words:					
NOTE: 1) Contractor need to fill the rates for 'Zero' qty. item also. 2) Make: Voltas, Daikin, Hitachi, Bluestar 3) The vendor should mentioned the company of AC unit while quating the rates. Min. 3 Star rating required of current year for all types of AC units. 4) The vendor should give warranty for minimum one year (1) for the entire A. C. unit and further four (4) years warranty for the compressors of the A. C. units.					
Name of Contractor with Seal & Signature					
Date :		Place :			