

UCO BANK		
ESTIMATES FOR PROPOSED INTERIOR WORKS IN BRANCH & ATM AT SHAJAPUR		
S. NO.	WORK	AMOUNT
1	TOTAL FOR INTERIOR WORKS IN BRANCH	
2	TOTAL FOR ELECTRICAL WORKS IN BRANCH	
3	TOTAL FOR FURNISHING & ELECTRICAL WORKS IN ATM	
4	TOTAL FOR A.C. WORKS IN BANCH & ATM	
	TOTAL FOR Rs.	

UCO BANK			SCHEDULE OF		
ITEMS FOR FURNISHING WORK IN BRANCH AT SHAJAPUR					
S. NO.	ITEM	QTY	UNIT	ESTIMATED COST	
	WORK FOR BRANCH			RATE	AMOUNT
1	<b>CASH COUNTER:</b> Supplying, fixing & keeping in position clerical counter made out of 19mm commercial ply. The cost shall be inclusive of following: Working top 2'8" wide ( at 2'6"ht) with 1.0mm thick laminate on top & provision for key board tray fixed below working top. Cable managers to be provided for wires & cables. Transaction top 1'4" wide (at 3'9"ht.) finished with 1.0mm thick laminate. Cash transaction slot to be provided as directed. Each counter will have 3 nos. drawer unit 1'4" wide made out of 19mm block board sides & 6mm ply bottom on sliding drawer channels with locking arrangement. Drawer will also have internal (removable) partitions in drawers as desired by the cashier for keeping notes of different denominations. A pedestal below 1'0" wide to be provided for keeping CPU. Facia of drawer & top of pedestal to be finished with 1.0mm thick laminate. Front panel shall be finished with 1.0mm thick laminate. All exposed edges of commercial ply will have 6mm thick T.W. beading. All fittings like handles, knobs, lock, hinges, etc., will be of superior quality. All wood work & exposed surface of block board will be polished in natural color. Counter shall have foot rest made out of 3" x 2" T.W. section duly polished.	4.50	R.ft.		
2	<b>CASH CAGE FRONT PARTITION:</b> P&F in position cash cabin partition above cash counter on front side made out of kail wood frame work with 12mm clear float glass with exposed edges duly polished. Glass will have etching work as directed. All wood work to be polished.	15	sq.ft.		
3	<b>Cash cabin partition (7'6" height)</b> P&F partition made of 50 x50mm Aluminium frame @ 600mm c/c fixed rigidly at floor level as well as ceiling bottom. 8mm thick commercial ply of approved make with 1mm thick laminate of approved quality and shade shall be fixed on both faces of partition as per design & groove, up to 1150mm from ground level from 1150 up to 2100mm Aluminium deco grill (DG 202) to be provided fixed with teak wood beading. Skirting shall be 100mm high made of 12mm thick teak wood section. The item includes door shutter made of 50 x 50mm Aluminium frame @ 300 to 400mm c/c both ways with 6mm thick commercial ply on both faces finished with 1.0mm thick laminate of approved quality & shade with teakwood edging out of 40 x 20mm section on all edges of shutter ( all round) with teak wood frame out of 75 x 50mm section. Item also includes necessary hardware such as hinges, tower bolts, door stopper, godrej lock (Night Latch) with SS handle (6") and door closer of approved quality and design. All exposed teak surfaces shall be finished with approved colour of melamine. The rates i/c of provision for electrical conduits, switch and junction boxes.	60	sq.ft.		
4	<b>FULL HEIGHT PARTITION:</b> a. P&F partition made of 50 x50mm Aluminium frame @ 600mm c/c fixed rigidly at floor level as well as ceiling bottom. 8mm thick MR GRADE ply of approved make with 1mm thick laminate of approved quality and shade shall be fixed on both faces of partition as per design & groove. ISI marked flush door (minimum 30mm)shutter confirming to IS: 2202 (Part-1) non-decorative type core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters using following hinges.50mm thick including ISI marked stainless steel butt hinges with necessary screws. Door will be finished with 1mm thik laminate on both side ,rate to include necessary hardware such as mortise lock, door closer, tower volt, aldorp ,angle iron frame for fixing flush door. All exposed teak surfaces shall be finished with approved colour of melamine. The rates includes making provision for electrical conduits, switch and junction boxes. b. <b>GLAZED PARTITION:</b> Same as item no. 01. But 1050mm high 8mm thick clear glass with etching work of approved make shall be fixed at 900mm height from floor finish level fixed with 20 x 35mm teak wood beading of approved design in place of frame and commercial ply with laminate. All exposed teak surfaces shall be finished with approved colour of melamine .(Measurement up to false ceiling)	330	sq.ft.		
5	<b>UPS/ RECORD ROOM PARTITION:</b> P&F UPS / Record room Partition Including Door 9mm thick cement board (BISON PANEL ONLY) finished with 1.00mm thick laminate of approved shade on both sides of the PANEL resting on 50 x 50mm Aluminium frame @ 300 to 400mm c/c both ways with ISI marked SS butt hinges with necessary screws, handles aldorp door stopper etc.	270	sq.ft.		
6	<b>LOW HEIGHT PARTITION: (4'0" height) including flap door</b> P&F partition made of 50 x50mm Aluminium frame @ 600mm c/c fixed rigidly at floor level. 8mm thick commercial ply of approved make with 1mm thick laminate of approved quality and shade shall be fixed on both faces of partition as per design & groove with necessary opening for the glass at 1050mm height. These opening shall be covered by 12mm thick plain glass with etching work fixed with brass clips on three sides or with wooden beading. All exposed edges of glass shall be grinded polished. Skirting shall be 100mm high with 1mm thick laminate.	55	sq.ft.		
7	<b>Glass on low height counter:</b> P&F 12mm thick plain glass with etching work (6" + 12") on low height counter fixed with brass clips, exposed edges of glass duly polished. T.W. intermediate support to be provided as directed.	26	sq.ft.		
8	<b>NOTICE BOARD:</b> P&F notice board/ display board made of 50 x50mm Aluminium frame @ 600mm c/c both ways with 6mm thick commercial ply / particle board with 12mm thick soft board covered with approved fabric & color , with 50x 25mm teak wood moulding all around finished with melamine.	12	sq.ft.		
9	<b>STORAGE FULL/LOW HEIGHT:</b> P&F storage unit 540mm deep made out of 19mm thick commercial ply of approved quality & make with 6mm ply back. One no. shelf to be provided horizontally and vertical partition will be at 1200mm c/c. All exposed vertical & horizontal surfaces to be finished with 1mm thick laminate. All exposed edges of ply to be finished with 6mm thick teak wood beading duly polished. The rates include necessary hardware such as piano hinges, tower bolts, lock, magnetic ball catcher, 4" long SS handle of approved design.	300	sq.ft.		

10	<b>CLERICAL COUNTER:</b> Supplying, fixing & keeping in position low height counters made out of 19mm thick commercial ply. Cost shall include : working top 810mm wide at 750mm height finished with 1.0mm thick laminate. A drawer unit consisting of 1 drawer unit & 1 storage unit 400mm wide, drawer to be made of 19mm ply with 6mm ply bottom. Facia of drawer, storage shutter, front panel to be finished with 1mm thick laminate. Each counter will have CPU stand, footrest, keyboard tray ( Ebco). All fittings like handles, knob etc., will be of superior quality. Item includes cutting of holes in top & sides , making provision in counter for pipes/ conduit i/c P&F of cable manager.	12	R.ft.		
11	<b>FALSE CEILING (CALCIUM SILICATE TILES)</b> P&F of false ceiling at all heights of 600mmx 600mmx6mm heavy duty Calcium Silicate Tiles (Marketed by Ramco) laid on arm strong prelude XL exposed grid systems with 9mm wide T Section flanges colour white. The frame work comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit approved hangers at 1200mm maximum centres. Hangers (GI wire) to be fixed by approved roof plug and screws etc. The last hanger at the end of each main runner should not be greater than 450mm. from the adjacent wall. flush fitting 1200mm. along cross tees (with double stitching) to be interlocked between main runners at 600mm. c/c to form 1200x600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mmx600mm modules to be formed by fittings 600mm long flush fitting cross tees centrally between the 1200mm cross tees. Perimeter trim to be arm strong wall angle secured to walls at 450mm. maximum centres.	216	sq.ft.		
12	<b>FALSE CEILING ( GYPSUM BOARD)</b> Providing & fixing in position false ceiling in Gyp board 12mm thick for horizontals & verticals fixed over G.I. framework as specified by India Gypsum Co. Ltd. including cutout for light fittings and finishing to proper line & level and finishing with white plastic paint etc., complete. (Measurement: For Vertical drop exposed height will only be considered.)	560	sq.ft.		
13	<b>MANAGER TABLE: (5'6" X 2'9" X 2'6" HT.) INCLUDING SIDE CREDANZA</b> Supplying & fixing in position Manager table made out of 19mm commercial ply finished with 1.0mm thick laminate on top and vertical surfaces . Top will also have 8mm thick float glass with edge polish. Table will have storage unit on one side with 2 nos. drawer on sliding drawer channel with locking arrangement & one cabinet below drawer with shutter. Facia of drawer & shutter shall be finished with 1.0mm thick laminate. Foot rest made out of 19mm block board (box type with top inclined) to be provided. All exposed edges of commercial ply will have 8mm T.W. beading. duly polished. All hardware fitting of superior quality. Table will be provided with Keyboard tray (Ebco). <b>SIDE CREDANZA (3'3" x 1'4" x 2'6" ht.)</b> S&F side units made out of 19mm block board & 8mm ply back. Top & side finished with 1.0mm thick laminate. Side unit will have a space for keeping CPU on pedestal and remaining portion will have a open shelf. Side unit will also have cable manager for wires & cables. All exposed edges of Block board will have 6mm T.W. beading. All exposed wood work & block board surfaces to be polished. All hardware fitting will be of superior quality.	1	Each		
14	<b>OFFICER TABLE: (5'0" X 2'6" X 2'6"HT.)</b> Specification same as item no. 13 but will have 6mm float glass on top.	1	Each		
15a.	<b>BM Chair Thril Mesh plus Chair with headrest Godrej</b>	1	Each		
b.	<b>Officer Chair Thrill Mesh Bach Chair Godrej</b>	5	Each		
c.	<b>Visitor Chair Ch1018 Godrej</b>	7	Each		
d.	<b>Visitor Chair 3 seater Steel</b>	1	Each		
16	<b>WRITING DESK: ( 3'0" x 1'4" x 1'0"ht.)</b> P&F in position writing stand made out of 19mm thick commercial ply finished with 1mm thick laminate having 12mm thick bevelled edge glass upper top of required shape exposed surfaces shall be finished with approved colour of melamine It will have a unit at lower level made of 19mm ply with 6mm ply back . Below glass top pockets for slips to be provided by providing 8mm thick glass.	1	Each		
17	<b>CHEQUE &amp; SUGGESTION DROP BOX:</b> P&F in position laminated cheque drop box made of 19mm thick commercial ply and will have locking arrangement. All internal surface of commercial ply to be painted with synthetic enamel paint (1 coat primer, 2 coat putty, 2 or more coat paint).	2	Each		
18	<b>VENETIAN BLINDS:</b> P&F 4" wide vertical venetian blinds for windows & Manager cabin glazed area (Vista/Trac) complete with all accessories.	70	sq.ft.		
19	<b>PAINTING:</b> Painting with <b>plastic emulsion paint</b> in minimum 2 coats, rate inclusive of scrapping, primer, cement based putty (Birla or J.K.) & paint	2300	sq.ft.		
20	Painting with <b>synthetic enamel paint</b> on rolling shutter i/c of scrapping, putty & paint.	450	sq.ft.		
21	<b>ENTRANCE DOOR (TOUGHEND GLASS)</b> Providing and fixing at site Main entrance Full ht. Full glass door of 12.0mm. thick toughened with polish edges to be fixed heavy duty floor spring (Dorma). Make only with patch fitting & locking arrangement and 450 mm SS brushed finish "D" type handle cost shall include all necessary fittings, all labor, materials, etc. complete.	25	sq.ft.		
22	<b>FIXED GLAZING: (TOUGHEND GLASS)</b> P&F fixed glazing as per design, made out of 12mm thick toughened glass fitted with patch fitting.	25	sq.ft.		
23	P&F cupboard for covering the <b>electrical panel</b> board. The cupboard/shutter will be made of 19mm BWP block board duly laminated with 1.5mm mica. Providing louver in the shutter as per Bank's instructions. Providing all fittings and painting the unexposed area	30	sq.ft.		
<b>TOTAL (A)</b>					

UCO BANK					
SCHEDULE OF ITEMS FOR ELECTRICAL WORK IN BRANCH AT SHAJAPUR					
S.NO.	ITEM	QTY	UNIT	ESTIMATED COST	
	WORK FOR BRANCH			RATE	AMOUNT
1	<b>LIGHT POINTS WITH UPS:</b> Wiring for light points with 2 x 1.5sq.mm.PVC insulated copper conductor wire of 650/1100 volts grade in concealed / exposed PVC pipe/ casing capping as required including 6 amp switch (modular) i/c of box, base plate & cover plate & making all connections complete. Rate also includes cutting chaises and making good the surfaces wherever required.	30	Each		
2	<b>LIGHT PLUG POINTS: (FOR WALL FANS)</b> Wiring for light plug points with 2 x 1.5sq.mm.PVC insulated copper conductor wire of 650/1100 volts grade in concealed / exposed PVC pipe/ casing capping as required including 6 amp switch & 5 pin 6 amp socket (modular) i/c of box, base plate & cover plate & making all connections complete. Rate i/c cutting chaises and making good the surfaces wherever required.	13	Each		
3	<b>6 AMP. POINTS ON SAME BOARD:</b> Supply, fixing and commissioning of 1 No 6A multi Socket with 1 No. 6A switch (Modular type) from with cover plate, sheet steel box / PVC modular box etc on surface / concealed manner i/c electrical connections and making good all the damages, painting, cleaning the site etc. complete as required.	8	Each		
4	P&F ceiling fan point i/c of step regulator & switch.	1	Nos.		
5	P&F bell point i/c of bell.	1	Nos.		
6	<b>CIRCUIT WIRING:</b> Wiring for light circuit with 2 core x 2.5sq.mm + 1core x 1.5 sq.mm PVC insulated copper conductor wire of 650/1100 volts grade in concealed / exposed PVC pipe/ casing capping as required & making all connections complete. Rate also includes cutting chaises and making good the surfaces wherever required.	8	Each		
7	<b>POWER POINTS:</b> Wiring for power points with 2 core x 4.0 sq.mm. + 1 core x 2.5 sq.mm. PVC insulated copper conductor wire of 650/1100 volts grade in concealed / exposed PVC pipe/ casing capping as required including 16 amp switch & socket (modular) i/c of box, base plate & cover plate & making all connections complete. Rate also includes cutting chaises and making good the surfaces wherever required. ( wiring from main DB to point & appropriate MCB on Main DB ) <b>Manager:3; Cash:2; Officer:1; Clerk :3;Strong room:1;Glowsing :1</b>	11	Each		
8	<b>AIR CONDITIONER POINTS:</b> Wiring for Air conditioner points with 2 x 4.0sq.mm + 1 x 4.0 sq.mm PVC insulated copper conductor wire of 650/1100 volts grade in concealed / exposed PVC pipe/ casing capping as required including metra plug & socket with 20 Amp SP MCB & making all connections complete. Rate also includes cutting chaises and making good the surfaces wherever required.	3	Each		
9	<b>MAIN PANEL AND DISTRIBUTION :</b> Supplying & fixing 8 way load line TPN distribution board with neutral links and an earth bar & Busbar with IP 42 degree of protection metal/acrylic; (Legrand) for provision of : Incomer: 100A (16KA) M.C.C.B. - 1 Nos. 63A TPN MCB -3Nos for UPS inclusive DB - 1 Nos. 63A TPN MCB -3Nos for A.C. inclusive DB - 1 Nos. 63A TPN MCB -2Nos for Light inclusive DB - 1 Nos. 63A TPN MCB -2Nos for Power inclusive DB - 1 Nos. 6A to 32A SP MCB – 28-30Nos. cost inclusive of connections etc. complete.	1	Nos.		
10	<b>MAIN SWITCH:</b> Providing & fixing of panel board comprising of main switch 63 amps, 415 volts, TPN with HRC fuse Make: L&T, ABB	1	Set.		
11	<b>CHANGE OVER SWITCH:</b> Providing and fixing at site 100 Amp manual change over switch to be fixed at the site inclusive of necessary wiring all materials, labor, etc. complete to be fixed before LDB.	1	Nos.		
12	<b>UPS INCOMING:</b> P&F 2 way SP &N DB with 40/ 63Amp DP.	2	Nos.		
13	<b>UPS OUTGOING:</b> P&F 12 way SP&N DB with 10nos. 6-10 Amp SP MCB controlled by 40/63 Amp DP MCB.	1	Nos.		
14	<b>UPS POINTS:</b> Wiring for UPS points (computer wiring) with 2 x 1.5sq.mm + 1 x 1.5sq.mm PVC insulated copper conductor wire of 650/1100 volts grade in concealed / exposed PVC pipe/ casing capping as required including 3 no. 6 amp switch & 3 nos. 5 pin 6 amp socket (modular) with fuse & indicator i/c of box, base plate & cover plate & making all connections complete. Rate also includes cutting chasis and making good the surfaces wherever required. <b>Manager:3; Cash:2; Officer:1; Clerk:3; Near Router:1; Near UPS:1</b>	11	Each		
15	<b>UPS WIRING:</b> Wiring with 4 x 10 sq.mm PVC insulated copper conductor wire of 650/1100 volts grade in concealed / exposed PVC pipe casing capping as required including making all connections. Rate also includes cutting chasis and making good the surfaces wherever required. <b>Main Panel To UPS Room</b>	20	R.M.		
16	<b>G.I.PLATE EARTHING:</b> G.I. plate earthing with 600x600x6mm G.I. plate with 40mm dia G.I. pipe, 12mm dia G.I. pipe, C.I. cover, bend, G.I. nut, bolts, washers, making 3 to 4m deep hole 0.9M dia, making haudi with bricks, cement sand etc. filling haudi with charcoal & salt all complete.	1	Each		

17	<b>COPPER PLATE EARTHING:</b> Copper plate earthing with 600x600x3mm copper plate with 40mm dia G.I. pipe, 12mm dia G.I. pipe, C.I. cover, bend, brass nut, bolts, washers, making 3 to 4m deep hole 0.9M dia, making haudi with bricks, cement sand etc. filling haudi with charcoal & salt all complete.	1	Each		
18	Supply & laying 6 sq.mm. PVC insulated copper wire in 15mm dia. Conduit pipe including accessories complete as required.	30	R.M.		
19	Supply & laying 8 swg. G.I. earth wire in 15mm dia. Conduit pipe including accessories complete as required.	30	R.M.		
20	<b>G.I. STRIP:</b> P&F 25x6mm G.I. earth strip from earth plate to Main board.	4	R.M.		
21	<b>COPPER STRIP:</b> P&F 25x3mm copper earth strip from earth plate to UPS.	4	R.M.		
22	<b>ELECTRICAL FIXTURES:</b> Providing & Fixing, testing & commissioning of following fittings & fixtures with proper connections with all material, labor to make installation complete in all respects.				
a	36 W LED 2x2 panel (Havells, Syska, Crompton, Bajaj, Wipro)	13	Each		
b	P & F down lighter recessed LED fitting 14W (Havells, Syska, Crompton, Bajaj, Wipro)	5	Each		
c	22W LED tubelight (Havells, Syska, Crompton, Bajaj, Wipro)	10	Each		
d	Wall/ bracket fan (Bajaj/Crompton)	13	Each		
e	Exhaust fan (300mm dia.) (Khaitan: heavy duty)	3	Each		
f	Ceiling fan (Crompton: High Breeze)	1	Each		
23	<b>MAIN CABLE:</b> Providing & laying PVC insulated PVC sheathed ( heavy duty) armored aluminum cable for working voltage up to 1100 volts complete i/c of termination glands. 3.5 core 50 sq.mm.	30	R.M.		
24	<b>LAN CABLING:</b> P&F lan cabling with Cat-6 ( D-Link) in PVC conduit/ casing capping/ flexible pipe as required. inclusive of RJ 45 info outlet (D-Link) complete with jack, box, cover plate, crimping etc., complete.	7	Each		
25	<b>PATCH CORDS:</b> Providing 1 M long patch chord ( D-Link)	7	Each		
26	<b>PATCH CORDS:</b> Providing 2 M long patch chord ( D-Link)	7	Each		
				<b>TOTAL (B)</b>	<b>0.00</b>

UCO BANK					
SCHEDULE OF ITEMS FOR FURNISHING & ELECTRICAL WORK IN ATM AT SHAJAPUR					
S.NO.	ITEM	QTY	UNIT	ESTIMATED COST	
	WORK FOR ATM			RATE	AMOUNT
1	<b>ENTRANCE DOOR (TOUGHEND GLASS)</b> Providing and fixing at site Main entrance Full ht. Full glass door of 12.0mm. thick toughened with polish edges to be fixed heavy duty floor spring (Dorma). Make only with patch fitting & locking arrangement and 450 mm SS brushed finish "D" type handle cost shall include all necessary fittings, all labor, materials, etc. complete.	21	sq.ft.		
2	<b>FIXED GLAZING: (TOUGHEND GLASS)</b> P&F fixed glazing as per design, made out of 12mm thick toughened glass fitted with patch fitting.	20	sq.ft.		
3	P&F suspended 12mm thick <b>gypsum board</b> ceiling with joint filling & leveling as per manufacturer specifications including painting with plastic emulsion paint.	40	Sq.ft.		
4	Painting with <b>synthetic enamel paint</b> on rolling shutter i/c of scrapping, putty & paint.	220	sq.ft.		
5	<b>ELECTRICAL FITING</b> :P&F 36 W LED 2x2 panel. (Havells, Bajaj, Philips, Crompton, Wipro) .	1	Each		
6	<b>ELECTRICAL FITING</b> :P & F down lighter recessed LED fitting 14W(Havells, Bajaj, Philips, Crompton, Wipro)	1	Each		
7	Electrical with UPS cabling, Modular switch & socket ( M.K., Anchor Roma). Wire (Finolex, Anchor).	1	Each		
	ITEM: a. 6/16amp. 6 pin socket with 16 amp switch 13 nos points ( ATM 2 nos., NIU 2 nos., Monitor 1 nos., Camera 1 nos., Text interface 1 nos.,Spare power point 1 nos.,A.C 2 nos. ) b. 6 amp. single switch for LED light, spot light, and signage - 6 nos. c. 3phase 4 way DB with 4 pole ELCB 63A 300MA appropriate nos. of 20-30 amp., SPMCB's 40amp 2 pole MCB 1 nos. d. SPN DB with appropriate MCB's 2 nos. 15 amptops. Cables for input & output to and from UPS Complete with testing & commissioning.				
8	<b>EARTHING:</b> 600 x 600 x 3mm <b>copper plate earthing</b> i/c of watering, GI pipe with funnel, salt & coal filling, 10" x 10" masonry chamber with sand plaster, CI lid, 10SWG copper wire in PVC pipe from bottom of pit to existing ground level.	1	Each		
9	Supply & laying 6 sq.mm. PVC insulated <b>copper wire</b> in 15mm dia. Conduit pipe including accessories complete.	20	R.m.		
10	<b>COPPER STRIP:</b> P&F 25x3mm copper earth strip from earth plate to UPS.	4	R.M.		
11	P&F 4 core 10 sq.mm. copper armoured cable from Meter to ATM main DB.	20	R.ft.		
12	P&F main switch 63amp., 415V, TPN with HRC fuse including installation complete as directed.	1	Each		
13	<b>TIMER:</b> P&F at site industrial Timer for glow sign board near the Main panel board including fixing the same as per the site condition i/c all accessories, labor, materials, etc.	1	Each		
14	<b>LAN CABLING:</b> P&F lan cabling with Cat-6 ( D-Link) in PVC conduit/ casing capping/ flexible pipe as required. inclusive of RJ 45 info outlet (D-Link) complete with jack,box, cover plate,crimping etc., complete.	1	Each		
15	<b>PATCH CORDS:</b> Providing 1 M long patch chord ( D-Link)	1	Each		
16	<b>PATCH CORDS:</b> Providing 2 M long patch chord ( D-Link)	1	Each		
				<b>TOTAL (C)</b>	<b>0.00</b>

UCO BANK					
SCHEDULE OF ITEMS FOR A.C. WORK IN BRANCH & ATM AT SHAJAPUR					
S.No.	Item	Qty.	Unit	Rate	Amount
1	P&F of 1.00 ton Split Air conditioner( <b>5 star</b> ) with LCD remote. Rates inclusive of installation of A.C. ( Carrier, Daikin, Bluestar ) ( <b>Branch &amp; ATM</b> )	3	Each		
2	P&F of 2.00 ton Split Air conditioner ( <b>5 star</b> ) with LCD remote. Rates inclusive of installation of A.C. ( Carrier, Daikin, Bluestar ) ( <b>Branch</b> )	2	Each		
3	P&F of 4/5 KVA stabilizer for A.C.	5	Each		
4	P&F of caging for A.C. of external unit made out of M.S. flat/square rod including painting the cage with synthetic enamel paint & a.c.Stand.	5	Each		
5	Additional Copper piping i/c insulation & electrical cable from indoor to outdoor unit for additional length after 3.0 RMT of standard length.( For additional length above 3.00 RTM) Concealing of copper piping, in wall under floor/walls as per site condition and repairing the walls and floor.	60	RM		
6	Timer switch of A.C.	1	Each		
7	Drain piping for A.C. i/c Concealing of drain pipe in wall under floor as per site condition.	30	RM		
				<b>TOTAL (D)</b>	<b>0.00</b>