


B.O.Q OF INTERIOR WORK FOR UCO BANK AT F.M COLLEGE BRANCH .					
SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
A	PARTITION WORK				
1(A)	FULLY HEIGHT Partition (Semi Glazed) Providing and fixing in position partly glazed full Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 ½" hevy gazed almunium section and/or as per frame work shown in the drawings with 9 mm plywood (conforming ISI 710) on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass with chemical eachingas per design and fitted with 3-1/4" thick beach wood beading and 2"x2" T.W. member for door sides . All exposed T.W / beading surfaces to be finished in melamine polish as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects. (Note : In case of false ceiling, the vertical members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)	Sft.	384.00		
B	LOW HEIGHT Partition (Semi Glazed) Providing and fixing in position partly glazed 4'-0" HT. Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 ½" hevy gazed almunium section and/or as per frame work shown in the drawings with 9 mm plywood (confermin ISI 710) on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass with chemical eaching as per design and fitted with 3-1/4" thick beach wood beading at glass sides All exposed wood. surfaces to be finished in melamine polish of as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.	Sft.	59.00		
C	Partition (Cement board partition.) Providing and fixing both side solid partition using framing and laminate as per details mentioned in Sl. No.1 (A) . The skin of the partition shall be made out of 10mm thick cement fiber board and finished with 1mm thick laminate of approved shade and scheme on the customer side (visible to customers) and 2 coats of ivory white enamel paint on the internal side (not visible from the customer lobby).The work should be completed in all labour and materials.	Sft.	389.00		



SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
2.0	Full glazed Partition				
	Providing , fitting & fixing 12mm thick float glass partition .The partiton will be supported with S.S patch panel fittings as per drawing and design. The exposed edge of the glass partition should be polished to super quality. The work should be completed as per direction of architect including cost of all labour & material .	Sft.	35.00		
B	DOOR WORK.				
1.0	Doors – Partly glazed/ solid				
	Providing and fixing partly glazed doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make (conforming IS 2202) and finished with 1mm thick approved laminate on both sides. The edges finished with teak wood lipping. The shutter will have part glazed 8mm thk float glass with body itching of and necessary TW wood beading etc mat polished with melamine polish of asian / ici , complete to match the aligned partition elevations designs, the rates are inclusive of cost of necessary hinges, handle , etc., all labour, materials, taxes, leads & lift to the place of work executed to the satisfaction of the Architect.	Sft.	155.00		
2.0	Doors – glazed				
	Providing and fixing Entrance Door (glazed) as per drawing in black Anodised aluminium door single groove section of size 125mmx25mm (Jindal make) in top and bottom & sides glazed with 10 mm thick glass of approved make . Item to include all necessary hardware of Stainless Steel finish and chemical eaching with bank's logo as approved by the Project Consultant/Bank complete in all respects.				
	a) Open able portion (it include SS finished H type 1'-6" long door handle)	Sft	24.50		
	b) Fixed portion	Sft	28.00		
3.0	Door closer				
	Providing and fixing Godrej/ Doorset make over head door closers in door with necessary fixtures and fittings etc.	Nos	4.00		
4.0	Floor spring				
	Providing and fixing Godrej/ Door set make heavy duty floor spring in entrance door with necessary fixtures and fittings	Nos	1.00		
5.0	Night latch lock				
	Providing and fixing Knightlatch lock of Godrej make to cash counter door with necessary fixture and fittings etc as per direction of architect.	Nos	1.00		
6.0	Motise lock				
	Providing and fixing motise lock to the door (6-lever- 8" lock of Godrej / Doorset make) as per direction of architect.	Nos	4.00		
7.0	Door Aldrop				
	Providing and fixing SS 10 inch Aldorp in door as per instruction including all labour, accessories and materials.	Set.	2.00		




SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
8.0	Flap door Providing, fitting and fixing of flap door with frame work made out of 35mmx35mm thick hard wood and nailed with 6mm. thick ply and finished with 1mm. Thick laminates of approved colour and design on both the surfaces of the frame work as per drawing and design. The edges of the door to be covered with decorative wood moulding with two coat of superior wax polish. The work is to be finished with all material, labour, nails, screws, hinges, locks, handles, and all other hard wares as per detail drawings and as per direction of architect.	Sft	0.00		
C	FURNITURE WORK.				
1.0	Cash Counter Providing and fixing of cash counter table of size 4'-6"x3'-0"x 2'-6" with table top of 25mm th. ply and the front facia is raised up to ht of 3'-6" with a horizontal 15" wide counter top and front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm th. ply (conforming IS 710) with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm th. laminates as per design of approved shade and the inner surface is finished with 0.7 mm th inner laminate . Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers, foot rest etc. The work should be completed including all	Nos	1.00		
2.0	Table Providing & fixing table made up of 19mm ply and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm th. ply (conforming IS 710) with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm th. laminates as per design of approved shade and the inner surface is finished with 0.7 mm th inner laminate . Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers , etc. of approved quality. The work should be completed including all labour and material.				




SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
	a) Approx. size of 6'-0"X2'-9"X2'-6" (with front drawer unit)	Nos	1.00		
	b) Approx. size of 4'-6"X2'-9"X2'-6"(with front drawer unit)	Nos	1.00		
	c) Approx. size of 4'-6"X2'-9"X2'-6"(without front drawer unit)	Nos	2.00		
	d) Approx. size of 3'-6"X2'-0"X2'-6"(with front drawer unit) Daftari	Nos	1.00		
	e) Approx. size 2'-0" wide as per design (with front drawer unit) May I help u table	Nos	1.00		
3.0	Keyboard try.				
	Providing fixing readymade keyboard of engineering plastic (KD 575 PMT/INNOFIT SYSTEMS OR Equivalent) .The keyboard is a pullout type, fixed to channels and screwed to below table top as per direction .	Nos	5.00		
4.0	CPU Trolly.				
	Providing and supplying mobile metal CPU trolley manufactured by M/s Godrej / EBCO attached with 4 wheels for holding CPU and for its smooth movement	Nos	5.00		
5.0	Table top glass				
	Providing , fixing and supplying table top glass of 8mm th. with all edge mirror polised and holes should be made as per wair manager in table top. The work should be completed in all respect including all labour and materials.	Sft.	65.00		
6.0	Foot rest .				
	Providing and supplying foot rest of size (250mm x 500mm x 125- 75 mm ht.) for each table made up of 19mm ply finished with two coat of enamel paint over one coat of primer.	Nos	6.00		
7.0	Side Storage Unit				
	Providing and fixing of table side storage cabinate as per mention size made out of 19mm th. block board having one/ two drawer uint at top and cupboard unit at bottom as per design / instruction by accchitect . The storage unit and drawer units should have locking arrangement with front shutter .The exposed surface is to finished with 1.0mm th.laminates as per design of approved shade and the inner surface is finished with 0.7 mm th inner laminate . The work also include intermediate shaves as per design .The work should be completed according to drawing and design including all labour and materials.				
	a) Approx. size of 3'-6" x 1'-6"X 2'-6"	Nos	1.00		
	b) Approx. size of 3'-0" x 1'-6"X 2'-6"	Nos	2.00		



SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
4.0	Storage Cabinate.				
	Providing and fixing of low/ full height storage cabinate having 450mm. depth of made out of 19mm th. ply (conforming ISI 710) and 6mm th. WPC ply on back side of storage unit having horizontal intermediate shalves as per requirement & as per design . The storage unit should have locking arrangement with front shutter .The exposed surface is to finished with 1.0mm th.laminates as per design of approved shade and the inner surface is finished with 0.7 mm th inner laminate .The work should be completed according to drawing and design including all labour and	Sft	115.00		
D	CEILING WORK				
1.0	False ceiling (Gride Celing)				
	Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 99 Prima tile with Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A. C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A. C. unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	Sft	388.00		



SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
2.0	False ceiling (Gypsum board.) Providing & fixing at site plain gypsum board stepped/ flush false ceiling as per pattern & design made from 12.5mm thk paper reinforced gypboard sheets fixed with mainframe channels 80mm x 26mm x 0.5mm, every 450mm c/c or as mentioned in drawing intermediate channels 15mm x 45mm x 0.9mm at every 1220mm c/c with perimeter channel 20mm x 26mm x 0.5mm all along the wall shall be provided. The whole system to be suspended with strap bolts as recommended using rawl plugs 12.5mm dia. x 35mm long, with 6mm dia bolt & soffit cleat 27mm x 37mm x 25mm x 1.6mm thk. Gypboards to be screw fixed to the above framework using 25 mm dry wall screws. Provisions of melamine polished white beach wood moulding at wall / partition joints. Arrangements are to be made to accommodate light fixtures by forming recessed channels etc., wherever directed. Depressions, nails & screws, jointing & finishing etc., shall be done with jointing compound & paper tape. Ceiling shall be finished with painting 2 coats of plastic emulsion paint (velvet touch) of approved shade . Ceiling to be leveled & free from cracks including fixing GI perimeter to hold light fittings. Item to be completed in all respect to the Architect's approval. Provision of Opening (openable) min 4 nos(for maintenance purpose) in ceiling as per site conditions are to be done with necessary timber frame work tied with perimeter channel properly such as to match the remaining area of ceiling by leveling perfectly complete in all	Sft.	797.00		
E	OTHER WORK				
1.0	Panelling (Mica finished) Providing and fixing wall / column paneling with 37.5mm x 25mm x 1.5 mm hollow aluminum square tube frame work covered by 6/12 mm thick BWP ply and finished with 1mm thick laminate / 1mm thick glossy mirror finish laminate pasted as per design and 100x12mm teak wood skirting polish finished including provisions for providing electrical switch box etc complete as per the tender specification . The work should executed as per as per Architect's recommendation & as directed by EIC. Cost includes all type of material, labour , necessary , staging , tools tackles, etc complete .	Sft.	208.00		



SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
2.0	Cheque drop box / Suggestion box				
	Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made. of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.Pteak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including. all free edges are to be finished with 1 mm thick laminate sheet of combination shade .Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel. paint of approved shade and quality over a coat of approved primer.Rate .to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved.designand quality.	Nos	2.00		
3.0	Writing platform for customers & application form set	Rft	3.00		
	Providing , fitting , fixing writing plat form at a height of 4' above floor level fixed to the wall made out of 19 mm BWP block board with lamination 1 mm tk on top & hard wood beading ducco painted . At least 10 nos vertical slip in chalan shelves attached to wall over writing platform made out of min 4 mm tk acrylic sheets with 6 mm tk ply back up. Each chalan shelf will be of size 6" height , 6" wide .The entire unit will be complete in all respect including materials ,labor etc to the satisfaction of consultant .				
4.0	Notice Board				
	Providing soft board covered with approved fabric with wooden frame work and decorative beading for display drawings and documents,with locking arrangementof the sliding shutter made up of 8mm th. flot glass. The work should be done including all labour and material.	Sft	10.00		
5.1	Vertical blinds				
	Supplying, fitting & fixing in position coloured 0.33mm thickness acrylic coated cleanable/ washable roller blinds (Marvel make) inclusive of all recommended accessories colour pattern etc., as per Architect's approval. The cost includes all the materials, labour, trasportation taxes etc., complete for the work.	Sft	122.00		



SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
5.2	Roller blinds				
	Supplying, fitting & fixing in position coloured 0.33mm thickness acrylic coated cleanable/ washable roller blinds inclusive of all recommended accessories, colour pattern etc., as per Architect's approval. The cost includes all the materials, labour, transportation taxes etc., complete for the work.	Sft	0.00		
6.0	Wall Putty work.				
	Providing and applying wall putty putty work punning in order to make the total plastered wall surface perfectly leveled , including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	Sft.	933.00		
7.0	Wall plastic paint.				
	Providing & applying 2 coats of plastic emulsion paint of royale ICI dulux & approved shade on wall, columns, beams, ceiling, etc. of back office hall including locker room, including preparation of surface, sand papering the intermediate coats, including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	Sft.	3,474.00		
8.0	Painting (Enamel paint)				
	Providing and applying a priming coat over steel/metal/wooden surfaces including preparation of surface by thoroughly cleaning oil, grease, dirt and other foreign matter and scoured with wire brushes, fine steel wool, scrapers and sand papers. Item also includes painting two coats of Synthetic Enamel paint of approved make and shade to give an even surface including cleaning all dirt dust etc. complete in all respect as directed by the Engineer in charge.	Sft.	673.00		
9.0	Façade of front entrance door.				
	Providing and fixing in position Aluminium composite panel boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5 mm – 3 mm – 0.5 mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow corning 789) masking tape, necessary scaffolding etc. as detailed in drawing complete in all respects. It also contain the shutter and lock system for the collapsable gate to hide at the entrance as per instruction of the architect. The work should be completed in all respect including all labour and material.	Sft	86.00		
10.0	Electrical Panel board cover				
	Providing and fixing of electrical panel board cover made up of 19mm ply with two shutter at the front having T.W luvvers as per drawing and design, it also have furnished with locking arrangement. The exposed surface is finished with 1mm. Th. Laminates and inner surface is finished with two cote of plastic emulsion paint over one coate of primer . The work should be completed including all hardware, material and labour.	Sft	28.00		



SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
11.0	Glazed display board.				
	Providing and fixing glazed display board as per design and instruction of architect of size 1'6"x2'-6" of 12mm th. Glass of edge polished and 1" edge beveled and fixed on wall with 1" SS stude as per direction . The work include all labour and materials.	Nos.	3.00		
12.0	Bank Logo				
	Providing,Fabricating and fixing in position of bank logo & branch name latter as per design (3'-0"x2'-0") in entrance area/B.M cabin of made out of 4mm thick acyclic sheet including cost of all labour and materials.	Set	2.00		
13.0	Textured Finished				
	Providing & applying a coat of textured finish on walls and columns. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats of approved make, quality & shade shall be provided.	Sft	70.00		
14.0	Dismantalling				
	Removing and demolishing existing partition , counter, glass etc as per direction in phase manner to not affecting the working condition of the branch. Complete the job in all respect i.e clening, removing the deamaged material out side the premises as per instruction, including all labour.	L.S	1.00		
15.0	Anti-termite treatment				
	Supplying, diluting and injecting Imidacloprid Chlorpyriphos or Equivalent approved chemical emulsion for POST-CONSTRUCTIONAL anti- termite treatment to total premises : a Along external wall where the apron is not provided using chemical emulsion @ 7.5 litres / sqm of the vertical surface of the substructure to a depth of 300 mm including excavation channel along the wall & rodding etc. complete using approved Chemical having concentration.as per manufacturer's recommendations.	Job	1.00		
	Treatment of soil under existing floors using chemical				
TOTAL					
INTERIOR WORK :-		Rs.			
GST @18%		Rs.			
TOTAL					

Total Amount in Words :-

