

**SCHEDULE OF SPECIFICATIONS AND QUANTITIES OF INTERIOR FURNISHING WORKS FOR ATM FOR HABRA BRANCH OF UCO BANK**

| SL NO. | DESCRIPTION OF WORK   | QTY         | UNIT | Rate Rs. | Amount Rs. |
|--------|---|-------------|------|----------|------------|
| 1      | Front wall Aluminium Frame fully glazed Main Door :   |             |      |          |            |
|        | Providing and fixing Aluminium frame with 12mm glass at the front wall comprising of appropriate 83.5mm vertical members, approximate 85-90 mm top & bottom , approximate 83.5mm middle member, Black powder coated. . 6 mm clear polycarbonate sheet with scratch free film on both sides. Wool pile / Weather strip on one vertical member. . Overall area of front wall is 64 Sq.Ft .The job also includes dismantling the present set up consisting of one glass door and rest portion fixed glass embedded into aluminium frame. | 70          | sft  |          |            |
| 2      | Painting of Rolling Shutter hood and side channels:   |             |      |          |            |
|        | Providing and painting on rolling shutter on both sides with cover hood with one coat of primer and two coats of synthetic enamel paint , including scrapping the surface with sirish paper   | 200         | sft  |          |            |
| 3      | FALSE CEILING ( 2' x 2' grid ceiling )  |             |      |          |            |
|        | Providing and fixing combination of grid false ceiling -2 ' x 2' (Armstrong or equivalent) with 12mm thick mineral fibre acoustic tiles with crisp.   | 56          | sft  |          |            |
| 4      | PAINTING WORK   |             |      |          |            |
|        | Supplying, applying putty with one coat of primer and two coats of emulsion paint on the walls ,including all about charges.  | 130         | sft  |          |            |
| 5      | NOTICE BOARD  |             |      |          |            |
|        | Supplying, fitting and fixing notice board of frameless double acrylic transparent sheet -2' x2'  | 4           | sft  |          |            |
| 6      | SWITCH BOX CABINET  |             |      |          |            |
|        | supplying, fitting and fixing cabinet for switch box, made of 19mm th. Blockboard and 1mm laminate with all necessary accessories,fittings and fixtures.  | 15          | sft  |          |            |
|        |   | GRAND TOTAL |      |          |            |
|        | (Rupees   |             |      |          |            |