

**SCHEDULE OF SPECIFICATIONS AND QUANTITIES FOR ELECTRICAL WORKS OF ATM AT HABRA BRANCH FOR UCO BANK**

ELECTRICAL WORKS					
SL. NO	DESCRIPTION	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Supply, laying connection of CAT-6 wire through PVC rigid pipe from HUB of ATM room. With IO Box and RJ 45	2	set		
2	Supply & installation of ATM power outlet points comprising of the following- 15A socket- 2nos., 16A switch with indicator- 2nos., 6m box & plate- 1set.	2	Set		
3	Supply & installation of SPN DB comprising of the following- 8way DB- 1no., 32A DP MCB- 1no., 16/25A SP MCB- 6nos.	2	Set		
4	Supply & installation of AC starter having starter 11-18A, 16A socket & 3pin plug top,	2	Set		
5	S/F of 4 x 6 + 2 x 1.5 sqmm CU wire through PVC pipe for UPS & AC line.	18	Mtr		
6	Light point wiring with 3x1.5 sqmm wire through PVC pipe.	6	Nos		
7	S/F of Recessed Light fixtures -6" dia down lighter.-LED -18 W	6	Nos		
8	S/F of 2 x 2.5 + 1 x 1.5 sqmm Cu wire through PVC pipe for AC and Sign Board	20	Mtr		
9	S/F of 2 x 1.5 + 1 x 1.5 sqmm Cu wire through PVC pipe for Raw Power Point with 6A Switch and Socket Modular	2	set		
	<b>TOTAL</b>				
	<b>( Rupees</b>				