

UCO BANK # SALT LAKE ZONAL OFFICE # BILKANDA BRANCH
B O Q FOR AIR CONDITIONING WORKS

SI No.	Description Of Item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
	SPLIT A/C WORK				
	Supply, Installation, Testing, Commissioning of Air-conditioning Systems (5 star- inverter) as follows (including 1 yr on site warranty)				
1	1.0 / 1.5 / 2.0 TR hi wall type BEE rated 5 star inverter technology split air conditioner with full function wireless remote and auto restart feature, with indoor/outdoor unit, gas charge, Copper condenser coils and Copper cooling coils company provided copper refrigerant pipe complete in all respects. Acceptable makes AC: Daikin / Blue Star / Hitachi				
a	Tonnage : 1.0 TR	1	unit		
b	Tonnage : 1.5 TR	4	unit		
3	Supply, installation, testing and commissioning of insulated copper refrigerant piping set (suction and discharge) with duly insulated by nitrile rubber for 1.5/2 TR AC. Size (thickness and dia) of both Copper pipe should as per recommendation of AC manufacturer's technical specification. (beyond 10'/machine)				
a	Set of two pipes for Hi-Wall units beyond 10'/machine	50	r. ft.		
4	Supply, installation, testing and commissioning of PVC 25 mm water pipe with accessories and taking care to prevent leakages, for water drainage in concealed manner either on wall or under floor including making good of damages.	70	r. ft.		
5	Supply, installation, testing and commissioning of inter connecting wiring/cabling between indoor and outdoor of hi wall split AC	70	r. ft.		
6	Supply and installation of bracket for outdoor units	5	unit		
7	Civil Work For cutting, Chisling, making holes in wall, Plastering of walls to conceal copper pipe, Drain pipe & Electrical wire including mending good with plaster finish.	5	unit		
	GRAND TOTAL				