

**Interior furnishing work, UCO BANK, Ayodhya chowk Branch**

BILL OF QUANTITY (BOQ)					
Sr.No.	Description	Qty.	Unit	Rate	Amount
4	<b>PAINTING &amp; PUNNING</b>				
4.1	Providing & applying POP on wall & column as per required and to give a smooth surface as per approval of the Architect.	100	sqm		
4.2	<b>Plastic Paint</b> : On Wall and Ceiling with the Base with POP punning to plumb level and 2 to 3 coats of Plastic emulsion on 2 to 3 coats of lappam and 2 coats of primer one before and one after lappam. All as per the instructions of the Architects.	100	sqm		
4.3	<b>APEX Cement based</b> of approved color and manufacture[ASIAN] to give an even shade including putty and priming coat with proper curing time. Surface to be sand paper cleaned and repaired, on old & new work. Etc complete in all respect to the satisfaction of Architect / Engineer .	100	sqm		
4.4	<b>Synthetic Enamel Paint</b> : For window, Grill, Rolling Shutter, & Collapseable Gate	50	sqm		
	Applying synthetic enamel paint, 2-3 coats , with base coat of metal primer. Complete with finishing.				
5	<b>PARTITION WORK:</b>				
5.1	<b>SOLID PARTITION WITH DOOR</b>				
	Providing & fixing 3" thick solid partition for made up of 18 gauge 50x50 mm Aluminium section framework at 600 mm c/c both ways (or as directed by the Architect); 12 mm HDMR & 1 mm laminate from both sides. Partition should be finished with specified finish as per design. The rate includes providing 35 mm thick flush door with necessary lipping patti polished. Rate includes all necessary hardware ( i.e ball bearing hinges of approved make, door closure, Cylindrical Lock with key, Door stopper etc) Exposed edges of the partition should have 75x12 mm matching wood Patti with groove in between. All provisions to be made for all electrical, networking, telephone etc. boxes onto partition framework at required heights/levels with necessary additional supports &/or scaffolding as required. The rate includes all necessary hardware & cleaning of partition to the satisfaction of the Architect etc. complete	24.25	sqm		
5.2	<b>Main Entrance Door with Partition</b>				
	Providing & fixing main door & partition made up of 12 mm thk. Clear toughened glass shall be fixed in.Ozon / Enox make patch fitting with necessary hardware.With application of sealant from all sides. Edge polish for all exposed sides of glass. Complete as per design Door size 7'0" x 3'0" - Providing & fixing main door made up of 12 mm thk. Clear toughen glass shall be fixed in.Ozone / Enox make patch fitting with necessary hardware like floor spring, 12" S.S. finished decorative handle pair,& locking arrangement. Edge polish for all exposed sides of glass. Complete as per design	18.4	sqm		
5.3	<b>4' htPARTITION</b>				
	Providing & fixing 3" thick partly glazed partition with 10mm thick clear float glass for made up of 18 gauge 50x50 mm Aluminium section framework at 600 mm c/c both ways (or as directed by the Architect); 12 mm HDMR & 1 mm laminate from both sides. Partition should be finished with specified finish as per design. The rate includes providing 35 mm thick flush door finished with 1mm laminate of approved make/shade on both sides with necessary lipping patti polished. Rate includes all necessary hardware ( i.e ball bearing hinges of approved make, door closure, Cylindrical Lock with key, Door stopper etc) Exposed edges of the partition should have 75x12 mm matching wood Patti with groove in between. All provisions to be made for all electrical, networking, telephone etc. boxes onto partition framework at required heights/levels with necessary additional supports &/or scaffolding as required. The rate includes all necessary hardware & cleaning of partition to the satisfaction of the Architect etc. complete Basic rate of 12mm thick ply: ---104----- Rs /sft. Basic rate of Laminate; -----35--- Rs/sft	0	sqm		
5.3	<b>SEMI GLAZED PARTITION WITH DOOR - CASH CABIN</b>				
	Providing & fixing 3" thick partly glazed partition with 10mm thick clear float glass for made up of 18 gauge 50x50 mm Aluminium section framework at 600 mm c/c both ways (or as directed by the Architect); 12 mm HDMR & 1 mm laminate from both sides. Partition should be finished with specified finish as per design. The rate includes providing 35 mm thick flush door finished with 1mm laminate of approved make/shade on both sides with necessary lipping patti polished. Rate includes all necessary hardware ( i.e ball bearing hinges of approved make, door closure, Cylindrical Lock with key, Door stopper etc) Exposed edges of the partition should have 75x12 mm matching wood Patti with groove in between. All provisions to be made for all electrical, networking, telephone etc. boxes onto partition framework at required heights/levels with necessary additional supports &/or scaffolding as required. The rate includes all necessary hardware & cleaning of partition to the satisfaction of the Architect etc. complete Basic rate of 12mm thick ply: ---104----- Rs /sft. Basic rate of Laminate; -----35--- Rs/sft	6.64	sqm		
5.4	<b>Wooden panelling</b>				
	Providing & fixing Panelling on existing walls as per design & drawing with sub- frame of size 25mm x50mm Aluminium frame,18 gauge @ 600mm x 600mm c/c vertically & horizontally . The frame to be fixed in walls with screws and wooden gutties. The panelling made of 12mm thick HDMR PLY finished with 1mm thick laminate. , Top edge shall be finished with 12mm thick steem beech wood lipping finished with melamine polish. Rates to include necessary notches in frame on carrying electrical conduit and switch boxes. It includes design & grooves in laminate as directed by Architect/Bank, includes providing Steembeechwood moulding, lacquer polish on top of low height panelling wherever necessary etc, complete in all respect to the satisfaction of Architect/ Bank.	101	sqm		
5.5	<b>Aluminium composite panelling</b>				
	<b>Aluminium composite panelling:-</b> Providing & fixing Aluminium composite paneling in standard aluminium frame as per manufacturers specifications, Aluminium sections of Jindal of standard sections and frame as per manufacturers specifications, Aluminium sections of Jindal of standard sections to be used. Aluminium composite panel specifications:-	#####	sqm		

Panel-AL-45,Thickness-4mm, width 1220mm, length-3660mm, foil thickness-0.50mm, Surface coating-  
PVDF, Application- Interior.Brand – Alucobond/ Alstone.[ note:-color of exterior grade ACP sheet shall  
be decided by bank/Architect.

6 FURNITURE WORKS


<b>6.3 Manager Table ( 6'0" x 2'6" x 2'6" ):</b>				
Providing & fixing table made up of 18 thk. Comm. Plywood frame with <b>10mm. thk. Clear glass on top.</b> The table should be finished with 1.0 thk. Laminate on exposed HDMR frame, inside edge of holes, polish from inside. The table shall be provided with single drawer, ply key board drawer ,ply C.P.U. trolley with ply footrest, wire manager ,& other required hardware. The glass shall have plain diamond edge polish on all four sides & <b>hole for wire manager.</b> The glass should cover the length of the table & width of side unit as shown in the drawing. Basic rate of 18mm thick ply: ---144/----- Rs/sft, . Basic rate of Laminate: ---45/----- Rs/sft	1	no		
<b>6.2 Side Units: size 3'x2'6" ht</b>				
Providing & fixing side unit made up of 18mm. thk. plywood framework & 6mm. thk. HDMR PLY as backing. Side unit should have 2 no. of drawers above & shutters below. Drawers should be made up of 18 thk. HDMR fascia, 12 thk. HDMR PLY sides & 6 thk. HDMR PLY bottom. Drawers should be mounted on heavy duty drawer sliders. Side unit should be finished with 1.0 mm. thk. Laminate of approved shade & colour on external surface & oil paint to non laminated surface. All exposed edges of 18 thk. & 12 thk. HDMR PLY should have lipping patti STEM BEECH All lipping patti's should be finished with paint/French polish on it. The cost should include necessary hardware, handles, Godrej make locks with common handles, Godrej make locks with common key for set of drawers etc. complete as per design. Drawers to be made of 12 mm thick comm. plywood and finished with laminate on front and enamel painted inside. Basic rate of 18mm thick ply: --144----- Rs/sft, Basic rate of 12mm thick ply: ----108----- Rs /sft. Basic rate of Laminate; -----35--- Rs/sft	1	nos		
<b>6.4 Writing Desk/ slip counter</b>				
Providing & fixing writing desk made up of 18 thk. Double HDMR PLY supports as shown in the drawing. HDMR PLY supports shall be finished in laminate on it. from both sides & to edges with groove (kani) at corners. The frame shall have 6mm thk. Plywood back & it should be finished with laminate. The desk shall have 12mm. thk. Clear glass with plain diamond edge polish & with round corners on front side. 12 thk. Glass shall be fitted with D-brackets on partition & rubber vacuums on plywood supports. The desk shall have 8mm. thk. Clear glass with plain diamond edge polish from all four sides. This glass should be fitted on D-brackets. The writing desk will be of hanging type as shown in the drawing. The rate should be fitted on D-brackets. The writing desk will be of hanging type as shown in the drawing.	1	No		
<b>6.5 Suggestion Box</b>				
Providing & fixing box made up 18 mm. thk. HDMR PLY framework, 6/12 mm. thk. plywood back as required as per design. Good quality blackboard shutters should be fixed on brass hinges should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminated surfaces. All exposed edges of HDMR PLY should have lipping patti on it. Lipping patti should be finished with French polish on it. The cost should include necessary handles, magnetic catches, Godrej make locks etc. complete as per design.	1	Nos		



Date: