

## TENDER NOTICE

Undersigned invites sealed limited tender from empanelled contractors (Except for contractors where tender are terminated) of our zone for Furnishing work and electrical work of Branch at:

<b>ATTA GORAYA BRANCH</b>	<b>SITUATED AT GORAYA, JALANDHAR</b>
---------------------------	--------------------------------------

Tender documents will be issued from our Zonal Office i.e. SCO 113-114-115, Master Tara Singh Nagar Market, Near BSNL Exchange, Jalandhar or can be downloaded from UCO Bank website: [www.uco.bank.in](http://www.uco.bank.in), and to be submitted along with a fee of INR 500/- (Rs. Five Hundred Only) in the form of Demand Draft favouring UCO Bank.

Opening date of Tenders receiving is **30.03.2026** and last date of receiving Tenders will be **13.04.2026 till 5:00 P.M.** Tender will be opened on **14.04.2026 at 11:00 AM** at our Zonal Office, i.e. SCO 113-114-115, Master Tara Singh Nagar Market, Near BSNL Exchange, Jalandhar.

  


**Assistant General Manager**

To

M/s \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

**ONLY EMPANELLED CONTRACTORS OF UCO BANK AT JALANDHAR ZO CAN APPLY**

ISSUED TO M/S \_\_\_\_\_

## **TENDER DOCUMENT**

### **FURNISHING OF UCO BANK BRANCH** **AT GORAYA.(PB).**

**OFFICE OF THE  
ASSISTANT GENERAL MANAGER  
UCO BANK, Z.O. S.C.O. NO. 113-115, 1<sup>st</sup> FLOOR,  
Master Tara Singh Nagar.Opp.D.C.Office,Jalandhar - 144001**

**ARCHITECTS :**



**S.C.O-283,SECTOR-35 D,  
JALANDHAR  
PHONE : 0172-2601465 (o)  
MOBILE : 09417495655,8837895110.**

Date of submission of tender: 13.04.2026 upto 5.00 PM  
Date of opening of tender: 14.04.2026 upto 03.00 PM  
(Tenders to be submitted in the office of AGM, UCO Bank, Z.O., Jalandhar)



## DETAILS OF TENDER

### **TENDER FOR THE FURNISHING OF UCO BANK BRANCH AT GORAYA.(PB.)**

1. Details of work to be done : Interior / Furnishing & Allied Electrical works for UCO Bank, At Goraya.
2. Form of Contract : Item wise rate
3. Earnest Money : Rs. 13,500/- (Thirteen thousand five hundred only) in form of Demand draft in favour of Uco Bank payable at Jalandhar.
4. Period of contract / Time of Completion : 4 Weeks
5. Last Date & time for receiving: Of sealed tender. **13.04.2026 upto 5.00 PM**
6. Liquidated damages for non-Completion of work in time : 1.0% of the contract value per week subject to a max of 10% of the contract value.
7. Defect Liability Period : 12 months (Twelve months) from the date of virtual completion as certified by Architect / employer.
8. Retention amount for 12 months: 8% of the total bill.
9. Period of submitting of Final bill. : 15 days from the date of completion.
10. Mobilization Advance / Secured Advance : No. Mobilization Advance / secured Advance will be given to the Contractor.
11. Place and date of opening of tender : UCO Zonal OFFICE Jalandhar 14-04-2026 upto 3:00 p.m. in Office of the AGM, Uco Bank,Zonal Office, S.C.O. 113-115, 1<sup>ST</sup>. Floor, Master Tara Singh Nagar. Opp. D.C. Office,Jalandhar - 144001.



**Asst General Manager, UCO Bank,  
JALANDHAR**



## **TENDER FOR THE FURNISHING OF UCO BANK BRANCH AT GORAYA.(PB.)**

### **GENERAL CONDITIONS**

1. The Contractor shall sign each page of this tender.
2. Payment to the Contractor Agency shall be made as per actual work done at site.
3. Quantity of work may increase or decrease at site as per requirement, which shall not affect the rates quoted by the contractor.
4. Furnishing works including electrical works etc. shall be done to the complete satisfaction of Bank and Architect-in-charge.
5. All teak / Cedar wood / rubber wood to be used should be knotless which is to be polished with all background surface preparation coarses maintaining the visibility of wood grains.
6. The rates to be quoted shall include the cost of material, labour charges, carriage, sales tax, or any / all other taxes any required hardware etc.
7. The contractor agency shall keep particular vigil on his workers / carpenters / painters etc. to maintain very good workmanship of all items, failing which no payment shall be made and no claim of material / labour used shall be made to him in any case, and the same work shall be executed by him again without charging any extra cost.
8. All rates shall be quoted in words & figures & any cutting over writing shall be signed.
9. All items to be executed as per drawings, if any change is required, the same shall be brought to the notice of Architect-in-Charge.
10. Any tender / quotation containing clerical or arithmetical mistakes shall be rejected.
11. Any addition, alteration or correction shall be signed and stamped properly.
12. Contractor agencies are advised (before quoting the rates) to inspect the site of the proposed work. He must go through all drawings and specifications and documents.
13. The Bank reserves the right to accept / reject any tender / quotation without assigning any reason.
14. The Contractor agency should have already executed works of furnishing interiors & exterior, civil works of very good workmanship.
15. Quality of material and workmanship rejected by the Architect / Concerned Authorities shall be removed immediately by the contractor and rectified / replaced.
16. No advance payment shall be made to the Contractor on supply of any material supplied at site for execution. Payment shall only be made on execution of any concerned / particular item.
17. The rates shall include the cost of coat of anti termite treatment on all wooden frame work and all commercial ply / board used for partitions and paneling, furniture etc. The contractor/s shall have to dismantle & dispose the existing counters, tables & partitions within the quoted cost of the total furnishing works.
18. Rates for partitions, paneling, wall cladding and false ceiling shall include cutting and making good of necessary cut-outs/chiseling to be made for electrical conduits, switch boards etc.
19. Bank shall not be responsible for any lose or damage to the contractor/labour due to any natural calamity during the course of construction. Contractor is liable to make good all the damages if any, till the work is completed and handed over to the Bank authorities.
20. Any payment to the contractor on account of execution of work, whether it is running payment or final, shall be verified by the Architect-in-Charge.
21. Unless, otherwise mentioned all materials to be used shall be I.S.I. marked. Failure to do so, the work may be rejected and in that case contractor shall have to remove the defective materials and replace / re-do the work for which no claim shall be entertained.
22. The total work shall be supervised by the Architect-in-Charge and he/she shall be kept fully informed by the contractor regarding the progress of work.
23. Bank may award the work in part or whole to a single party or any other party.
24. It may please be noted that the Bank is not bound to allot the work to the lowest party. And as such, the allotment of work shall be based on workability of rates quoted by the contractor on account of quality work.
25. The bank reserves the right to reject any or all the tenders without assigning any reason whatsoever.
26. The earnest money deposited shall not carry any interest and will be refunded to the unsuccessful tenderers.



27. Earnest money paid by the contractor shall be forfeited by the Bank if contractor fails to undertake the job if he is communicated about acceptance his rates/tender.
28. The contractor shall take all the necessary precautions while working and to safe guard adjacent property, Bank's property, Bank's Employees, and traffic persons.
29. All the rates quoted are inclusive of removal of existing counters, partitions, wiring, rubbish/ debris collected during the progress of work, rejected materials etc.
30. The contractor shall not directly or indirectly sublet the work to other party without written permission of the Bank.
31. The quantities mentioned in schedule are provisional and likely to increase/decrease to any extent or may be omitted thus altering the aggregate value of the contract. No claim for loss of profit / business shall be entertained on this account.
32. The Bank reserves the right to distribute the work for which quotations have been called, among more than one parties, if found necessary. No claim in this respect shall be considered and the contractor agrees to cooperate with other agencies appointed by the Bank.
33. All the workers of the contractor must be properly covered by an insurance policy under "Workman's Compensation act" and "Fatal Accidents Act". The contractor at his own expenses arrange to effect and maintain until the virtual completion of the contract, insurance policy in the joint name of Bank and the contractor against this risk to be retained by the Bank until the virtual completion of the work, and indemnify the Bank from all the liabilities arising out of such events. In case of delay, contractor shall arrange to extend insurance policy till work is completed.
34. All the work should be completed within the specified period in the tender. If the work is delayed due to the reasons beyond the control of the contractor, he should keep intimating the Bank explaining, therein the reasons for such delays, immediately and if in the opinion Bank's authorities the delay is justified, the contractor shall be granted extension in time limit.
35. The contractor shall furnish well in time before work commence at his own cost, colors, samples of materials or workmanship that may be called by Bank's Architect / Engineer for approval. Rates quoted shall cover for such preliminary work.
36. All the glass panes, door handles/ hinges, electric fittings, fans, furniture, records, floors etc. are to be thoroughly cleaned after the work is completed.
37. The rates quoted by the contractor shall be firm throughout the duration of contract (including extension of time if any granted) and will not be subject to any fluctuation due to variation in cost of material and labour.
38. Conditional tenders are liable to be rejected.
39. The successful tenderer is bound to carry out any item of work necessary for the completion of the job even those such items are not included in schedule of quantities.
40. If in any case of work required to be abandoned, the contractor shall not be entitled for any claims and he will be paid as per the actual work done till that period, if deemed fit.
41. Decision of the Bank shall be final and binding on any matter connected with the work. The matter of any dispute shall be decided after mutual discussions based on the terms and conditions of this contract. However, if the matter cannot be resolved then the same shall be referred to the respected qualified person in agreed to both the parties and his opinion shall be binding on both the parties. However, this is precourse to any legal action in this regard.
42. If at any stage during the progress of work, it is observed that the contractor is not progressing the work with due diligence, care of lagging much behind the schedule or fails to gear up the work despite instructions from Bank's Architect, the Employer (Bank) reserves the right to terminate the contract with 7 days notice. In such case the contractor shall be liable to pay the Employer any extra cost involved for the completion of the said work and will not obstruct any way in completing the work through other agency. After completion of entire work the contractor shall be paid for the actual work executed by him at the quoted rates after deducting any claims, damages. In case of such termination the security deposit held by the Bank will be forfeited.
43. Contractor shall follow all rules / regulations in force and should posses the license for employing labour and also follow all safety measures, labour bye laws and shall be responsible for any lapse.
44. At any stage i.e. during the execution of work, any kind of change reqd. whether it is in design or specification, the same has to be in-corporated by the contractor.



**TENDER FOR INTERIOR, FURNISHING & ELECTRICAL WORK FOR  
UCO BANK BRANCH AT GORAYA.(PB.)**

Grand Summary:-

<b>S.No.</b>	<b>Sub Head</b>	<b>Amount (Rs.)</b>
<b>A.</b>	<b>FURNISHING WORKS</b>	<b>Rs.</b>
<b>B.</b>	<b>ELECTRICAL WORKS</b>	<b>Rs.</b>
	<b>SUB TOTAL</b>	<b>Rs.</b>
	<b>DISCOUNT (IF ANY)</b>	<b>Rs.</b>
	<b>TOTAL AMOUNT</b>	<b>Rs.</b>

**GST Extra as applicable.**

Rupees                  Lacs                  Thousand                  Hundred                  Only

***Signature of the Contractor***



**RECOMMENDED MAKE TO BE USED FOR THE INTERIOR WORKS OF  
UCO BANK BRANCH & ATM AT GORAYA.(PB)**

S.NO	DESCRIPTION	MAKE/BRANDS
1.	Plywood (M R Grade)	Bhutan Tuff , Green Ply, Century Ply Wood ,Kit ply, Archid, Truewood.
2.	Laminates(1mm thick)	Greenlam,Aica,Merrino, Amulya,Archid.
3.	Lipping & Moulding	Teak Wood/Steam Beach Wood
4.	HDHMR Board	Green / Kitlam/Action Tasa / Century / Duro / Archid.
5.	Adhesive	For Wood- Fevicol SH,Vemicol-HV., For Glass & Granite - Araldite, For Lacquered Glass - Silicon (Dow)
6.	Locks	Godrej/Harrison/Ebco/ Hettich,Vision .
7.	Night Latch	Godrej.
8.	Glass	Modi / Triveni / Saint Gobain,Asahi,Glaverbel.
9.	ALUMINUM SECTION	JINDAL,INDAL, HINDALCO.
10.	Aluminum Cladding	Eurobond / Altobond / Alukbond.
11.	Suspended Ceiling & sections	INDIA GYPSUM, Saint Gobain,USC,Boral,Dexune.
12.	PPGI Metal sheet / Grid Tile & sections	Armstrong including their suspensions
13.	Door Closer & Floor Spring.	Godrej/Ozone/ Dorma/Yale/Hafele..
14.	Paint	Nerolac / ICI Dulux./ Asian/Berger.
15.	Wood Preservative	Bison by British Paints / Termiseal by ICI.
16.	Wood	Well Season partal / Gumar / Badam/kail.
17.	Drawer Channel	EARL BIHARI,Ebco, Vision,Hassle.
18.	Screw	Nettle fold, Ozone, Dorma,Self
19.	Key Board Drawer	EBCO, EARL BIHARI.
20.	Telescopic CPU Stand /Trolley	EBCO, EARL BIHARI.
21.	Cable Organiser	EBCO
22.	Polyurethan foam	Dunlop
23.	Texture paint	Spectrum / Heritage/British paint/Kilurk Nixon.
24.	Venetian / Vertical Blinds	Vista Levelor / Mac. / Hounter Douglas
25.	Lacquered Glass.	Saint Gobain. - (Approved Shade only).
26.	Tapestry / leather form	Harmony, Vimal, Bhor.
27.	Vinyl Film / Frosted / Printed film	3 M
28.	Patch Fitting & Floor Spring for fixing frame	Dorma / Godrej/Ozone
29.	Flush Doors	Duro/Green/Century
	<b>ELECTRICAL LIST OF APPROVED MAKES OF MATERIALS</b>	
S.NO	DESCRIPTION	MAKE/BRANDS
1.	PVC/MS CONDUIT PIPE (ISI) MARKED	BEC / PRECISION / AKG / SETIA/CAP
2.	WIRES 1100V GRADE FR/FRLS MULTI STRANDED ONLY-ISI	FINOLEX/ SKYTON/ POLYCAB/ BONTON/ RR KABEL/KEI/RELISONS/ESC
3.	CABLES 1100V PVC INSULATED FRLS XLPE	SKYTON/ BONTON/RELISONS/ KEI/ GRANDLAY/POLYCAB/FINOLEX/ESC
4.	MCBS, MCCBS & ELCBS	SCHNIDER/ LEGRAND/ L&T-HAGER/ ABB/ C&S/HPL/
5.	MOULAR SWITCH, SOCKET, PLATES, BOXES & OTHER ACCESSORIES (MDEL MENTIONED)	LEGRAND- Linc/ Mosaic/ CRABTREE-Athena/ PHILIPS-Elite / MK - Wraparound/ North West- Stylus only /Anchor – Woods/Viola/ Simon-Vivid-38/ Great White-Myraha
6.	FLUORESCENT/LED/CFL LUMINAIRES	PHILIPS/CROMPTON/ BAJAJ/TRILUX/ /HAVELLS /HELONIX/WIPRO/EVEREADY/HPL
7.	METAL CLAD SOCKET OUTLETS	ABB/ L&T/ LEGRAND/ NORTH WEST/C&S
8.	TELEPHONE CABLE	DELTON/AMP/D-LINK/FINOLEX



9.	BAKELITE SHEET	HYLAM / FORMICA/
10.	SOLDERLESS LUGS / FERRULES	DOWELL/
11.	CABLE GLANDS	COMET /GRIPWEL/ DOWEL
<b>S.NO</b>	<b>DESCRIPTION</b>	<b>MAKE/BRANDS</b>
12.	TAG BLOCK (TELE)	KRONE
13.	DISTRIBUTION BOARDS (DOUBLE DOOR TYPE)	INDOASIAN/SCHNIDER/ LEGRAND/ L&T-HAGER/ ABB/ C&S/
14.	JOINTING KITS/ CONNECTORS	SCREWLESS WAGO & CONTROLS (I) LTD/3M/RPG
15.	METERING EQUIPMENTS	RISHAB/ AE/ CONZERV/L&T/SECURE
16.	ASS/VSS	KAYACEE/ L&T/
17.	FANS	Crompton/BAJAJ/USHA/Havells/Orient
18.	LAN & VOICE	AMP/ D-LINK
19.	VOLTAGE STABILIZER & AC TIMER	RITLINES/ BLUE BIRD/ LOGICSTATE/ INLINE/V-GAURD/SERVOKON/SERVEL/RUPTRONICS
20.	FIRE EXTINGUISHERS	Cease Fire/Safex / Minimax/Zenith .
<b>AIR CONDITIONING LIST OF APPROVED BRANDS / MAKES</b>		
1.	AIR CONDITIONING UNIT WITH 5 STAR RATING	Hitachi/Daikin/Carrier/Voltas/Blue star
2.	GSS Sheet	Jindal / Tata / Sail
3.	Factory Made Ducts	Rollastar / Nutech
4.	Propeller fans	GE/Alsthom/Crompton/carrier
5.	Flexible pipe connection	Resistoflex / Dunlop
6.	Extruded Aluminum Grilles /Diffusers	Pine air/Balance/Tristar/ carrier
7.	Fire dampers / Volume Control Dampers	carrier /Pine air/Balance/ Tristar
8.	Flexible insulated ducts	carrier / ATCO/ MAPRO
9.	Fibre glass	OWENS CORNING/ UP TWIGA
10.	Extruded Polystyrene Board	SUPREME
11.	Cross linked polyethylene	SUPREME/A-Flex/Aeroflex
12.	Class 'O' Nitrile rubber insulation	SUPREME /K-FLEX / SUPERLON /EUROBATEX / ARMACELL/A-Flex
13.	Copper Pipe	RAJCO / MANDEV / MAXFLOW / Total Line / Shree Shayam
14.	PVC PIPE	SETIA/ FINOLEX/ PRAKASH/ SURYA
15.	Conduit of Electrical wires	AKG, SETIA, BEC
16.	Expanded polystyrene	Styrene Packing / Indian Packing
17.	Vibration Isolation Spring	Dunlop / Resistoflex
18.	Paints	ICI / Asian
19.	Dash Fasteners	Canon / Fisher / TKS/Hilti
20.	Welding Rods	Advani / L&T
21.	ACB, M.C.B., & MCCB	L&T / GE / Crompton
22.	Power/Control Cable	ICC/ CCI/ Gloster / Grandlay/ Universal
23.	Centrifugal / Axial Fans	ABB / Kruger / Comfrei / Nuaire (UK)
24.	Inline Fans	Kruger / Nuaire / Ostberg / System air/ carrier

**Note:-**

1. Work will be carried out as per tender specifications / drawings and instructions of Architect .
2. Work shall be done as per CPWD / tender specifications / drawings & instructions of Architect / Bank's Engineer & material shall be of the make as mentioned above & of ISI mark.
3. Bank may ask for the bills / cash memo of various items purchased by the Contractor from the market, for its satisfaction.
4. All other Materials shall be best quality heavy section mentioned in the bill of quantities and also approved by Architect.

Signature of contractor



NAME OF WORK : PRICE BID OF FURNISHING OF UCO BANK BRANCH & ATM AT GORAYA.(PB)					
PART -A (INTERIOR WORKS)					
<p><b>Note: (i) For the works of paneling, full height partitons and low height partitons measurement shall be done only for plain visible surface, no extra cost for extrusions or extra frame work required will be made. The work done above ceiling, below floor finish level or not directly visible shall not be measured.</b></p>					
<p><b>(ii) All ply to be sprayed with anti terminate and anti borer spray.</b></p>					
S.N	Item of Work	Qty	Unit	Rate	Total Amount
1.	<p><b>Main Entrance Door &amp; Manager Cabin Door.</b>  <b>a)</b> (Toughened Glass 12.0 mm thk. with etching )            Providing &amp; fixing frameless fully glazed 12.0 mm thk. toughend float glass single leaf /Double leaf glazed Toughened door of size approximately, 4'-0" to 3'-0"X 7'-0" all sides edge grinded, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accommodate fitting etc. the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant where ever required and SS cover over patch fittings to accommodate toughened glass of above items - Hardware viz: PT1040 forover/side panel,PT 1041 connector for Side/Upper Panel,PT1020 Upper patch,PT1010 Bottom Patch,PT1049 E floor Lock ,PT1052 Strike Plate Floor Spring BTS 84 - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, etc. all complete of godrej / dorma/Hettich. the rate shall be include etching film / logo (etching with Birla 3M film digital lazer cut ) all inclusive, complete in all respect. (Note: In case of false ceiling, the vertical members to be fixed below R.C.C slab but the area of Glazing payable will be below the false ceiling only).</p>	70.00	Sq.ft		
	<p><b>b)</b> <b>12mm clear float toughened Glass fixed partition :-</b>            Providing and fixing in position 12mm clear float toughened Glass partition with patch fittings for the full height glass partitions as per the direction of the Architect/ Engineer-in-charge. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., then toughen the same. The cost to include all hardwareviz: PT1040 forover/side panel,PT 1041 connector for Side/Upper Panel,PT1020 Upper patch,PT1010 Bottom Patch,PT1049 E floor Lock ,PT1052 Strike Plate Floor Spring BTS 84 (PATCH FITTINGS etc) required of <b>Ozone/ Hettich/ GODREJ</b> or approved equivalent make etching film / logo (etching with Birla 3M film digital lazer cut ) as per design and drawing. The</p>	150.00	Sq.ft		

	maximum size of each glass shall be 1200mm to 2000mm x 2400mm to 2700mm as per the site requirement. The rate is for a finished item of work etc., complete as directed. The cost to include the cost of bevelling and smoothing of the exposed edges of the glass.				
2	<p><b>WALL PANELLING :-</b> Wall paneling to be providing in Banking hall on as marked on drawing, made from aluminium frame work using aluminum sections of 1.5"x1.0" - 1mm thick Jindal/ Indal make work Properly fixed to the Wall or Column with proper Spirit level. Frame work to be covered with 8mm thick Plywood of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) of century, green make and 1 mm laminate as per color scheme of the bank. 35mm X 12mm steam beach Lipping to be provided to all the edges . Complete job including melamine polish on edge beading/Cornices etc. and painting of grooves in approved colour. All job to be done to architects' satisfaction/ as per bank direction .</p> <p><b>BANKING HALL:-</b> Wall paneling Ht : 4'-0", Centre pillars to be cladded upto ceiling bottom "(i.e. + 9'-0 level) ,</p> <p><b>(Note: the area under storage or table, side credenza shall not be counted in wall paneling. only visible area will be payable).</b></p>	400.0 0	Sq.ft		
3(a)	<p><b>FULL HEIGHT SOLID PARTITIONS:-</b> Providing and fixing full height partitions of 44 mm X 44 mm X 16 Gauge aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically &amp; horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rowel plugs / steel plugs . 8 mm thick Ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the bank. doors with lock is to be providing as per drawing and fixed with Steam beach molding duly melamine polished/paint. 35mm X 12mm steam beach Lipping to be provided to all the edges of the door. All wood to be painted in wood preservative. The rate include making provision for electrical conduits and switch boxes. All job to be done as per architects satisfaction/ bank direction . Note: (In case of false ceiling, the vertical members to be fixed below R.C.C slab but the area of partition payable will be below the false ceiling only).</p>	360.0 0	Sq.ft		

b)	<b>PARTIALLY GLAZED PARTITIONS:-</b> Providing and fixing full height partially glazed partitions of 44 mm X 44 mm X 16 Gauge aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rowel plugs / steel plugs . 8 mm thick Ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the bank. <b>12 mm Toughend Glass</b> to be provided between the partition as per drg. and fixed with Steam beach molding duly melamine polished/paint. 35mm X 12mm steam beach Lipping to be provided to all the edges of the door. All wood to be painted in wood preservative. The rate include making provision for electrical conduits and switch boxes. All job to be done as per architects satisfaction/ bank direction . Note: (In case of false ceiling, the vertical members to be fixed below R.C.C slab but the area of partition payable will be below the false ceiling only).	100.0 0	Sq.ft		
c)	<b>LOW HT. PARTITION FOR COUNTER SEPARATION:—</b> Providing and fixed low height partitions made of 44 mm X 44 mm X 16 Gauge aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as wall with rowel plugs / steel plugs . 8 mm thick ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the bank. <b>12mm thick Toughend glass</b> to be provided on the Top of Partition. Teak wood beading 1 ½ " X 3 ¼"( melamine polished ) around partition edges complete in all respects. height : 4'-0"	120.0 0	Sq.ft		
d)	<b>12 MM thk. toughend glass for Banking / SWO Counters with Etching. - front &amp; Sides.:</b> Providing and fixing 12 mm thick, clear plain toughened glass of fixed in vertical position at counter level & to side partitions as per drawing, the counter top glass fixed on both sides to toughened glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded and polished complete in all respects	30.00	Sq.ft		

4(a)	<p><b>CASH CABIN'S SIDES:-</b> providing and fixing side and back partition for Cash cabins ( ht. 7'-0" ) made of with Aluminium frame work of 2.5"x1.5"x 1.0mm thick section with 2'0"x2'0" c/c vertically and horizontally. Frame to be covered with 8 mm plywood from both sides. 1mm thick laminate to be covered from both the sides of the partition. <b>Glass (12mm thick toughend)</b> with etching as per design and doors with lock is to be providing as per drawing and fixed with Steam beach molding duly melamine polished. 35mmX 12mm steam beach Lipping to be provided to all the edges of the door. Frame should be properly fixed to the Floor. Also providing for cheque transfer ( 3"x6'-9" ) made of partal / kailwood frame with 8mm thick ply laminated with 1.0 mm thick laminate is provided. All exposed surfaces to be properly polished / painted to approved colour. All work to be done as per design including lipping / moulding/ beading ( melamine polished ) around door edges and partition edge complete in all respects. as per color scheme of the bank.</p>	100.00	Sq.ft		
b)	<p><b>CASH CABIN'S FRONT PARTITION:-</b> Providing and fixing <b>Glass (12mm thick toughend)</b> over cash counter in front partition 4'-0" height upto 7'-0" along with 1 ½" X ½" teakwood beading polished to matching laminate colour along with 1 ½" X ¾" decorative moulding / beading / lipping ( melamine polished ) at partition edge, complete in all respects.</p>	20.00	Sq.ft		
5	<b>Hardware</b>				
a	Providing and fixing of Godrej /Harrison night latches in cash cabin doors as per the directions of the Bank.	1.00	Nos		
b	Providing and fixing of Mortice locks of approved make (Godrej /Ozone/Hettich/ Dorma) in UPS,ATM, Record Room, etc. as per the directions of the Bank.	5.00	Nos		
c	Providing and fixing hydraulic door closures Silver colour of approved make(Godrej /Ozone/Hettich/ Dorma) & color.	5.00	Nos		
6	<p><b>Cash counter 's with 1½" thick post-form factory made Tops (HT. 4'-0" &amp; 2'-6")</b> Providing and fixing cash counter with 1½" thick post-form factory made Tops 2'-6" wide having working top at + 2'-6" and 12" wide customer top at + 4'-0" and rest counter made of 19MM thick commercial Ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) finished with 1.00 mm thick vertical laminate and 1.00mm thick horizontal laminate of specified. One keyboard drawer ( Size 2' x 1'x3") three cupboard drawers ( size 1'-3" x 1'-6" x 6" – 2 Nos. 1'-3" x 1'-6" x 1'-0" – 1 No.) with proper sliding arrangements, and auto lock are provided along with storage unit ,one drawer to have provision for storing cash,<b>ready made powder coated CPU stand</b> , foot rest 3" x 1 ½" are provided below the main working top. Customer top has depressed portion ( 7" x 13"x4") lockable from</p>	5.00	R.Ft		

	inside for cash transfer. The counter will have all necessary hardware, decorative jalli pattern, laminate band and teakwood / partial wood beading/ moulding. Recessed skirting ( ¾") finished with 1.0mm thick laminate . All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish. All work is done complete in all respects.				
7	<b>C.T.O &amp; Officer's Counters with 1½" thick post-form factory made Tops :-</b> 2'-6" wide having working top at + 2'-6" made with 1½" thick post-form factory made Tops and rest counter made of 19MM thick commercial PlyBWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) finished with 1.00 mm thick vertical laminate and 1.00mm thick horizontal laminate of specified and colour one keyboard drawer ( size 2'x1'x3") two cupboard drawer ( size 1'-3" x 1'-6" x 6") with proper sliding arrangement and auto lock are provided along with storage unit ,one drawer to have provision for storing cash, <b>ready made powder coated CPU stand</b> , footrest 3" x1 ½" below the main working top. The counter will have all necessary hard ware, laminate band and teakwood beading1 ½ " X ½" / moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present below the counter. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish. All work is done complete in all respects to architects satisfaction.	10.00	R.Ft		
8	<b>Low storage unit with ¾" thick post-form factory made Tops:-</b> Providing storage unit of size 18"x2'-6" & 18" x 3'-6" (W x H) of ¾" thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) with 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate having one shelf in center. The storage unit will have all necessary hardware,locking arrangement, laminate band and teakwood/ partial wood beading ¾ " X ½"/ moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present. Clip hinges ( dadoo kabzaa ) to be used for fixing storage unit shutters. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish .the work to be done complete in all respects.	70.00	Sq.Ft		
9	<b>OVER HEAD STORAGE:-</b> Providing storage of size 16" x 2'-3" (WXH) of ¾" commercial Ply with 1.0mm thick horizontal and vertical laminate having one shelf in center. Top portion of storage shall be tapered with 3". Cedar wood lipping ¾ " X ½" is provided at edge. Open able shutter with clip hinges ( etching colour ), ball catchers, multi purpose locks(approved make) are to be provided. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be	25.00	Sq.Ft		

	paint/polish . All work is done complete in all respects to architects satisfaction & as per colour scheme of bank. The storage unit is properly fixed to wall at+ 5'-9" . concealed tube lights ( 3 Nos. ) to be provided along with electrical wires and connections ( Note : Electrical fittings given separately in electrical part)				
<b>10</b>	<b>Full height storage unit :</b> Providing storage unit of size 18''x9'-0'' ( W x H ) of ¾'' thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) with 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate having shelves @1'-3'' C/C. The storage unit will have all necessary hardware, decorative jalli pattern laminate band and teakwood/ partal wood beading / moulding. Recessed skirting (3/4'') finished with 1.0mm thick laminate . Clip hinges ( dadoo kabzaa ) to be used for fixing storage unit shutters. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish .. All work to be done complete in all respects.	160.00	Sq.Ft		
<b>11</b>	<b>Wooden boxing for electrical panel:</b> Providing Cabinet unit of size 18''x8'-6'' ( W x H ) of ¾'' thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) with 1.0mm thick horizontal laminate. 8mm thick bison panel board back side alongwith wall. The storage unit will have all necessary hardware, decorative jalli pattern laminate band and teakwood/ partal wood beading / moulding. Recessed skirting (3/4'') finished with 1.0mm thick laminate is present. Clip hinges ( dadoo kabzaa ) to be used for fixing storage unit shutters. All work to be done complete in all respects	70.00	Sq.Ft		
<b>12</b>	<b>PIN UP BOARD :-</b> Made of 12mm thick soft board covered by 25mm x 25mm teak wood beading painted polished to approved colour and soft board covered with blazer/ fabric cloth of approved colour. Texture and sample approved by architect. Notice Board to be fixed to wall space between storage unit ( ground placed ) and storage unit ( wall hung ) in manager's Cabin & on top of writing table & in Banking Hall. ( basic rate of fabric shall not be less than Rs.65/- per mtr.)	40.00	Sq.Ft		
<b>13</b>	<b>FALSE CEILING:-</b>				
<b>a</b>	Providing and fixing Gypsum board false ceiling in levels as per the detailed drawing - made up of G.I. frames as specified by Gypsum India limited and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel, suspenders etc. shall be standard sections supplied by Gypsum India LTD. Spacing of intermediate channels shall be at 1200c/c, and ceiling section at 457mm c/c.the work includes finishing of joints, applying primer, two or more coats of plastic emulsion paints (white colour) , making cut-out for light fixtures, etc.	850.00	Sq.ft		

	providing of perimeter channels / beading etc. complete in all respect				
<b>b</b>	<p><b>PPGI METAL SHEET FALSE CEILING:</b> Providing &amp; fixing in position false ceiling in <b>Armstrong 600 x 600 mm PPGI Metal microlook lay-in standard perforated tiles silhouette 38</b> made of 120 gsm pre-painted galvanised iron, Grade-GPL as per IS277 (2018) with coating durability as per IS 4246 color as approved by Bank/architect with laid on 15mm exposed grid system. The suspension system shall be the <b>Armstrong Trulok Silhouette</b> revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with “birds mouth “ notches to provide mitered cruciform junctions. The framework comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers. Hangers (GI wire of 4.0mm dia) to be fixed by approved roof plug, level adjusters and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees (with double stitching) to be interlocked between main runners at 600mm centers to form 1200 x 600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200m cross tees and making arrangement for light fixtures, etc. complete in all respect.</p>	435.0 0	Sq.ft		

14	<p><b>Manager's table with 1½" thick post-form factory made Tops :-</b> Providing Table for manager (Size 6'-0" x 3'-0" x 2'-6" )made to shape as per drawing of 1½" thick post-form factory made Tops &amp; ¾" thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) finished with 1.0mm thick laminate of specified colour and make. 12mm thick bevelled glass (approved make) of same size is placed with edges covered with partial wood beading. Drawer unit ( drawer size: 1'-1" x 1'-6"x6", 3Nos. ) is located on one side with proper sliding arrangement and auto lock are provided along with storage unit. The counter will have all necessary hardware, laminate band and teakwood/ partial wood beading 1 ½ " X ½" / moulding. Recessed skirting ( ¾") finished with 1.0mm thick laminate is present below the counter. In front, apron of ¾" board ( laminate finished ) is provided. Keyboard drawer. <b>ready made powder coated CPU stand &amp; footrest 3" x 1 ½"</b> etc. to be provided. Laminate colour combination scheme with beading to be followed. All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish. All work is done complete in all respects. . All work is to be done complete in all respects.</p>	1.00	Nos		
15	<p><b>Officer's table with 1½" thick post-form factory made Tops :-</b>Providing Table for Officer's tables(Size 5'-0" x 2'-6" x 2'-6" ) rest specification as per Item No-13.</p>	1.00	Nos		
16	<p><b>Side credenza with ¾" thick post-form factory made Tops :-</b> Providing and placing side rack(Size 3'-6" x 2'-3" x 1'-4" ) made of ¾" thick ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated )finished with 1.0mm thick horizontal laminate. 4 Drawers ( Size 1'-1" x 1'-3" x 4" ) of ¾" board are placed below. Remaining portion has 2 shutters with 1 shelf. Laminated colour combination scheme to be followed. All necessary hardware eg hinges, screws, multipurpose locks, stoppers, drawer slides, ball catchers to be provided along with teakwood / partial wood beading/ moulding . All inside surfaces are finished with 0.7mm thick laminated and beading/moulding shall be paint/polish .All works to be done complete in all respects.</p>	2.00	Nos		

17	<b>Writing desk / Customer Voucher Stand / Forms Stand including Cheque Drop &amp; Suggestion Box with 1½" thick post-form factory made Tops :-</b> Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of 2 Nos Cheque Drop & 1 no Suggestion Box made of 19 mm thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall cost of spacers etc. all inclusive complete.	1.00	No		
18	Providing and fixing white board of size 3'-0"x3'-0" in Manager's chamber clamping on the wall complete in all respect as per directions of the bank/Architect.	1.00	No		
19	<b>TEXTURE PAINT:</b> Ground Floor walls to be finished with texture paint of approved make ( Rustic) above 4'-6" upto ceiling bottom including scaffolding, cleaning & supply of all materials. Also providing & fixing 2" wide hillock wood flat member at junction between ceiling & wall along length.	350.0 0	Sq.ft		
20	<b>Panelling With exterior grade ACP / Aluminium Composite Panels (With Aluminium Frames)</b> Supplying & fixing 4mm thick Aluminum component sheet of approved make and shade including making of ground of (1"X2") aluminum hollow section as per design ,with 6mm-19mm wide vertical or horizontal groove finished with Dow Cowing sealant (789) as per Architect's drawings & instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.5 mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealent) for proper finish. The works includes front face shutter boxing complete. the rate includes all required shuttering,scafoulding, labour, material, complete	200.0 0	Sq.ft		
a)	ACP partition and door with ACP sheet on both sides inclusive of all hardware like lock.handle etc. and fittings .	65.00	Sq.Ft		
b)	ATM Panelling With interior grade ACP / Aluminium Composite Panels (With Aluminium Frames)	300.0 0	Sq.ft		
21	P&F UCO Bank logo made with Acrylic steel sheet as per design, 2'-0" high & 2'-0" wide having provision of pipe light below logo screwed with stainless steel screw. All work is done complete in all respects to architects / bank managements satisfactory	1.00	No		
	<b>TOTAL OF INTERIOR WORKS</b>			Rs.	
<b>B</b>	<b>ELECTRICAL WORK</b>				

S.	Description of Items	Qty.	Unit	Rate	Amount
1	<b>Point Wiring</b>				
	Supply all material, receiving, storing, fixing, laying wiring & testing the same for light, ceiling fan, exhaust fan, 6A socket; starting from the point control box to out let; using 1.5 sqmm copper conductor PVC insulated 1100V grade wiring cable in concealed system using 20/25/32 mm ISI marked PVC conduit including all conduit accessories like conduit bends, tees, draw boxes, fan hookes etc., where ever required, together with wiring accessories such as flush type modular & flush type sockets, point control boxes,PVC bushes for conduit ends, batten holders, chrome plated brass screws including 1 sqmm copper PVC insulated earth wire, identification ferrules at either ends, complete in all respect. Conduit being concealed either in ceiling/ wall chase or on surface, including making & filling chases with cement mortar & painting the surface conduit etc. complete as reqd. Rates include providing & fixing modular switches & sockets with switch boxes and plate etc. complete (Rates include 3x2.5 sq.mm copper conductor PVC insulated wiring laid in PVC pipe for circuit wiring). Wire Make: HAVELLS/KEI/ECKO/RR CABLE/Polycab only and Switch & socket make: Anchor/Crabtree/North-West/MK)				
a)	6 amp switch controlling single light/fan point	45	NO		
b)	6 amp switch controlling the four downlighters OR Two 2x2 light fittings (No. of lights will be counted for calculation)	20	NO		
c)	<b>15 Amp wiring</b> with 2.5mm sq. multi strand PVC copper wire & metal clad enclosure sockets & plug. ( 3 pin 15 amp. Switch& socket will be counted as a one point)	10	NO		
d)	<b>5 Amp plug point</b> wiring with 1.5mm sq. multi stand PVC copper wire inc. Plate switches, sockets, plugs. Etc. ( 3 pin 5 amp. Switch& socket will be counted as a one point)	10	NO		
e)	<b>Call-bell point</b> wiring including Ding-dong bell with 1.5mm sq. multi strand PVC copper wire including plate switches, sockets, etc. ( 3 pin 5 amp. Switch& socket will be counted as a one point)	1	NO		
f)	<b>Signage wiring</b> (material & labour) – P&F of 3x4mm & copper flexible wire & PVC conduiting of ISI make complete with all accessories like Saddles, bends modular switches etc.	2	NO		
g)	<b>Electrical wiring for Air-Conditioning with metal clad to be fixed on wall:</b> P / F 32 Amp wiring with MCB from D/B to site of outdoor and indoor A/C Unit, i.e. circuit wiring with 4mm sq. multi-strand PVC copper wire, earth wire with DP switches.	6	NO		

<b>2</b>	<b>ELECTRICAL FITTINGS &amp; FIXTURES</b>				
a)	<b>Supply, Installation, testing and commissioning of 36 watt (2'X2') LED Light LCTLR-36-CDL of Crompton.</b> above 100 lm/watt fitting complete including necessary connection from 2x1.5sq.mm copper wire in ceiling etc. as reqd.	20	NO		
b)	Supply, Installation, testing and commissioning of recess down lighter with assembly complete with <b>15watt LED Light LCND-15-CDL of Crompton.</b> above 85 lm/watt including necessary connection from 2x1.5sq.mm copper wire in ceiling etc. as reqd..	28	NO		
c)	SITC of <b>18/20 watt LED Batten</b> above 90 lm/watt including necessary connection from 2x1.5sq.mm copper wire in ceiling etc. as reqd	7	NO		
d)	SITC of <b>300 mm exhaust fans</b> 1400 rpm (Double ball bearing) Heavy duty Crompton Greaves / Phillips.complete with self opening louvers/shutters etc. complete with suitable wooden/iron frame as reqd	4	NO		
e)	SITC of <b>400 mm sweep wall fan</b> etc. complete as reqd.of Khaitan / Crompton Greaves / Orient make.	11	NO.		
f)	SITC of 30 watt Street light /Flood light for lighting the front side of the branch(M/s Crompton Cat No. LSTS-30-CDL or equivalent of Philips/Wipro .	2	no.		
g)	<b>4.5/5 Watt LED strip light</b> for cove with Driver (M/s. Philips Wipro / Bajaj ) Complete in all respects.	30	mts		
<b>3</b>	<b>Main Cable</b>				
a)	<b>Provided and laying 3.5 x 50 sq.mm.</b> aluminium conductor with 2 no. 8 SWG G.I. wire	30	mts		
b)	<b>Generator Connection :-Provided and laying 3.5 x 25 sq.mm. aluminium conductor</b> with 2 no. 8 SWG G.I. wire	25	mts		
<b>4</b>	Providing & fixing <b>Main electrical Panel Board</b> with all internal electrical and generator connections with 25 sq.mm multi strand copper wire, which shall include the following items.				
a	Providing & fixing <b>3 No. 160 amp kitkats</b> (fuse carrier & base) with 1 no. neutral link on suitable size of bakelite sheet of thickness not less than 6 mm etc. complete as reqd.	3	No.		
b	1 no. 0-500V Digital Voltmeter & Digital Ammeter with one set of CTs (3no.) with CT ratio 100/5 A with LED type indication lamps with protection fuses in separate compartment	1	Set		
c	Aluminum bus bar <b>200 Amp.</b>	1	No.		
d	<b>160 Amps. Main switch MCCB.</b>	1	No.		
e	<b>Change –over 160 Amps.</b> 3-phase of Havells make.	1	No.		
f	<b>4 way TPDB</b> double door comprising of 1 no. incoming 100amp isolator & 6 nos. 32 DPMCB (For AC's distribution)	1	No.		

g	<b>4 way TPDB</b> double door comprising of 1 no. incoming 63 amp 4P isolator & 12 nos. 6/10Amp SPMCB (For Lighting and raw power distribution)	2	No.		
h	<b>8 way MCBDB</b> double door in recessed wall including cutting of wall and making good the damages comprising of 1no. 63amp isolator and 6no. 6/10amp MCBs etc. complete as reqd.(For UPS's distribution)	1	No.		
i	<b>ELCB</b> :-Supplying 40 Amp. earth leakage circuit breaker (ELCB) confirming to IS-12640 / 1988 & BS 4293 / 1983 having sensitivity 100 MA and breaking capacity of 10 KA and suitable for 3 Phase and neutral 415V having characteristic quick acting & tripping with all advance features & do not in-corporate any electronic component with suitable enclosure box.	1	No.		
j	Making <b>double-door powder coated M.S. Distribution</b> board 4'x4' to accommodate the above noted electrical items.	1	No.		
<b>5</b>	<b>Electrical wiring for UPS input-output:</b> P / F 32 Amp wiring with with 2 DP's of 32 Amp. from D/B to the location of UPS/UPS room for input and output power supply with 2 runs of 4mm sq. and one run of 1.5 sq. mm as earth wire multi-strand PVC copper wires, with DP switches / power pt. i.e. switch-socket.	2	No.		
<b>6</b>	Providing and laying following sizes of <b>PVC insulated copper conductor</b> flexible wire of 1100V in flexible/solid PVC conduit etc. including making necessary connection complete as reqd.				
a)	<b>2x 6 sq.mm with 1.5 sq. mm</b> copper PVC insulated earth wire <b>(For UPS input &amp; output connections)</b>	25	per mtr.		
<b>6</b>	<b>UPS POINTS:</b>				
	P/L & testing electrical three point wiring /circuit wiring having individual circuits for computers with 2.5mm <sup>2</sup> Multi-strand copper PVC wire in unbreakable PVC conduits 25mm dia wall thickness 2mm thick with specials under floor / wall & above false ceiling including chase cutting, disposal of malba away from the site and repair of the same with cement mortar, incl. Switches & socket M.S. switch boxes with rust proof treatment size to accommodate the required nos. of Modular switches, sockets etc. & plate type sockets with indicator three in one plate including earthing with 1.00 mm <sup>2</sup> multi strand wire complete in all respect.				
a)	Set of 6 amp. 4 sockets & 4 switches	7	pts		
b)	As per item 6 above but with 2 Nos. 15 A 5 pin socket controlled by 1 no 15 A switch and indicator. ( <b>U.P.S and Data Points are to be provided in lock and key arrangement</b> )	2	each		
<b>7</b>	<b>UPS supply to tube lights:</b> Point wiring / circuit wiring with 1.5mm sq. from D/B to switches & fittings multi strand PVC copper wire including plate switches, sockets, etc. (for payment no. of switches shall be counted).	4	no		

8	<b>Data Cable:-</b> Data cabling work for computer networking starting from mounting rack at suitable position of banking hall with UTP CAT-6e LAN Data cable in 2mm thick 25 mm dia ISI mark PVC conduit with accessories such as bends, Tees, junction boxes including providing and fixing cat-6 I/O plates and SMB complete with all networking accessories etc complete as reqd., testing and ferruling (D-Link/MOLEX/AMP/COMMSCOPE). Note: maximum 6 no. data cable must be run in one PVC pipe.	7	pts.		
a)	supply, installation, testing and commissioning of 24-port Patch Panel	1.00	no.		
b)	supply, installation, testing and commissioning of mounted rack 15" hight made of powder coated MS sheet	1.00	no.		
9	supply, installation, testing and commissioning of factory manufactured <b>CAT-6e patch chord</b> complete with 2 no. connectors etc. complete as reqd.				
a)	1 mtr. Long	7.00	no.		
b)	2 mtr. long	7.00	no.		
10	<b>TELEPHONE</b> Wiring for telephone points with 0.6 mm dia 2 pair insulated annealed tinned electrolatic copper conductor in 2 mm thick 25 mm dia ISI marked PVC conduit complete with accessories such as bends, junction boxes etc. with suitable size of PVC box modular plate and cover in front on surface or in recess including providing and fixing modular type telephone socket outlet and making necessary connections etc. complete as reqd. Wiring for telephone points with 0.6 mm dia 2 pair insulated annealed tinned electrolatic copper conductor in 2 mm thick 25 mm dia ISI marked PVC conduit complete with accessories such as bends, junction boxes etc. with suitable size of PVC box modular plate and cover in front on surface or in recess including providing and fixing modular type telephone socket outlet and making necessary connections etc. complete as reqd.	4	pts.		
a)	<b>Tag Block</b> : Supply, Providing & installing 20 pair PVC Tag Block in hinged type complete as reqd. Tag Block : Supply, Providing & installing 50 pair PVC Tag Block in hinged type complete as reqd.	1	no		
11	<b>EARTHING(GEL TYPE MAINTENANCE FREE EARTHINGS)</b>				
	GEL TYPE CHEMICAL EARTHING (Distance between each pit shall be min 1.5meter) (Generator + UPS + Raw Power)= 1 Nos & ATM = 1nos Supplying and installation of copper Gel Earthing station having length 3000 mm including bore-well, chamber with cover and all required civil allied works each earth pit to filled with 2 bags in 30 Kg pack of "Black-Fill Compound" (BFC)EARTHING CONDUCTORS: Wiring with 1x10 sqmm PVC insulated copper conductor wire of 650/1100 volts grade (Finolex make flame guard quality) as earth wire with	2	Nos		

	concealed/exposed PVC pipe including making all the connections.				
<b>12</b>	<b>Earth Box:</b> Providing and fixing suitable size of MS box fabricated with 16 S.W.G. MS sheet either in recess wall or on surface to accommodate dedicated earth from earth electrode and further distribution of earth to computer points including providing 5mm Bakelite sheet on base connector strip and painting of box etc complete as reqd.	1	Nos.		
<b>13</b>	Supplying & Laying of following COPPER REFRIGERANT PIPING Thickness 22 SWG For Hiwall Split AC complete with fittings Suction / Discharge line insulated with 12 mm SUPERLON / ARMAFLEX suction line. Multi-runs between Indoor & Outdoor units shall be considered as ONE length for the purpose of measurement. (Make: Total Line/Armacell)				
<b>a)</b>	1/4" + 1/2" Refrigerant piping - For Hiwall Split AC's ( 1.0 Tr & 1.5 Tr)	70	mtr.		
<b>14</b>	Supplying & laying recessed in wall Rigid ISI Mark PVC drain pipe of size 20mm dia complete with fittings, U traps etc. & as specified to the nearest toilet / drain point under floor or in recessed walls for AC drains including cutting of walls, bends & Tees. making good the damages etc. wherever required. (Make: Diplast/Supreme)	40	mtr		
<b>15</b>	Supplying and providing FRLS Eletrical flexible cable of 3x2.5sq.mm multi strand suitable for 1.0/ 1.5 Tr H.W Split Multi-runs between Indoor & Outdoor units and between Metal Clads to Out door for electrical supply etc complete as required (Make: Havells/ RR Kable / KEI/Finolex)	70	mtr		
<b>TOTAL OF ELECTRICAL WORK</b>				<b>Rs.</b>	
<b>SUMMARY</b>					
<b>A</b>	<b>INTERIOR WORK</b>			<b>Rs.</b>	
<b>B</b>	<b>ELECTRICAL WORK</b>			<b>Rs.</b>	
<b>TOAL</b>				<b>Rs.</b>	
<b>DISCOUNT (IF ANY)</b>				<b>Rs.</b>	
<b>GRAND TOTAL</b>				<b>Rs.</b>	
<b>GST Extra as applicable.</b>					

Signature of contractor

