

**SCHEDULE OF SPECIFICATIONS AND QUANTITIES FOR INTERNAL FURNISHING AND CIVIL WORKS  
WORKS OF ALAMGANJ CURRENCY CHEST, UCO BANK**

| A    | PARTICULARS   | QTY | UNIT | RATE | AMOUNT |
|------|---|-----|------|------|--------|
| 1.   | <b>FALSE CEILING</b> ( Gypsum board and 2' x 2' grid ceiling ),   |     |      |      |        |
|      | <b>A. FALSE CEILING (GYPSUM BOARD) :</b> Providing & Fixing gypsum board false ceiling system in 2 steps / In combination the grid ceiling Armstrong tiles ceiling vertical profile using 12.5mm gypsum plaster board on G.I.metal frame work. The frame work made up of perimeter channels of 20 x 27 x 30 x 3657mm fixed on wall & partitions and ceiling sections of 80 x 26 x 0.5x 3657mm as a cross member provided at 457mm c/c and the intermediate channel of 15x 45x.09 x 3657mm as a main runner at 1220mm c/c suspended by means of G.I.angle 25 x 25 x .05 mm from the existing ceiling by means of M.S. rawl plug with bolts/screws at 1200 mm c/c max. The joints of gypsum board to be taped 3 times and sealed with jointing compound. Finished with one coat of primer and min 3 coats colour or matching spectrum colour complete as per detail and specifications in drawing incl. all lights, diffuser cuttings complete.   | 600 | sft  |      |        |
| 2.   | <b>PARTITION</b>  |     |      |      |        |
|      | Providing and fixing partition in position as per design with 2"x 1.5" sal wood /kappor wood / badam wood , finished section frame work @ 2'-0" c/c both ways screwed to the floor and ceiling with M.S. Cleats and to be treated with anti termite oil. The frame work will be cladded with 6 mm thk. BWP and termiteproof plywood both side and to be finished with approved 1.0 mm laminate (with vertical grain and groove in between the laminate portion) as per design with approved band adhesive, extra frame work to be fixed for fixing glass. In the glazed partition 10 mm thk. Modiguard/Saint Gobain clear float glass with film sheet on top to be provided, duly fixed with white beach/white ceader lipping 50 mm x 25 mm all complete duly reddish brown/ rose wood colour polish with melamine finish or stainless steel glass clips on both sides of the wooden support to fix up the glasses . The work should be completed as per specification, design & approval of the Architect. For the door 32 mm solid core bwp Flush door with a frame work of white beach/ white ceader size 75 mm x 62.5 mm with necessary hold fast fixed to the wall/partition, finished with 1.0 mm laminate and lipping in all sides and 1.5" x 1.5" white beach/ white ceader wooden moulding to be provided along the periphery of the door frame. supplying and fixing door accessories as door closure, brass hinges, Cylindrical / Night latch locks and s.s handle.<br><b>Laminated skirting of 4" ht. and at the soffit of false ceiling level , as per approved colour code to be placed all around the partition as per direction and colour code of UCO BANK</b> |     |      |      |        |
| 2.A. | Partly glazed partition   |     |      |      |        |
| a    | <b>PARTLY GLAZED PARTITION upto 4' ht</b>   | 20  | cft  |      |        |

|    |   |     |     |  |  |
|----|---|-----|-----|--|--|
| b  | <b>TABLE GLAZED PARTITION WITH / NO. DOOR FOR<br/>MANAGER'S CABIN</b>   | 120 | sft |  |  |
| c  | <b>BLOCK PARTITION</b> -Upto 8'-6" ht. , ceiling ht and soffit of beam, including doors . Elect. Panel board to be included   | 40  | sft |  |  |
| 3. | <b>Main Entrance Door</b>   |     |     |  |  |
|    | Providing and fixing glass door -1 way - 3'-6" x 7'-- for main entrance. .A white beach wood frame size- 6" x 2" as top and bottom rail with a decorative handle of 600 mm of approved brand, floor spring , locks, etc all complete. 12 mm thk. toughened glass with glass films on top as directed and <b>UCO BANK</b> logo to be provided and edge should be machine beveled polished. The work to be completed as per design and specification of the architect all complete. the wooden portion to be duly melamine polished.  | 25  | sft |  |  |
|    | <b>TABLE</b>  |     |     |  |  |
| 4  | Providing and fixing tables made out of 18 mmth. blockboard of approved make clad with 1.0mm laminate (color with vertical grain ) as per design in all visible areas. All the exposed edges to be covered with wooden lippings and mouldings to be reddish brown or rosewood colour polish with melamine finish. The drawers are to be made out of 18 mm thk. plywood duly 1.0 thk. laminated in the front, sides to be made out of 18 mm blockboard and bottom to be made out of 6 mm BWP and termiteproof plywood and it should play in drawer telescopic sliding channels. The inside of the drawer and the table to be duly polished. A legrest to be provided duly polished made out of 18mm thk.blockboard. A shutter to be made by 18mm th. blockboard clad with 1.0mm laminate. The necessary locks handles to be provided in each drawers and shutters. <b>The table should have wooden key board tray and wooden ups trolley.</b> The necessary wire managers to be provided on the tables and provision for lights to be kept in the front of the table. CPU to be fixed with the table at the bottom and it should not be placed on the floor or on the trolley.The work to be completed as per design and approval of the Architect. <b>10 mm th. clear glass on top of branch manager table . 4.5" skirting of approved colour code of the bank to be fixed at the bottom of the table and at the soffit of false ceiling level as per direction of Architect.</b> |     |     |  |  |
| a  | Table --- 4' - 3" x 3'-0" --- 2 nos.  | 24  | sft |  |  |
| 5  | <b>Side Units : Low ht. Cabinet</b>   |     |     |  |  |
|    | Providing and fixing Side Unit/Back Unit made out of 18 mm th. blockboard finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 18 mm blockboard in the front clad with 1.0 mm laminate, side to be made out of 12 mm plywood and bottom made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 18mm blockboard and should play on drawer sliding castors on powder coated channels. The necessary locks, handles, etc to be provided. 4" laminated skirting to be provided all along the visible areas. Inside of the unit to be enamel painted in matching tone. All the exposed  | 152 | sft |  |  |

|          |  |           |     |  |  |
|----------|--|-----------|-----|--|--|
|          | <p>unit to be enamel painted in matching color for the exposed edges of the boards/plywoods to be covered with wooden lippings/mouldings duly polished all complete. The work to be completed as per approval and specification of the Architect.</p> <p><b>4.5" skirting of approved colour code of the bank to be fixed at the bottom of the cabinet</b> as per direction of Architect.</p> <p><b>low ht. . cabinet</b> --( 9' ) x 3'-6" ht. +</p> <p><b>low ht. cabinet</b> --- ( 3'-3" x 1 no ) x 2'-6" ht. +</p> <p><b>elect. panel box</b> --- 4' x 3' <b>full ht. cabinet</b> --- 100 sft</p> |           |     |  |  |
| <b>6</b> | <b>Notice board</b>  |           |     |  |  |
|          | Providing and fixing soft board with necessary frame work with 12 mm bwr plywood on top jolly board to be fixed finished with fabric @ Rs. 100, with necessary moulding duly polished along the periphery.   | <b>12</b> | sft |  |  |
| <b>7</b> | <b>OUTER SHUTTTER BOX FOR TOP AND TWO SIDES OF ROLLING SHUTTER - 2 nos</b>   |           |     |  |  |
|          | Overhead and two sides outside shutter boxmade of sal wood frame of 2" x 2", to be fixed with 12mm plywood with 1mm thk. Laminate finish and openable shutter for outside area   | 120       | sft |  |  |
|          |  |           |     |  |  |
|          | <b>TOTAL FURNISHING</b>  |           |     |  |  |
|          | <b>Rupees</b> +<br><b>GST EXTRA</b>  |           |     |  |  |









