

BOQ FOR FURNISHING, ELECTRICAL & AIR CONDITIONING WORKS AT UCO BANK MODEL TOWN DELHI					
S.NO.	DESCRIPTION OF ITEM	QTY	UOM	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
1.0	DISMENTALING WORK				
	Making temporary connections , Dismantling of counters as per Branch requirement and shifting of points all across the Branch and for workstations (Electrical, data, UPS and telephone) to enable smooth functioning of the branch during renovation all complete as per the instructions of Bank's Engineer/ Architect. Item to include supplying all wires, cables, conduits etc. for the same. Nothing extra shall be payable in this regard.	1.00	Job		
2.0	DOORS				
2.1	ENTRANCE DOORS - WITH TOUGHENED GLASS (PATCH FITTINGS)	45.00	Sq. Ft.		
	DOORS - WITH OZONE / HAFFLE / YALE / GODREJ MAKE FITTINGS				
	Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma/Ozone/ Haffle/Yale/ Godrej make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)				
2.2	ALUMINIUM DOOR	0.00	SqFt		
	Providing and fixing of Aluminum door with powder coated Aluminum sections of size 3.25"X 1.75" for door opening size of 2 x 2'-6" x 7'-0" in double panes (Branch entrance) & 1 x 2'-9" x 6'-6" (ATM Entrance) in single pane or as per drawing. Item shall include providing & fixing in position 6mm thk clear glass on door panes with bank's logo & frosting film of aproved make with approved artwork . Film shall be of approved make, self-adhesive with bubblefree installation. Item shall also include all the required hardware & fittings of approved makes such as heavy duty floor spring, D type matt finish SS handles of size 1'-3" of both sides of the door, 3 round dead lock arrangement, tower bolts of matching colour, self-adhesive push-pull indication stickers on both sides etc complete.				
2.3	SOLID DOORS-IN LAMINATE FINISH (with hardware fittings MAKE EVERITE/GOLDEN /HARDWIN/EVEREST) (WITH OR WITH OUT VISION PANEL AS PER DIRECTION OF BANK / ARCHITECT	0.00	Sq.Ft.		
a	3-0" x 7'-0" - IN LAMINATE FINISH - (WITH 2" x 3.5" finished size WOODEN FRAME)				
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping. A door frame of 3.5" x 2" steam beach section shall be provided finished in mellamine. Rate shall include Dead lock (Godrej Make), floor springs / door closure (as the case may be), door stopper, a pair of handles 12" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items and with or with out door frames as mentioned above				
3.0	PARTITIONS WORK				
3.1	FULLY GLAZED PARTITION-WITH TOUGHENED GLASS				
a.	USING OZONE/HAFFLE/YALE/GODREJ MAKE FITTINGS	100.00	Sq.Ft.		
	Providing and fixing of Fixed Glass partition with 10mm thick toughened glass using Standard fittings of above - mentioned makes at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.				
3.2	ALUMINIUM PARTITION	0.00	SqFt		

	Providing & fixing Aluminium powder coated banks' approved coloured frame of sections 1.75" X 1.75" of 16 gauge (1.6mm) or higher thickness and 6 mm thk clear fixed glass. Item shall include all fixtures & fittings like neoprin rubber beading, springs etc complete. Item shall also include supply and installation of frosting film of aproved make with approved artwork. Film shall be of approved make, self-adhesive with bubblefree installation to be done on clean glass.				
	In case a ceiling type formation is to be prepared for enclosing the entrance vestibule of the branch / ATM from top due to avoid site nuisance of dust, pests etc where false ceiling is not carried out, the top of the partition vestibule shall be fabricated with aluminium frame as above and finished with approved make pre-laminated board panels of bank's colour on the visible surface. <u>Note</u> - The additional ceiling partition item (if carried out) shall be measured on plan area and shall be added to the partition item quantity.				
3.3	PLYWOOD/WOODEN PARTITION WITH ALUMINIUM SECTION				
	Frame Work: Providing and fixing in position Full Height partition in framework of 600 X 600 mm grid (horizontally and vertically) comprising of 50mm X 50mm heavy duty GI Box Sections (1.6 mm) with 8 mm thick ply on both sides finished with 1 mm thick laminate as mentioned below.				
	Note: a) In case of false ceiling, the vertical GI members to be fixed to RCC ceiling but the area of partition payable will be below the false ceiling only. b) Measurement of height shall be taken from finished floor only, in case of varying heights on either side of partition, average height shall be considered. c) Openings/ door/ glass shall not be measured for payment and shall to measured and paid under seprate relevant item.				
	Laminate: 1.0 mm thick matt laminate (shade and design as per Bank's Scheme) pasted over MDF with approved adhesive. Laminates shall be combination of 2 or 3 colours - as per bank's guidelines to be approved from the bank prior to application. Partition shall have 100mm high skirting from the finished floor in banks' approved shade and a 100mm high top band from the soffit/ceiling/visible top of the partition in bank's approved shade. Remaining Area to be covered with bank's approved colour .				
	The necessary openings and provisions in the frame work for Electrical Conduits, modular electrical boxes, AC Grills & pipes, AC Ducts / louvers, doors / glazing etc. should be provided as per site requirements while keeping the structural integrity and strength of the framing intact. The GI frame members shall be fixed rigidly to the floor, columns, RCC Ceiling and beams. <u>Note:</u> In case of false ceiling, the vertical GI members of the frame should be fixed / screwed / grouted rigidly on the Roof / RCC ceiling but the area of partition payable will be measured from the finished floor up till the false ceiling only. In case of varying heights on either side of partition, average height shall be considered.				
3.3.1	SOLID PARTITION(FULL HEIGHT)-BOTH SIDE LAMINATE	250.00	Sq. Ft.		
	Proving and fixing both side laminated solid partition using framing, MDF and laminate as per details mentioned in Sr. No.3.3 All exposed edges of partition shall be fixed with teakwood lipping of appropriate thickness enough to cover the entire exposed edges and frame opening for doors chowkhat (75mmx75mm thick sections or as per site) with 2 coats of melamine polish. The rate quoted must be inclusive of the 32-35mm thick door (Size - 7'-0"x3'-0") made with approved plywood / board of approved make with 1.0 mm thick matte finish laminate pasted over plywood along with skirting and top band on both sides of the door as per bank's colour scheme. The rate quoted must also include installing / affixing all necessary fittings like 4 Nos. SS Butt Hinges (100mmx5.5mm size), screws, Hydraulic Door Closer, Mortise Lock Assembly, SS Handles on both sides & Brass Door Stopper etc as per approved makes. The exposed edges of the door must be finished with teakwood lipping with 2 coats of melamine polish.				
3.3.2	SOLID PARTITION (FULL HEIGHT)- CEMENT FIBRE BOARD FOR UPS ROOM	135.00	Sq. Ft.		

	Proving and fixing both side solid partition using framing and laminate as per details mentioned in Sr. No.3.3 The skin of the partition shall be made out of 10mm thick cement fiber board and finished with 1mm thick laminate of approved shade and scheme on the customer side (visible to customers) and 2 coats of ivory white enamel paint on the internal side (not visible from the customer lobby). The rate quoted must be inclusive of the providing one pane door for UPS room (Size - 7'-0" x 2'-9") & 2 panes door (Size-7'-0" x 2'-0" for electrical panel) or door sizes as per site requirements in combination of 6mm thk cement fibre board and 19mm thick approved block board pasted / screwed together to form a single entity and finished as per matching scheme. The block board shall be on the outer side and shall be pasted with 1.0 mm thick matt laminate along with matching skirting & top bands as per bank's scheme and the cement fiber side of the door shall be on the inside with 2 coats ivory white enamel paint over a coat of primer. Exposed edge of door thickness shall be finished with teakwood lipping & melamine polish.				
	Item shall include installing / affixing 12" X 6" aluminium louvers at the horizontal centre of the door panes at suitable height along with all other necessary hardware & fittings such as 4 Nos. SS Butt Hinges (100mmx5.5mm size), screws, mortice lock / brass tower bolt, SS Handles on both sides, magnetic ball catchers etc of approved makes. Note - For the purpose of contractor's payment in case of Electrical panel cabinet, only front elevation area shall be measured. BUT the partition shall be erected till soffit of the actual ceiling along with the board concealing the entire area and not just till the false ceiling				
3.3.3	PARTLY GLAZED PARTITION (FULL HEIGHT)				
A	Manager Cabin Partition (Partly Glazed - Full Ht.)	50.00	Sq. Ft.		
	Proving and fixing both side laminated partly glazed partition using framing, MDF and laminate as per details mentioned in Sr. No.3.3 The partition shall be solid till 3'-6" height and glazed with 6mm thick clear float glass in size 3'-6" (H) & 4'-0" (W) or of appropriate size as per site requirements. All sides of the glazing must be provided with teakwood beading on both faces and finished with 2 coats of melamine polish. Solid partition to be provided over the fixed glazing till soffit of false ceiling / roof / RCC Ceiling. All exposed edges shall be fixed with lipping of appropriate thickness enough to cover the entire exposed edges and frame opening for fixed glazing / doors chowkhat / windows (75mmx75mm thick sections or as per site) with 2 coats of melamine polish. The rate quoted must be inclusive of the 32-35mm thick door (Size - 7'-0" X 3'-0") made with commercial plywood / board of approved make with 1.0 mm thick matt finish laminate pasted over plywood along with skirting and top band on both sides of the door as per bank's colour scheme along with making 8-10mm glass opening of size 18"(W) X 48"(H) positioned at the horizontal centre & 5'-0" height for visibility with proper teakwood framing and polishing. The exposed edges of the door must be finished with teakwood lipping with 2 coats of melamine polish. Item shall				
B	Cash Cabin Partition (Height 7'-6")	60.00	Sq. Ft.		
	Proving and fixing both side laminated Solid partition for cash cabin using framing, MDF and laminate as per details mentioned in Sr. No.3.3 The partition shall be solid till 4'-0" height and thereafter an opening of 2'-6" Height & 2'-6" width (or of appropriate size as per site requirement) for Aluminium Decorative Grill (12mm thick having hexagonal openings) which shall be provided with double sided 2 coat melamine polished teakwood beading. Rest of the height shall be solid partition till the height of 7'-6" from the finished floor. All exposed edges of MDF shall be fixed with teakwood lipping of appropriate thickness (75mmx75mm thick sections or as per site) enough to cover the entire exposed edges and frame opening for aluminium grill / doors chowkhat / windows etc.) with 2 coat melamine polish.				
	The rate quoted must be inclusive of the 32-35mm thick door (Size - 7'-0"x3'-0") made with commercial plywood / board of approved make with 1.0 mm thick matt finish laminate pasted over plywood along with skirting and top band on both sides of the door as per bank's colour scheme along with making 6mm thk glass opening of size 18"(W) X 48"(H) positioned at the horizontal centre & 5'-0" height for visibility with proper teakwood framing and polishing. The exposed edges of the door must be finished with teakwood lipping with 2 coats of melamine polish. Item shall also include supply and installation of frosting film of aproved make with approved artwork. Film shall be self-adhesive with bubblefree installation to be done on clean glass.				

	A 2" deep slip tray made of 11mm/12mm MDF covered with 1.0 mm thick white matt laminate with edges finished with teakwood beading and 2 coats of melamine polish to be affixed at a height of 4'0" from the finished floor on the side partition adjacent to the passing Officer's counter at an appropriate slot to ensure convenient usage by both staff members. The slip tray must be 6" wide 10" long and must be positioned such that it must be emanating 4" on either side of the partition. The front edges of the partitions i.e., the edges visible to the customers, shall be finished with 1.0mm thick laminate of banks' approved shade. The rate quoted must also include installing / affixing all necessary fittings like 4 Nos. SS Butt Hinges (100mmx5.5mm size), screws, Hydraulic Door Closer, Night latch, SS Handles on both sides & Brass Door Stopper etc as per approved makes.				
3.4	Low Height Partition (Height 4'-0") - Between working Counters, cubicles & support for Flap door)	70.00	Sq. Ft.		
	Providing and fixing both side laminated solid partition using framing, MDF and laminate as per details mentioned in Sr. No.3.3 The partition shall be solid till 3'-0" then glazing with 8-10mm thick clear float glass of 1'-0" Height & supported on 4" wide solid partition pillars on both sides of the glass. The exposed edges of the glass shall be bevelled, grinded and machine finished to render smooth edges. The glass in the partitions shall be fixed with beading / moulding on both sides. All exposed edges of partition shall be fixed with teakwood lipping of appropriate thickness (75mmx75mm thick sections or as per site) enough to cover the entire exposed edges and frame opening for fixed glazing / doors / windows) with 2 coat melamine polish. Item shall also include supply and installation of frosting film of aproved make with approved artwork. Film shall be self-adhesive with bubblefree installation to be done on clean glass. NOTE:- The length of the partitions between the counters shall be 3'0"				
3.5	Flap Door (4'0" High)	15.00	Sq. Ft.		
	Providing and fixing of flap door using 19mm thick block board of approved make laminated on both sides with 1mm thick laminate of approved shade as mentioned above. The exposed edges of the board shall be finished with teakwood beading of appropriate thickness (enough to cover the entire exposed edges). The rate quoted must also include a vertical brass tower bolt assembly, 2 Nos. SS Butt Hinges (100mmx5.5mm size), screws & magnetic ball catchers etc of approved makes. There shall be 100mm high skirting at the bottom of the door with 1mm lamination in banks' approved shade & a 100mm high top band of bank's approved colour at the vertical top of the door so as to match the surrounding scheme.				
4.0	COUNTERS & TABLES				
	Providing & Fixing Box type Tables and counters of size mentioned below as per branch drawing and layout. The tables / counters are made out of 19mm thick approved ply / block board frame work for top, verticals, apron, sides, drawer unit with shelves, shutters, customer top, foot rest. The sides, sliding shutters, front apron of drawer unit shall be made out of 12.0mm thick approved ply while backs & bottom of drawer unit shall be made with 6mm thick approved ply. The drawer unit of 450mm width x 750mm height x 500mm depth or size approved by the bank shall be placed on a suitable side of the table / counter as per layout. The drawer unit shall consisting of 3 nos. drawers of equal height to cover the entire height of the unit & each must be 450mm deep OR of size & number as approved by the bank. Each drawer shall have SS handles with multipurpose concealed lock. The drawers shall be fixed with telescopic SS sliding channels of approved make with easy push-pull mechanism.				
	A uniform 100mm high skirting shall be provided at the visible bottom of the side unit with 1.0mm thick laminate of banks' approved shade. A fixed footrest made with T.W. member of size 4"x1.5" finished with french polish shall also be provided at the bottom of the inside of the tables / counters at a comfortable height. The working top of ALL counters / tables shall be provided with 10mm thick clear glass on top with edges bevelled and machine finished to render smooth edges. Grooves / openings for cable managers shall also be provisioned in the table and glass along with supply & fixing of cable manager. The shape of the top glass shall be prepared / cut in such a manner that the entire surface of the working top of the table / counters should be covered by the top glass.				

	All the open surfaces of the tables / counters / drawer units shall be completely covered with 1mm thick laminates. The front apron and visible side apron(s) of the counters / tables shall be provided with 100mm top band of 1.0mm thk laminate of bank's approved shade & 100mm skirting of 1.0mm thk laminate of bank's approved shade. The remaining area shall be provided with 1.0mm thick bank's approved colour. The counter / table top shall be provided with 1.0mm thick laminate of bank's approved shade. The other exposed edges shall be finished with teakwood lipping & 2 coats of melamine polish. All inner surfaces shall be finished with approved 0.8 mm thick laminate of ivory / white shade of approved make.				
	All table / counters shall be provided with sliding key board unit of size 12"x20" made of 19mm thick approved board finished with 1.0mm bank's approved colour and mounted with telescopic channels of approved make on the sides made out from 12mm thk approved board with 1.0mm thick bank's approved colour. All exposed edges to be finished with teakwood beadings of appropriate size and 2 coats of melamine polish along with all other finishes / hardware / fittings etc required to complete the job.				
	For CASH COUNTER- Same as above but the cash counter shall have two working tops viz. one working top at height of 2'-6" for staff & other, the customer top, at height of 4'-10" for customer use. The customer top shall be 450mm wide of length as mentioned below and shall be fabricated such that it is projected 150mm outwards i.e. towards the customer. The rate quoted must include full front portion and customer top of mentioned height and style made out of 19mm approved ply and 1.0mm thick laminate of design as approved by the Bank, along with 10-12mm plain float front glass which should be 3'-0" high over and above the customer top and of required length as mentioned below. A support partition shall also be provided on top of the glass till a height of 7'-6" from the finished floor. The partition over the glass shall be made out of 19mm thk approved board finished with 1.0mm thick laminate of bank's approved shade. The front glass shall be fixed rigidly over the customer top with teakwood beadings on both sides finished with 2 coats of melamine polish. Two openings / slits shall be provided in the front glass - one opening of 300mmx150mm as the horizontal centre at the bottom of the glass and another 2" wide horizontal slit				
4a	Branch In-charge Table (Size: 6'0"x3'0"x2'6"(H))	1.00	No.		
4b	Officer Table (Size: 5'0"x2'6"x2'6"(H))	2.00	No.		
4c	Staff Counters (Width of working top: 2'6"; Height: 2'6")	10.00	R. Ft.		
4d	Cash Counters (Width of working top: 3'0" & width of customer top: 1'6"; Heights as per description above)	5.00	R. Ft.		
5.0	STORAGE CABINETS / CREDENZAS				
	Providing & placing in position box type storage cabinets / Credenzas 18" deep & height as given below made out of 19mm approved board with 1mm laminate with shade as per bank's approved scheme. The top of the low height storages / credenzas shall be finished with 1.0mm thk bank's approved shade. The sides, partition, top, shelves & bottom shall be made out of 19mm thk. approved board and back made out of 6mm thk. approved ply. Item shall have one 6" high drawers on top made out of 19mm thick approved ply / board complete with handles, locks etc of approved makes. The shutters made out of 19mm commercial ply wood finished with 1.0mm thk laminates of approved scheme on the outer surface shall cover the remaining space available below the drawers. All inner surface shall be finished with 0.8mm thick bank's approved colour with matching edge tapes for all exposed edges. A 100mm high top band shall be provided on top front face of the storage cabinets / credenzas finished with 1mm thk bank's approved shade & 100mm high skirting finished with bank's approved shade shall be provided as per approved make.				

	The drawer must be finished with 1.0mm thk laminate of shade as per Bank's scheme on outer surface and 0.8mm thick bank's approved colour on the inner surfaces. The drawers shall be supported with SS telescopic sliding channels of approved make with smooth push-pull mechanism along with SS handles and individual locks. The shutters below the drawer shall be supported with soft close clip-on SS Hinges of approved make of required number depending upon the size of the shutter. Each shutter shall be supplied with necessary accessories and hardware such as individual locks, SS handles, magnetic ball catchers, SS tower bolts, individual locks etc. of approved makes screwed and fixed rigidly. Horizontal shelves & vertical planks made out of 19mm thick commercial board shall be provided inside the shutters in such a manner to create optimum number of storage chambers each of equal storage space depending upon the size of the cabinets / credenzas. These partitions shall be finished with 1mm thick bank's approved colour on all faces and exposed side (thickness) edges of the partition members shall be finished with teakwood lipping and 2 coats of melamine polish. Note - For the purpose of contractors bill payment, only front elevation area shall be				
5a	Side credenza adjacent to the tables and counters (2'-6" High & 3'-0" Wide OR as mentioned in layout) Same as Sr. No.3 but with 1 no. 6" high drawers at top & shutters below drawer.	10.00	Sq. Ft.		
5b	Low Ht. Storage (2'-6" High) (FOR B.M. Cabin and Cash Cabin only) Same as Sr. No.3 but with 1 no. 6" high drawers at top & shutters below drawer.	25.00	Sq. Ft.		
5c	Low Ht. Storage (4'-0" High) (FOR space behind staff counters in Branch Hall only) Same as Sr. No.3 but without drawers & with shutters fitted with SS butt hinges, vertical and horizontal shelves of appropriate size to utilize the entire space available as per layout for creating optimum space inside storage chambers at different heights.	0.00	Sq. Ft.		
5d	Full Ht. Storage (8'-6" High) (FOR space in record room) Same as Sr. No.3 but without drawers & with shutters fitted with SS butt hinges, vertical and horizontal shelves of appropriate size to utilize the entire space available as per layout for creating optimum space inside storage chambers at different heights.	180.00	Sq. Ft.		
5e	Overhead Storage (2'-0" High) (FOR space in Pantry) Same as Sr. No.5 but without drawers & with shutters fitted with SS butt hinges, vertical and horizontal shelves of appropriate size to utilize the entire space available as per layout for creating optimum space inside storage chambers at different heights.	0.00	Sq. Ft.		
5f	Full Ht. Baison Board Storage (8'-6" High) (FOR ELECTRICAL PANEL only) Same as Sr. No.5 but without drawers & with shutters having baison board on all inner surface fitted with SS butt hinges, vertical and horizontal shelves of appropriate size to utilize the entire space available as per layout for creating optimum space inside storage chambers at different heights.	50.00	Sq. Ft.		
6.0	CUSTOMER WRITING DESK.	5.00	R. Ft.		
	Supply and fixing of free standing box type customer writing desk of required length, 42" height and 18" deep. The desk shall be made out of 19mm thick approved block / ply upto the height of 36" and glass bins above (open towards the front for keeping challans) of size 6" X 6" each made up of 10 mm thick plain glass on back & side partitions of the bins affixed firmly to the base and the writing top over the bins shall be made of 12mm thk clear glass, finished with smooth edges and sealed with silicon sealant. The bottom of the desk shall consist of 2 nos. box type cabinets of size - 12" (w) x 24" (h) x 18" (d) made out of 19mm thick approved ply with shutters with a viewing glass pane of appropriate size using 6-8mm plain glass and 20mm horizontal slit at the top of the shutter. The shutter shall be complete with all accessories like lock, SS handles, SS Hinges etc. All the exposed surfaces of the board shall be covered with 1mm thk laminate of approved shades and exposed edges to be finished with teakwood lipping and 2 coats of melamine polish.				

	The exterior visible portion of the desk shall be finished with 1.0mm thick approved laminate on visible sides as per bank's colour scheme with matching top band skirting (100mm bank's approved shade Top Band and 100mm bottom skirting of bank's approved colour). All inner surfaces shall be finished with approved 0.8mm thk laminate in white shade. Item shall include all required hardware & accessories such as SS clamps, screws, slits etc to ensure that the rigid fixing of the desk members / parts and complete the item upto the satisfaction of the bank / Architect.				
7.0	LOGO BOARDS FOR COUNTER FRONT ELEVATION	0.00	Nos.		
	Supplying and fixing logo boards on the front elevation laminated surface of counters with 5mm thick acrylic sheet of size 18" x 18", attached with SS glass studs (1" or more). Stickers with bank logo (colour and shape as per Bank scheme) in the center to be pasted on the back side of the acrylic sheet neatly without any bubbles. The logo board must be placed on the centre of the front elevation of the counters visible to the customers EXCEPT on the Branch Manager's Table.				
8.0	GLASS BARRIER	65.00	Sq. Ft.		
	Providing and fixing glass barrier in the front of clerical / working counters made out of 10mm thick clear float glass with chamfered and polished edges. The glass must be supported at each end of the individual counters either with low ht. partitions or 3"x3" square towers of required height made with 19mm thick approved ply finished with 1mm thick laminate of approved shade on all faces as per the design approved by bank. In case of square towers, the top of the towers should be finished with 1mm thk approved laminate. The glass should be clamped rigidly to the low ht. partition / towers with teakwood beading finished with melamine polish along with necessary hardware / accessories as required. The height of the glass barrier shall be 450 mm (or as directed by the bank). The length of the glass barrier in single piece must be equal to the length of the individual counter. Item shall also include frosting film of approved make with approved artwork. Film shall be of approved make, self-adhesive with bubblefree installation.				
	<u>There shall be 2 uniform slits, each 100mm high; one at the bottom of the glass barrier just above the counter / Table top & one at the vertical centre of the glass barrier.</u>				
9.0	PANELING				
9a.	WALL / COLUMN PANELING (Full Ht. - till soffit of false ceiling) (IN ATM Room / Walls in Manager Cabin / Walls in Cash cabin / Independent pillars in branch hall / Side wall adjacent to Officer Table ONLY)	770.00	Sq. Ft.		
	Providing and fixing in position wall panelling in 600 X 600 mm grid (horizontally and vertically) comprising of 25 mm X 50 mm heavy duty GI Box Sections (1.6 mm) with 8 mm thick ply finished with 1 mm thick laminate finish of approved shade and make. The soffits of the doors / windows shall also be covered with paneling as well. Item shall include 100mm high skirting on bottom of the finished floor in banks' approved shade and a top band of 100mm high from the soffit/ceiling/visible top height of the paneling in bank's approved shade. Remaining area shall be finished with 1.0mm thk bank's approved colour of approved make. Note - No paneling shall be provided behind the storage / cabinets / tables sides or any other surface which is not visible (no payment for same shall be entertained by the bank). Entire paneling shall be provided only on visible surfaces as per approved layout or as directed by the Bank. Also, no paneling shall be provided on the columns embedded in walls. The paneling should be provided on independent pillars in the branch hall only that too till soffit of false ceiling.				
	Note:- In case of wall not being true to plumb extra shims of aluminium section shall be provided. Nothing extra shall be payable in this regard.				

	Note: a) In case of false ceiling, area of panelling payable will be below the false ceiling only. b) Measurement of height shall be taken from finished floor only, in case of varying heights on either side of panelling, average height shall be considered. c) Openings/ door/ glass shall not be measured for payment.				
9b.	ACP WALL PANELLING (For outside front walls and outer pillars of ATM only)	0.00	Sq. Ft.		
	Providing & fixing in position ACP (Aluminium Composite Panel) wall panelling having minimum ACP thickness of 3mm and minimum foil thickness of 0.25 mm on both sides with Aluminium framing tube sections of min 1.5" X 1" (20 gauge or down) @ 2'-0" C/C both ways. Panels shall be neatly fixed to the frame with 3M or equivalent adhesive and joints shall be finished with silicon based sealant. ACP shall be of approved make and in Ivory & banks' approved shade as per bank's approval. Item shall include proving & fixing additional sections as required for fixing Indoor AC units, proper access panel for ATM power point, proper locking arrangement for plug point by providing additional framing etc complete. Note - For the purpose of payment, the measurements shall be taken up to the visible height / false ceiling level only.				
10.0	FALSE CEILING (Branch & ATM)	625.00	Sq. Ft.		
10.1	FALSE CEILING - GYP BOARD				
	Providing and fixing ½" thk. Gypsum India board false ceiling at levels as shown in the drg. From FFL. Rate shall be inclusive of all Gypsum India components contained G.I. perimeter channels of size 0.55 thick having one flange of 20mm and another flange of 30mm and a web of 27mm alongwith perimeter of ceiling, screw fixed to brickwall/partition with the help of nylon sleeves and screws, at 610mm centres. The suspending G.I.intermediate channels of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angle of width 25mm x 10mm x 0.55 thick fixed to soffit with G.I. cleat and steel expansion fastners at every 610mm c/c. Ceiling sections of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment.				
	The boards are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edge of the boards with jointing compound & joint paper tape. Rate shall be inclusive of Cut outs for A/c machiness, spot lights, light fixtures, A/C. Grills, fire and security systems cut outs, All Sections should adhere to the manufacturers guidelines. Vertical sides visible will be measured.				
10.2	MODULAR FALSE CEILING-ARMSTRONG/equivalent make	400.00	Sq. Ft.		
	Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm Grid sections) false ceiling of size 24"x24" at levels as shown in the drwng. from FFL. Rate shall be inclusive of providing the total system with installation etc.. The contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations (till Inauguration).				
10.3	FALSE CEILING IN PLY WITH LAMINATE	0.00	Sq. Ft.		
	Providing and fixing Designer Wooden ceiling make / fabricated out of 8/12 mm thick plywood , duly covered with 1.0 mm thick laminate and making grooves in the desired pattern, and duly screwed to GI ceiling sections also incorporating 2" x 2" soft wood sections where ever specified as drawing. The work includes edge bending from all sides and filling the grooves with matching colour paint / polish etc complete as reqd.. The payment area will be the visible area only.				
11.0	ROLLING BLINDS	0.00	Sq. Ft.		
	Providing and fixing Roller blinds of approved design and shade by the Architect,incl all std fittings as per manufacturer's specification. The work to be completed as per specification and approval of the architect. (approved brand Vista, Hunter Dogulus)				

12.0	GLASS SHELVES	40.00	Sq. Ft.		
	Providing and fixing glass panes / shelves of required sizes with all edges neatly grinded, polished and fixed to the wall surfaces using SS D-brackets. The glass shall be 10mm thk plain glass of approved make. Item shall include all required arrangement / hardware/ accessories to complete the job upto the satisfaction of bank / Architect. <u>Note</u> - For the purpose of contractor's payment, front elevation area shall be measured.				
13.0	CHEQUE DROP / SUGGESTION BOX (with glass front)	2.00	Nos.		
	Supplying and fixing wall mounted Cheque Drop Box of outer size 10" (D) X 12" (W) X 20" (H) with front openable partly glazed shutter, lock, slot for dropping cheques from top along with all required hardware & accessories like SS handle, SS butt hinges etc to complete the job upto the satisfaction of the bank / Architect. The box shall be made out of 12mm thk approved plywood finished with 1mm thk approved laminate on outer faces & 0.8mm thk bank's approved colour on all inner faces. The front door shall have 6mm thk glass of size 6"x12" fixed with beach wood beeding. All exposed edges of Plywood shall be fixed with teakwood lipping of appropriate thickness enough to cover the entire exposed edges with 2 coats melamine polish. The box shall be complete with all accessories like SS hinges, SS Handles, Locks etc of approved makes.				
14.0	NOTICE / PIN-UP BOARD	1.00	Nos.		
	Providing & fixing Notice Board made of tag board of approved make & design of size 4'-0" X 3'-0" with powder coated aluminum border / frame. The board should be 3/4" thk straw board with velvet type fabric covering of banks' approved shade.				
15.0	BOXING FOR ROLLING SHUTTER	50.00	Sq. Ft.		
	Providing and fixing rolling shutter panelling / enclosure of required size as per description at Sr. No.9b- ACP Paneling. The rate shall inclusive of necessary hardware fittings like hinges, screws, tower bolts sealant, trap door, locking arrangement etc complete.				
16.0	ALUMINIUM GRILL FOR BULK CASH COUNTER TOP	40.00	Sq. Ft.		
	Providing & fixing 7.5mm thick 48mm X 48mm opening size, white colour powder coated aluminium grill at the top of the cash cabin fixed with 8mm thick teakwood beadings of necessary width. All the exposed wood / beadings shall be neatly finished with 2 coats of melamine polish. All the accessories used shall be concealed type.				
17.0	PAINTING				
17a	PLASTIC EMULSION PAINT	650.00	Sq. Ft.		
	Applying 2 coat of Plastic emulsion paint (asian) of approved make and shade on walls including scrapping off, preparing the base ect color and shade to give an even and smooth surface on new work including necessary scaffolding, coat of cement primer etc. all complete as per direction of Bank. (Other than banking hall).				
17b	ENAMEL PAINT				
	Applying 2 or more coats of enamel paint (NEROLAC/ ASIAN) on wooden/ steel doors & windows to give even & uniform surface.	100.00	Sq. Ft.		
18.0	Providing and fixing 4.5" wide seamless panel on the existing wooden surface i/c cutting the same and fixing with the help of suitable adhesive / nailing etc in approved design and pattern etc complete as reqd.	75.00	Sq.Ft.		
19.0	Providing and fixing of wooden rafter of approx size 7"x2" made out of wooden member and duly cladded with 1 mm thick laminate i/c fixing the same on the existing ceiling / floor etc complete as reqd.	35.00	RMT		
20.0	Providing and fixing of indoor artificial plant to create decorative vertical garden in the existing surface byfixing of base frame and artificial plants in the approved pattern and design etc complete as reqd	48.00	Sq.Ft.		

	ELECTRICAL WORK				
1	SITC of 3 Nos. Kit Kat Rewirable Porcelain fuse carrier & Base with neutral link on wooden frame of 100 amp/415 Volt near meter Box complete with connections complete in all respect to the satisfaction of Bank.	1.00	Set		
2	ELECTRICAL MAIN PANEL: Supply, delivery, installation, testing, commissioning, of L&T make indoor wall/ floor mounted type distribution boards made out of 2 mm thk. CRCA sheet metal duely acid treated premised & painted with 2 coats of enamel paint compartment arrangement for each equipment & bus bar chamber on the top of the panel running horizontal through out its length duly lamp, vermin proof having provision cable by conduit entry , earthing stud as per specification mentioned below duly factory wired confirming to the relevant ISS & as per special condition of contract, making good the damages M.S. Cubical type Panel board should have hinged door at the front. The panel shall be provided with all accessories & following arrangements complete in all respect & direction of EIC (Before Placing the Panel order, firstly it passed by the Bank Authority, otherwise it will not considered). It shall have the following:	1.00	Job		
	INCOMER: 1 No.100 Amp. TPN, MCCB (25 KA breaking capacity) with overvoltage protection as incommer for Main supply. Bus bars 100 Amp., 3 phase, 4 strips, 415 volts, 50 Hz. Electrolytic grade Aluminum Bus Bars insulated with colored Heat Shrinkable PVC Sleeves & duly supported on SMC/DMC molded supports with Antitracking barriers. There should be 2 sets of BUS BAR in such a way that AC load should not be connected to GENERATOR power. 100 amp Onload changeover with 1 Nos 125 amp 25 KA, TP MCCB for DG supply with 100 amp bus bar. Instruments: TWO set of Digital Multi function Meter (One for Main Power Supply & Other for Generator Supply) of standard make for displaying Input Voltage, Ampere, Power factor, KWH used with CTs. Note- 1. All wiring and lugs inside the panel shall be of copper to be fixed using nut-bolt & spring washers. 2. All switchgears shall be properly marked with operaion marks.				
	OUTGOING: 5 Nos. 32/40/63 Amp. TPN MCB (For LDB/INVERTER, PDB, Branch UPS, ATM DB and Spare Feeder) from Generator Powered Bus. 2 Nos. 63 Amp. TPN MCB (For AC DB and Spare Feeders) from Non-Generator Powered Bus. 6-32 AMP DP MCB. 3 Nos (for Glow Sign board, Strong Room & One Spare) from Generator Powered Bus.				
3	Supply & Installation of SPD (Surge Protector Devicve) for general protection of main Electrical Panel Legrad Make Cat No. 412247 (3P+N) , 40 KA, T2- Imax 40KA/pole with complete wiring.	1.00	Nos.		
4	DISTRIBUTION BOARDS:				
a	Rotary Phase selector switch - TO BE LOCATED INSIDE UPS ROOM				
	SITC of 40/63 Amp. Rotary Phase selector switch complete with RYB indication in enclosure for Branch's UPS input power network, ATM and Inverter . Complete in all respect as required.	3.00	Nos.		
b	U.P.S. DISTRIBUTION BOARD (INCOMER DB) - TO BE LOCATED INSIDE UPS ROOM				
	SITC of the surface / recess mounting following way Double door MCB D.B.- Single phase distribution board (Consumer unit) for single phase out going with IP 42 protection incl. the followings accessories – incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
	INCOMER (Branch UPS & ATM UPS)				

	1 NOS 63 A DPMCB				
	OUTGOINGS				
	2 Nos- 40 Amp DP MCB+ 1 Spare				
	SET AS ABOVE	1.00	Nos		
c	<u>U.P.S. DISTRIBUTION BOARD (OUTGOING DB) - TO BE LOCATED INSIDE UPS ROOM</u>				
	SITC of the surface / recess mounting following way Double door MCB D.B.- Single phase distribution board (Consumer unit) for single phase out going with IP 42 protection incl. the followings accessories – incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
	INCOMER (Branch UPS & ATM UPS)				
	1 NOS 40 A DPMCB				
	OUTGOINGS				
	2 Nos- 40 Amp DP MCB+ 1 Spare				
	SET AS ABOVE	1.00	Nos		
d	<u>INVERTER INCOMER & OUTGOING MS BOX - TO BE LOCATED INSIDE UPS ROOM</u>				
	SITC of 32/40 Amp. DP MCB in a MS encloser Single Door complete complete in all respects as required.	2.00	Nos.		
e	<u>LIGHT DISTRIBUTION BOARD</u>				
	SITC of the surface / recess mounting following way MCB three phase distribution board for single phase outgoing with IP 42 protection , direct on wall incl. the followings accessories				
	INCOMER - Incoming Supply from Inverter output				
	1 No. DPMCB 40 Amp				
	OUTGOINGS				
	6-8 Nos SPMCB 6-10 Amp				
	SET AS ABOVE	1.00	Nos		
	incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
f	<u>POWER DISTRIBUTION BOARD</u>				
	SITC of the surface / recess mounting following way MCB three phase distribution board for single phase outgoing with IP 42 protection , direct on wall incl. the followings accessories				
	INCOMER				
	1 No. TPMCB 63 Amp				
	OUTGOINGS				
	6-12 Nos SPMCB 16/32 Amp				
	SET AS ABOVE	1.00	Nos		
	incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
g	<u>AC DISTRIBUTION BOARD</u>				
	SITC of the surface / recess mounting following way MCB three phase distribution board for single phase outgoing with IP 42 protection , direct on wall incl. the followings accessories				
	INCOMER				
	1 No. TPMCB 63 Amp				
	OUTGOINGS				
	8 Nos DPMCB 25 Amp + 2 Nos Spare				
	SET AS ABOVE	1.00	Nos		
	incl. Electrical connection, earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
h	SITC of 12 WAY SPN Double Door DB complete with 1 No. 40 AMP DP MCB as incomer and 10 NOS. 6-10 AMP SPMCB as outgoing for Branch UPS power distribution to Computer points on Staff Counters / Tables.	1.00	Nos.		

i	SITC of 8 WAY SPN Double Door DB complete with 1 No. 32 AMP DP MCB as incomer and 6 NOS. 6-10 AMP SPMCB as outgoing for UPS power distribution points for ESSENTIAL LODAS like CCTV System, Fire & Burglar Alarm Systems, Networking Rack, ATM (if separate ATM UPS not available) and select Light points powered by UPS.	1.00	Nos.		
j	SITC of 1 no. 10A DP MCB with MS enclosure Industrial Plug Socket Unit with 1.0 mtr long 3 core 2.5 Sqmm Copper flexible cable for strong room power supply switch board installed at STRONG ROOM/SAFE ROOM entrance Gate complete in all respect as required.	1.00	Nos.		
k	ATM DISTRIBUTION BOARD (ATM DB) - to be place near to ATM Room				
	SITC of the surface / recess mounting following way MCB three phase distribution board for single phase outgoing with IP 42 protection , direct on wall incl. the followings accessories				
	INCOMER - Incoming Supply from Inverter output				
	1 No. DPMCB 40 Amp				
	OUTGOINGS				
	10 Amp SP MCB - 3 Nos. (ATM light)				
	2 Nos DPMCB 25 Amp + 1 Nos Spare (ATM AC)				
	SET AS ABOVE	1.00	Nos		
	incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
5	CABLES				
	All cables / wires shall be routed through PVC conduits / bends / elbows etc., as required, of appropriate dia. The conduits shall be clamped firmly to the walls / columns / pillars etc. with clips / clamps and fasteners rigidly even if above false ceiling.				
	Complete job shall include cutting chiseling in walls, floor and making good of all chases / cuts etc. with combination of cement-mortar, including painting with type and shade of existing wall. The work shall be completed to the satisfaction of Bank. NO CABLE / WIRE / CONDUIT SHALL BE VISIBLE IN THE BRANCH HALL / CUSTOMER LOBBY / STAFF WORKING AREA.				
a	SITC of 4 Core 25.0 Sq.mm Copper conductor Armoured Cable for service line connection up to Kit kat fuse unit complete in all respect as required.	15.00	Mtr.		
b	SITC of 4 core 6.0 Sq.mm Copper conductor Armoured Cable from Main Panel to INVERTER, LDB, ATM UPS & Branch UPS input power supply.	40.00	Mtr.		
c	SITC of 2 runs of 6.0 Sq.mm and 1 no. of 2.5 Sqmm FRLS PVC Insulated Multistrand Copper conductor wire from selector switch to UPS/INVERTER to UPS/LDB Distribution boards.	20.00	Mtr.		
d	SITC of 4 core 10 Sq.mm + 1 X 4 sq.mm Copper conductor Armoured Cable from main Panel / Non Generator power Bus to AC DB.	10.00	Mtr.		
e	SITC of Sub main Wiring for Strong room and Glow Sign Board with 2 No. 4.0 Sq.mm and 1 No. 2.5 Sq.mm Multistrand Copper conductor FR pvc/ xlpe insulated Wire in required dia pvc conduit complete in all respects as required.	35.00	Mtr.		
6	AC POINT (High wall and Cassette)				
a	SITC of AC Point Wiring with 2 No. 4.0 Sq.mm and 1 No. 2.5 Sq.mm Multistrand Copper Wire & Industrial plug & Socket with 10/16 Amp. DPMCB complete in all respect as required by the Bank (for 1.0 / 1.5 TR Hi-Wall Split ACs)	1.00	Nos.		
b	SITC of AC Point Wiring with 2 No. 6.0 Sq.mm and 1 No. 2.5 Sq.mm Multistrand Copper Wire & Industrial plug & Socket with 20 Amp. DPMCB complete in all respect as required by the Bank (for 2.0 TR Hi-Wall Split / Cassette ACs). The point shall be placed near outdoor unit.	3.00	Nos.		
c	SITC of AC Point Wiring with 4 No. 6.0 Sq.mm and 1 No. 2.5 Sq.mm Multistrand Copper Wire & 20/32/40 Amp. TPN MCB in a MS Box complete in all respect as required by the Bank (for 3.0 TR/4.0 TR Hi-Wall Cassette ACs). The point shall be placed near outdoor unit.	0.00	Nos.		

7	EARTHING				
a	Preparation and commissioning of earth pits with PIP technology GEL type 50mmdia 3000mm long earth electro. (One Dedicated Earthing for ATM UPS, Branch UPS and Main Electrical Panel)	2.00	Nos.		
b	Supply fixing and termination of 32x6 mm G.I. strip with earth station below ground level etc as required.	30.00	Mtr.		
c	SITC of Earthing conductor from earth terminal to load point with 10 sq mm multstrand copper conductor FR pvc /XLPE insulated cable in required dia PVC heavy duty conduit complete in all respect as required.	35.00	Mtr.		
8	UPS/RAW POWER POINT				
	Computer/Raw Power point wiring in heavy duty PVC conduit of IS specification of proper size with 3nos 2.5sq.mm single core PVC insulated stranded copper wire 1.1KV grade (Finolex/Havells/Polycab/ RR Kabel/ Richa/KEI or equivalent) and with all material supply installation and commissioning complete from UPS DB/PDB (Raw). The wiring shall be carried out on surface above false ceiling by chiseling the existing surface and plastering the same with cement etc. after fixing the heavy duty PVC conduit with all ccessories like saddles screws, bends T-joint etc. 2 coats of painting Matching to the surface including supply installing, testing, commissioning of modular plate type switch and socket (Legrands / Havells or equivalent) for computer terminal on sheet steel enclosure (cadmium plated),duly fitted with screw to the steel conduit and fixed to the wall partition furniture with all interconnection and proper earthing. All the opening shall be covered with blank plate and be sealed to make the box vermin proof.B48				
a	With 3nos 6A socket with single 16A switch. (UPS POINT)	8.00	Nos.		
b	With 2nos 16A socket with individual 16A switch. (RAW POWER POINT)	6.00	Nos.		
c	With 1nos 16A socket with individual 16A switch. (RAW POWER POINT)	3.00	Nos.		
9	LIGHT/FAN POINT				
	Wiring for light/fan/exhaust fan points using 3 X 1.5 1.1 kV grade PVC insulated stranded copper conductor wire (Finolex/ Havell's/ Richa/ RR kebel/ KEI or equivalent) for phase, neutral and earth (with proper R,Y,B color code) in 25 mm dia heavy duty PVC conduit along with associated accessories like MS junction boxes, bends, saddles, screws et. concealed in wall, floor, under flooring, below false ceiling or on surface as well as suspended from ceiling with 25mm X 3 mm MS flat suspenders duly painted above false ceiling from individual light/Fan/Exhaust Fan point outlet. etc. to individual modular type switch boards, 10 Amp modular plate type switches etc.(MK/Legrands/Havel's or equivalent), as required complete including circuit wiring with 3 X 2.5 sqmm. 1.1 kV grade PVC insulated stranded copper conductor wire and as per site requirement and as instructed by Engineer In-Charge.				
a	One light point including the cost of 6A modular switch	15.00	Nos.		
b	Two light point including the cost of 6A modular switch	15.00	Nos.		
c	Three light point including the cost of 6A modular switch	10.00	Nos.		
d	Four light point including the cost of 6A modular switch	0.00	Nos.		
e	Ceiling Fan Point including the cost of 6A Switch along with 5 step electronic fan regulator.	1.00	Nos.		
f	Wall Fan Point along with 6 AMP switch & 3 PIN Socket	7.00	Nos.		
g	Exhaust Fan Point along with 6 AMP switch & 3 PIN Socket	2.00	Nos.		
h	SITC of Call Bell Point & Call Bell.	1.00	Nos.		
i	6A Switch & Plug point in same switch board	3.00	Nos.		
j	Cove light points including the cost of 6A modular switch	0.00	Nos.		
k	16A, 5 pin industrail plug & Socket with 25 A MCB protected (for Strong Room/SAFE room & Record room)	3.00	Nos.		
10	DATA CABLING & POINT				
	Supplying and laying of D-Link make CAT-6 (UTP) cable through trenches / conduits.				
a	Supplying and laying D-link make CAT-6 Cable in P.V.C. Conduit Complete with CAT-6 information outlet with plate & suface Box at individual Tables	8.00	Nos.		
b	Supplying and fixing of 1 mtr long crimped patch cord	8.00	Nos.		
c	Supplying and fixing of 2 mtr long crimped patch cord	8.00	Nos.		

d	Supplying and fixing of 12 U Rack complete with exhaust fan, lockable front glass door, cable managers, electrical socket board etc.	1.00	Nos.		
e	Supplying and fixing of 24 port jack panel	1.00	Nos.		
11	VOICE NETWORKING				
a	Supply and fixing of 1 nos. 30 pair telephone MDF consisting of tag blocks, disconnecter type, complete with powder coated metal enclose, krone tag block mounting arrangement telephone distribution chart and locking arrangement [for P&T/EPABX]	1.00	Job		
b	Supplying and laying telephone cables 0.5mm dia 2 pair electrolytic tinned copper conductors PVC insulated and twisted pair with rip cord, including PVC conduits/Racewaysand RJ11 telephone socket outlet. The rate shall include termination at both ends on tag blocks. 2 Nos. RJ11 Telephone socket with plate and box	3.00	No.		
12	FIRE & ELECTRICAL SAFETY INDICATION				
a	Supply and installation of Vinyl sticker for on Electrical DBs like, " Switch Off at Night", Switch Off For Safety , etc	4.00	Nos.		
b	SITC of a set of indication lamp set (4 Nos. RED, YELLOW, BLUE & GREEN Color) in a concealed PVC modular box.	1.00	No.		
c	Wiring in heavy duty PVC conduit of IS specification of proper size with 2 runs of 1.5sq.mm single core PVC insulated stranded copper wire 1.1KV grade (Finolex/Havells/Polycab/ RR Kabel/ Richa/KEI or equivalent) and with all material supply installation and commissioning complete from Computer Counter DB, AC DB, LDB, PDB outgoing to a set of indication lamp set (4 Nos. RED, YELLOW, BLUE & GREEN Color).	10.00	Mtrs		
13	SITC of Angle holder complete in all respect with 9W LED lamp	2.00	Nos.		
14	SITC of LED COVE/ STRIP LIGHT WITH ITS ELECTRONIC DRIVER(BLUE COLOUR):- SITC of bright LED strip light with its electronic driver complete as required. PHILIPS, WIPRO, HAVELLS, CG.	75.00	Mtrs		
15	Supply and laying of ISI mark Electrical safety Insulating mat of dimension 1000mm X 1000mm in UPS Room.	1.00	Nos.		
16	FIXTURES/FANS (All light fixtures and fans to be supplied COMMERCIAL MODELS only)				
a	SITC of 36W 2' X 2' Square decorative LED light fitting of approved model & make. (contractor to get the model approved from bank before installation)	14.00	Nos.		
b	SITC of surface mounted 20W LED batten light including required hanging arrangement wherever required	8.00	Nos.		
c	SITC of 10W LED Down Lighter of approved make	28.00	Nos.		
d	SITC of 5-7W LED COB / Spot light of approved model & make (contractor to get the model approved from bank before installation)	0.00	Nos.		
e	SITC of 450mm Wall Mounted full metal body Fan of approved make.	6.00	Nos.		
f	SITC of 1200mm / 900mm Ceiling Fan of approved make with required down rod and hanging arrangement	1.00	Nos.		
g	SITC of 9" metal body exhaust fan of approved make.	2.00	Nos.		
	AIR CONDITIONING WORKS				
1	Supplying, erection, testing and commissioning following wall mounted Split / Root mounted split/cassette units of with cordless remote complete with all necessary fittings duly insulated with 9 mm thick nitrile rubber pipe insulation with (All coils – copper only) , fan and fan motor, machine control panel improved Refrigerant Joints. Air conditioners shall be fitted with hermetically sealed type suction cooled reciprocating or discharge cooled rotary compressor or scroll compressor. Compressor unit operating on R32/ R-410. All complete as per drawing, approval and instructions of the Architect/ Employer (Rates to be inclusive of Copper refrigerant pipe with insulation and Drain pipe up to 3 Mtr length) . <i>Item to include powder coated outdoor stands as per the manufacturer specifications.</i>				
a	2.0 TR wall mounted split unit (Minimum 5-Star rating inverter type) including all necessary fittings and mountings as specified by the manufacturer	Nos.	3.00		
b	1.5 TR wall mounted split unit (Minimum 5-Star rating inverter type) including all necessary fittings and mountings as specified by the manufacturer	Nos.	0.00		

c	1.0 TR wall mounted split unit (Minimum 5-Star rating inverter type) including all necessary fittings and mountings as specified by the manufacturer	Nos.	1.00		
2	EXTRA REFRIGERANT PIPING				
	Supplying and laying of Extra copper refrigerant piping with nitrile rubber pipe insulation, both of size as specified by the manufacturer suitable for 1.5 TR TR Split type AC and 2.0 TR TR Cassette AC (From Indoor to outdoor Units).				
a	For 1.0 TR/1.5 TR/2.0 TR Split AC as specified by the manufacturer	Mtr.	100.00		
b	For 1.5 TR / 2.0 TR Cassette AC as specified by the manufacturer	Mtr.	0.00		
3	DRAIN PIPING				
	Providing and fixing drain piping up to drain as directed by the engineer incharge with all accessories e.g. elbows, unions, sockets, reducers, reducing tees, nipples etc. Complete job including cutting chiseling in walls, floor and making good of all chases/ cuts etc. and				
	discharging the drain into a floor trap/ gully as per site conditions with insulation, both as specified by the manufacturer.				
a	25 mm dia PVC drain pipe for Split AC	Mtr.	100.00		
b	32 mm dia PVC drain pipe for Cassette AC	Mtr.	0.00		
4	Providing and fixing Stabilizer with 3 step relay and input voltage range of 170-270 V and output to be 230 V (Blue bird/ Logic state/ Inline/ V-gourd) (copper winding).				
a	4 KVA (For 1.0 TR / 1.5 TR AC)	Nos.	1.00		
b	5 KVA (For 2.0 TR AC)	Nos.	3.00		
5	Supplying and laying of Extra Electrical interconnecting control cables from indoor to outdoor of size as specified by the manufacturer suitable for 1.5/2.0/3.0 TR Cassette type AC.	Mtr.	0.00		
6	Supplying and laying of Extra Electrical interconnecting control cable from indoor to outdoor of size as specified by the manufacturer suitable for 1.0TR/1.5TR/2.0 TR Split type AC.	Mtr.	100.00		
7	Providing and fixing of lockable caging (including stand) for outdoor unit grouted on wall or on roof with open able shutter made of 10 X 10 mm MS square bars placed vertically @ 5" c/c welded with 40 X 3 mm MS flat all- round. Item includes all necessary hardware, priming coat, synthetic enamel paint, hanger, clamps other accessories etc. All complete as per approval and instructions of the Architect/ employer.				
a	For 2.0 TR / 1.5 TR ceiling mounted cassette unit	Nos.	0.00		
b	For 1.0/1.5/2.0 TR Hi Wall split units	Nos.	4.00		
8	Supply, installation, testing and commissioning of Drain pumps minimum 2 litre hi flow tank with all fixing materials etc. all complete as per the directions of Architect/ Engineer-in-charge.	Nos.	0.00		
9	Providing and fixing timer switch for switching power alternatively between two A/C, timer will be analogue dial type adjustable TIMER switch which is adjustable over 24hrs. With 15 minutes intervals and is to have 1NO+1NC (20A) contact. Timer will have its own backup battery and will be enclosed in 16gauge MS Box with acrylic lid together with suitable connector block. (ABB/MDS/L&T)	Nos.	0.00		
10	Removing, Repairing & Refixing Old Split IDU & ODU & STABILIZER & MS FRAME from existing location at UCO Bank Aligarh Branch to proposed location. It include necessary repair & filling coolant gas as required as per direction given by Architect. It also include concealing copper pipe & drain pipe to drain point as per instruction.	Nos.	0.00		
	TOTAL (Rs.)				
	Buy back items Discount for (Buy Back Items)(-) i/c old existing furniture, tables, counters, wooden storage cabinets, paneling, electrical wiring, lighting fixtures, data cabling, switch boards etc.Dismantling of existing wooden furnishing/electrical work i/c disposal of rubbish and making temporary arrangements for running of branch. (Buy Back Items)(-) COMPULSORY ITEM				
	GRAND TOTAL (Rs.)				
	* GST EXTRA AS APPLICABLE				