



**TENDER FOR INTERIOR FURNISHING WORKS OF UCO BANK SATELLITE  
BRANCH & ATM (UNDER AHMEDABAD ZONAL OFFICE)**

**PART 2 (B.O.Q. / PRICE BID / FINANCIAL BID / COMMERCIAL BID)**

<b>ISSUE TO (NAME OF CONTRACTOR)</b>	
<b>ADDRESS</b>	
<b>CLIENT</b>	<p><b>DEPUTY GENERAL MANAGER UCO BANK, ZONAL OFFICE - AHMEDABAD, GAD DEPARTMENT , 7TH FLOOR, UCO BHAVAN, NR. SANYAS ASHRAM, ASHRAM ROAD, AHMEDABAD - 380009</b></p>
<b>ARCHITECT</b>	<p><b>M/S SHIVAM GANDHI 21, VIRNAGAR SOCIETY, OPP. I.D.B.I. BANK, NR.GAYATRI HOSPITAL, BHIMJIPURA, NEW WADAJ, AHMEDABAD - 380013 (M) 9016310164</b></p>



**FINANCIAL BID FOR INTERIOR FURNISHING WORKS OF UCO BANK  
SATELLITE BRANCH & ATM  
(UNDER AHMEDABAD ZONAL OFFICE)**

SR. NO.	PARTICULARS	TOTAL AMOUNT IN (RS.)
PART - A	TOTAL AMOUNT OF NEW INTERIOR FURNISHING WORKS <u>EXCLUDING G.S.T.</u>	
PART - B	TOTAL AMOUNT OF EXISTING FURNISHING RENOVATION WORKS <u>EXCLUDING G.S.T.</u>	
	TOTAL AMOUNT OF NEW & EXISTING FURNISHING WORKS (PART-A + PART-B) <u>EXCLUDING G.S.T.</u>	
	IN WORDS :-	

**SIGN & STAMP OF AUTHORIZED PERSON OF CONTRACTOR FIRM**

BOQ FOR INTERIOR FURNISHING WORKS OF UCO BANK SATELLITE BRANCH & ATM (UNDER AHMEDABAD ZONAL OFFICE)					
SR. NO.	DESCRIPTION	QTY.	UNIT	RATE IN RS.	AMOUNT IN RS.
1	Demolition / Removal of Existing Works from existing Premises ( Branch / ATM / E-Lobby Etc.) & removal of debris away from site. ( Note :- Contractor is instructed to First, Visit the Existing Premises before quote the Rate)				
1.1	Demolition / Removal of Existing Ceiling Works & removal of debris away from site	1	Job		
	Demolition / Removal of existing Wooden / Gypsum Ceiling / Greed Ceiling / Armstrong Ceiling works & supporting frame structure of existing branch including disposal of un-useful material from site all as directed by consultant. The work also includes shorting & staking of useful materials. The work should be carefully done so existing branch functions, staff & customers should not disturb & no damage to the building structure. The rate should including labor, loading, unloading, transportation etc. <u>(Note :- The Branch is located on First Floor)</u>				
1.2	Demolition / Removal of existing furniture items like wooden partitions, doors, tables, storage, Paneling works	1	Job		
	Demolition / Removal of existing furniture items like wooden partitions, doors, tables, storage, Paneling works of existing branch including disposal of un-useful material from site all as directed by consultant. The work also includes shorting & staking of useful materials. The work should be carefully done so existing branch functions, staff & customers should not disturb & no damage to the building structure. The rate should including labor, loading, unloading, transportation etc. <u>(Note :- The Branch is located on First Floor)</u>				
2	GYPSUM BOARD FALSE CEILING: (NOTE :- THE RATE SHOULD INCLUDING PROVIDING OF 2 COAT OF BIRLA PUTTY, PRIMER + THREE COAT OF PLASTIC EMULSION PAINT)	500	SFT		
	Providing & fixing as per design with suspended false ceiling consisting of 12mm.thk.Gyp. board suspended on G.I. framework to consists of G.I. perimeter channels 0.55 mm thk. x 20mm .x 30mm. along perimeter of false ceiling; screw fixed to wall/partition with nylon sleeves & screws @ 600mm. dc. Suspending G.I. Intermediate channels of size 0.9mm thk.x45mmx15mm. from the soffit at max. distance 1220mm. dc with ceiling angle 0.55mm. thk.x2n5mm.x10mm. Fixed to soffit using proprietary supplied G.I. Cleats & steel expansion fasteners. Ceiling section 0.55mm thk. xweb size 51.5mm & flanges 26mm. Each & 10.5 mm. lips fixed perpendicular to intermediate channel at 457mm. c/c Gyp board is screw fixed to ceiling section with 25mm. drywall screws at 230mm. c/c. boards to be finished with proprietary supplied jointing tape & jointing compound & sand papered to achieve a smooth finish etc. Complete or as directed by the Architect/Bank. Gyp ceiling where necessary as normal specification Rate should include all types of cut-outs, grooves, moulding & plain troughs for tube lights / Down Lighter as directed by the designer. Note: Where RCC Slab is old and concrete is weak, the GI suspended channel shall be fixed with epoxy chemical and necessary load test to be carried out before fixing Gypsum board fixing. Rate shall be inclusive of epoxy chemical and fixing of suspenders with chemical.				
3	False Ceiling (Armstrong Silhouette type)	700	SFT		

	<p>Providing &amp; fixing of sillehoutte type Mineral Fiber false ceiling of "Armstrong" make tiles, with hot dipped galvanized steel grid work, surface chemically cleaned capping pre-finished in backed polyester paint, Main Tees of size 33 (H) X 24mm every 1.2 M centre to centre, rotary stitched Cross Tee at 0.60 M centre to centre to form a grid of 600mm X 600mm and suspending the grid from RCC roof using 2mm G. I. rod and 6mm nylon rawl plug at every 1200mm intervals and laying "Armstrong" New NDF mineral fiber Acoustic ceiling tiles. New NDF Tegular edge 15mm thick of size 595 X 595mm Tiles are having fire rating of 60 minutes as per BS47G/23 of 1987. Light Reflection &gt; 75 %, Noise Reduction Coefficient (NRC) of 0.55 to 0.60, Sound Attenuation of 32 db, K = 0.52-0.57 W/mk. Humidity Resistance (RH value) up to 99 % at 50°C. The tile comes pre-painted with three coats of white on facing side and one coat primer on back side. The above ceiling will be completed as per direction of Architect/ Bank. The measurement shall be as per plan area of the premises.</p>				
<b>4</b>	<b>Providing Partitions</b>				
<b>4.1</b>	<b>Full Height / Low Height Solid Wooden Partition</b>	120	SFT		
	<p>Providing &amp; fixing 3" thick solid partition for made up of 18 gauge 50x50 mm Aluminium section framework at 450mmx600 mm c/c both ways (or as directed by the Architect); 8 mm commercial plywood &amp; 1 mm laminate from both sides. Partition should be finished with specified finish as per design. The rate includes providing 35 mm thick flush door with necessary lipping patti polished. Rate includes all necessary hardware ( i.e ball bearing hinges of approved make, door closure, Cylindrical Lock with key, Door stopper etc) Exposed edges of the partition should have 75x12 mm matching wood Patti with groove in between. All provisions to be made for all electrical, networking, telephone etc. boxes onto partition framework at required heights/levels with necessary additional supports &amp;/or scaffolding as required. The rate includes all necessary hardware &amp; cleaning of partition to the satisfaction of the Architect etc. complete. (Note: In case of false ceiling, the vertical Aluminium section to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only).</p>				
<b>4.2</b>	<b>Partly Wooden &amp; Partly Glazed Full Height / Low Height Partition</b>	180	SFT		
	<p>Providing &amp; fixing 3" thick partly glazed partition with 12mm thick clear float glass for made up of 18 gauge 50x50 mm Aluminium section framework at 450mmx600 mm c/c both ways (or as directed by the Architect); 8 mm commercial MR plywood &amp; 1 mm laminate from both sides. Partition should be finished with specified finish as per design. The rate includes providing 35 mm thick flush door finished with 1mm laminate of approved make/shade on both sides with necessary lipping patti polished. Rate includes all necessary hardware ( i.e ball bearing hinges of approved make, door closure, Cylindrical Lock with key, Door stopper etc) Exposed edges of the partition should have 75x12 mm matching wood Patti with groove in between. All provisions to be made for all electrical, networking, telephone etc. boxes onto partition framework at required heights/levels with necessary additional supports &amp;/or scaffolding as required. (Note: In case of false ceiling, the vertical Aluminium section members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only).</p>				
<b>4.3</b>	<b>Glazed Partition using 12 mm thick toughened glass for Entrance Façade of Branch / E-Lobby / ATM</b>	15	SFT		

	P/F 12mm thick fix Toughened glass partition for Entrance Façade of Branch / E-Lobby / ATM & for glass divider in E-Lobby. The Full height Glass Partition to be fixed by the fixing the wooden partition structure above 7'0" / Ceiling height & upto RCC Slab / Beam Bottom to be made out of 2" x 1" x 1.5mm thick aluminum section frame members @ 1'-6" x 2'-0" c/c with both way 6mm thick MR grade approved make plywood on both sides and finished with 1mm thick approved make laminate of approved color & shade. Lower portion below 7'-0" / bottom of the ceiling height of partition to be provide with 12mm thick toughened glass of Modiguard / Saint Gobain make glass with necessary steam beech molding with laquore polish. The glass will have decorative / itching / frosting / film etc. complete. All the exposed surface of beading, molding, frames shall be duly laquore polish. The item includes fixing, transportation, loading, unloading, labor for fixing glass shutters & hardware etc. The antiglare glass film of Garware make to be fixed on glass portions by approving glass film design from architect / consultant.				
4.4	<b>Glass Partition using 12 mm thick toughened glass for glass divider in ATM / E-Lobby for privacy &amp; security for customers.</b>	1	No.		
	Glass Partition using 12 mm thick toughened glass for glass divider in ATM / E-Lobby for privacy & security for customers using 12mm thick toughened glass of Modiguard / Saint Gobain make glass of size 3'9" L x 5'0" Ht & to be supported & fixed by providing & fixing of S.S. D-Brackets at 2 nos at bottom & 3 nos at wall side. The glass will have decorative / itching / frosting / film etc. complete. All the exposed surface of beading, molding, frames shall be duly laquore polish. The item includes fixing, transportation, loading, unloading, labor for fixing glass shutters & hardware etc.				
4.5	<b>Aluminum Fix Glazing Partition (Using 8mm Thick Toughned Glass)</b>	0	SFT		
	P/f Aluminum Fix Glazing Partition using power coated Aluminum Section of Jindal make of heavy section 200mmx100mm at bottom & top for shutter frame with fixing of 8 mm thick toughned glass in paneling. The framing should made from powder coated heavy quality jindal make hollow section of size 85 mm x 50mm & thick section all as per architect design & direction.				
4.6	<b>Full Height / Low Height Solid Partition Using Bison Board. (For UPS Room)</b>	135	SFT		
	Providing & fixing 3" thick solid partition made by using 18 gauge 50x50 mm Aluminium section framework at 450mmx600 mm c/c both ways (or as directed by the Architect); 12 mm Bison Board on both sides. Partition should be finished with 2 coat of Putty & Primer & 3 coat of Plastic Paint of approved make & shadeall as per architect guidance. The rate includes providing 32 mm thick FRP door with necessary oil based paint. Rate includes all necessary hardware ( i.e ball bearing hinges of approved make, door closure, Cylindrical Lock with key, Door stopper etc) All provisions to be made for all electrical, networking, telephone etc. boxes onto partition framework at required heights/levels with necessary additional supports &/or scaffolding as required. The rate includes all necessary hardware & cleaning of partition to the satisfaction of the Architect etc. complete. (Note: In case of false ceiling, the vertical Aluminium section to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only).				
5	<b>Providing &amp; Fixing of Doors</b>				
5.1	<b>Main Entrance Glazed Door with 12 mm thick toughened glass dully fixed with Ozone / Godrej / Ebco make heavy duty floor spring.</b>	52	SFT		
	P/F 12mm thick fix toughened glazed door in entrance o be providing in two shutter opening (size - 2No. 3.0' x 7.0'). The item also includes fixing of all necessary hardware like door handle, Ozone / Ebco / Godrej make heavy duty floor spring, labor for making glass hall, transportation, loading, unloading, labor for fixing glass door & hardware etc. The antiglare glass film of Garware make to be fixed on glass door shutters by approving glass film design from architect / consultant.				

5.2	<b>Aluminum Section Glazed Door (Double Leaf) With 8mm Thick Toughened glass for Entrance Door.</b>	0	SFT		
	Providing & fixing powder coated Aluminum section frame of size 65mmx45mm to be fixed with 8mm thick toughened glass with decorative designs / frosting / bank logo with installation of all necessary hardwares such as locking arrangement, handles, rubber fixing etc. complete as per detailed drawings for Single or Double leaf. The Aluminum section should be of Jindal make and must be powder costing is approved color etc. complete as per direction of Architect.				
5.3	<b>Laminated flush door to be fixed by providing Wooden / Stone Door Frame</b>	35	SFT		
	P/F 30 mm thick of approved make flush door to be finished with 1 mm thick approved make laminate of on both side fixed by providing tickwood frame (in case of door inside banking hall area) / stone frame (incase of utility area) using MS anchor fastner. The item includes all hardware & polished on exposed wooden edges as directed by consultant.				
5.4	<b>Wooden Flap Door</b>	0	SFT		
	Supplying & fixing wooden flap door shutter made out of 19mm thick plywood of MR grade UF Plywood of approved make with 1mm thick laminate of approved make on both sides with necessary periphery steam beech beading with laquore polish. Door will have required hinges, stopper, handle etc. complete as per direction of Architect.				
5.5	<b>Heavy duty door closer</b>	5	No		
	Providing & fixing ISI approved heavy duty door closer of mate aluminum body of Ozone / Godrej / Efficient gadget / Hettich make.				
6	<b>PROVIDING OF MOVABLE FURNITURE (MANAGER, OFFICER, CLERK TABLE &amp; CASHIER TABLE) :-</b>				
6.1	<b>Branch Manager Table (Size :- 5'-9" Length X 2'-9" Width X 2'-6" Height)</b>	0	NO		
	Providing & fixing new wooden table for Branch Manager made out of 19mm thick MR grade UF plywood of approved make boxing with top, sides, front etc. the table will have one drawer cabinate unit with one nos. of required size drawer with telescopic channel etc. and below openable shutter with lock, handles, stoppers. The drawer will have required shelves etc. Front facia of table will have required thickness. The entire table will be finished with 1mm thick laminate of approved color and shade. All the exposed surface will have steam beech molding with laquore polish. The table will have approved quality key board tray, cable manager, foot rest, cup stand etc. The all inner surface of table, drawer & storage to be finished with approved make & approved shade 0.8mm thick inner laminate / liner etc. complete as per direction of Architect. (Size :- 5'-3" Length X 2'-6" Width X 2'-6" Height)				
6.2	<b>Officer Table (Size :- 5'-3" Length X 2'-6" Width X 2'-6" Height)</b>	1	NO		

	Providing & fixing new wooden table for Officer's made out of 19mm thick MR grade UF plywood of approved make boxing with top, sides, front etc. the table will have one drawer cabinate unit with one nos. of required size drawer with telescopic channel etc. and below openable shutter with lock, handles, stoppers. The drawer will have required shelves etc. Front facia of table will have required thickness. The entire table will be finished with 1mm thick laminate of approved color and shade. All the exposed surface will have steam beech molding with laquore polish. The table will have approved quality key board tray, cable manager, foot rest, cup stand etc. The all inner surface of table, drawer & storage to be finished with approved make & approved shade 0.8mm thick inner laminate / liner etc. complete as per direction of Architect. (Size :- 5'-3" Length X 2'-6" Width X 2'-6" Height)				
6.3	<b>Workstation / Clerk Table (Size :- 4'-6" Length X 2'-6" Width X 2'-6" Height)</b>	1	NO		
	Providing & fixing new wooden table for Officer's made out of 19mm thick MR grade UF plywood of approved make boxing with top, sides, front etc. the table will have one drawer cabinate unit with one nos. of required size drawer with telescopic channel etc. and below openable shutter with lock, handles, stoppers. The drawer will have required shelves etc. Front facia of table will have required thickness. The entire table will be finished with 1mm thick laminate of approved color and shade. All the exposed surface will have steam beech molding with laquore polish. The table will have approved quality key board tray, cable manager, foot rest, cup stand etc. The all inner surface of table, drawer & storage to be finished with approved make & approved shade 0.8mm thick inner laminate / liner etc. complete as per direction of Architect. (Size :- 4'-3" Length X 2'-6" Width X 2'-6" Height)				
7	<b>Cash Counter (Size :- 5'-0" Length X 2'-6" Width X 2'-6" Height)</b>	5.5	RFT		
	Providing & fixing new cash counter made out of hard wood frame, 19mm thick MR grade UF plywood of approved make boxing. The counter will have top at 2'-6" height with 2'-6" width as per design and customer top at 3'-9" to 4'-0" height with 1'-3" width. At sitting area the counter will have three drawers made out of 19mm thick MR grade UF plywood of approved make with necessary telescopic channels of approved quality, multipurpose locks etc. The counter will have approved quality key board tray, cable manager, foot rest, cup stand. The entire counter will be finished with 1mm thick approved make laminate. The counter will have 12mm thick glass front above customer top as per requirement. The all inner surface of table, drawer & storage to be finished with approved make & approved shade 0.8mm thick inner laminate / liner etc. complete as per direction of Architect. ( Size :- 5'-0" Length or length as per layout x 2'-9" Width x 2'-6" Height all as per direction.)				
8	<b>Cash Shorting Table (Size :- 3'-0" Length or length as per layout X 1'-8" Width X 2'-6" Height)</b>	1	NOS.		
	Providing & fixing new wooden table for cash shorting made out of 19mm thick MR grade UF plywood of approved make boxing with top, sides, front etc. the table will have one drawer cabinate unit with one nos. of required size drawer with telescopic channel etc. with lock, handles. Front facia of table will have required thickness. The entire table will be finished with 1mm thick laminate of approved color and shade. All the exposed surface will have steam beech molding with laquore polish. The table will have approved quality key board tray, cable manager, foot rest, cup stand etc. The all inner surface of table, drawer & storage to be finished with approved make & approved shade 0.8mm thick inner laminate / liner etc. complete as per direction of Architect. ( Size :- 4'-6" Length or length as per layout x 2'-0" Width x 2'-6" Height all as per direction.)				
9	<b>Table top Glass (10mm thick Toughned Glass)</b>	18	SFT		

	Providing & fixing 8mm thick Modiguard / Saint Gobain make toughened glass with polished crystal edge finished etc. on table top complete as per direction of Architect.				
10	<b>Customer Writing Desk / Cheque Drop Box</b>	1	NOS.		
	Supplying and fixing wall hung customer's writing desk of Size 4'-0" X 1'-6" x 1'-0" made out of 19mm thick plywood of MR grade UF Archid ply / Silicon Ply / Kit Ply make with required shelf compartments for keeping slips, finished with matching shade laminate 1.5mm thick laminate of Archid laminate / Formica laminate make on top and sides with liquor polish (matching with the laminate) to all exposed surfaces with required teak wood beading etc. complete as per direction of Architect. The writing desk will have 12mm thick Float glass with crystal edge finish etc. complete as per direction.				
	Providing & fixing Cheque Drop Box made from 19mm thick MR grade UF plywood of approved make. Door made of 12mm thick plywood of approved make to the size of 150mm X 230mm fixed with 2 nos. of good quality 50mm stainless steel hinges of approved make. Inner surface painted with one coat of primer and two coats of synthetic enamel paint and out side finished with 1mm thick laminate of approved shade as per direction of Architect. The middle portion of suggestion box will have transparent 5mm thick glass of approved size fixed properly etc. complete.				
11	<b>Suggestion Box</b>	1	NOS.		
	Providing & fixing Suggestion Box made from 19mm thick MR grade plywood of approved make. Door made of 12mm thick plywood of approved make to the size of 150mm X 230mm fixed with 2 nos. of good quality 50mm stainless steel hinges of approved make. Inner surface to be finished with 0.8mm thick approved make inner laminate / liner & all outside face to be finished with 1mm thick laminate of approved shade as per direction of Architect. The middle portion of suggestion box will have transparent 5mm thick glass of approved size fixed properly etc.				
12	<b>Providing &amp; Fixing of Wooden Storage</b>				
12.1	<b>Side Unit cabinate for Branch manager &amp; Officer table. (Size :- 3'-0" Length or length as per layout x 1'-3" Width x 2'-6" Height all as per direction.)</b>	15	SFT		
	Providing & fixing side cabinet (storage units) made out of 19mm thick MR grade UF plywood of approved make top, sides, rear, shelves and front doors with steam beech beading to exposed edges. The units shall be finished with laminate of approved make laminate of approved colour and shed on front shutter, side and top. The storage cabinate will have necessary shelves as per requirement. All the exposed wooden surfaces shall be duly laquore polished (matching with the laminate). The shutters shall be provided with Ebco/Godrej make multipurpose locks, SS hinges, handles, stopper inner side, magnet lock of approved quality. The side cabinate will have 2 nos. of drawers on top with required size with approved quality telescopic channel etc. and bottom portion will have openable shutter. The all inner surface of table, drawer & storage to be finished with approved make & approved shade 0.8mm thick inner laminate / liner etc. complete as per direction of Architect. ( Size :- 3'-0" Length or length as per layout x 1'-3" Width x 2'-6" Height all as per direction.)				
12.2	<b>Full Height Storage / Low Height Storage / Back Storage (Credenza) as per design.</b>	100	SFT		



	Providing and fixing in position Full height Storage/Low Height Storage/ Back Storage (Credenza) as shown in Drg.) respectively using Plywood of required thickness finished outer surface with laminate and all inner surface shall be finished, with colour of approved quality & shade suggested by Consultants as shown in the drawing The Storage (Credenza) shall be provided Consultants as shown in the drawing The Storage (Credenza) shall be provided with handles (Brass liquor finish) and channels as per approval of the Project Consultant / Bank. All exposed plywood surfaces to be finished by laminate of approved make & shade, and all exposed edges of top & ply verticals to have 1" x 1/4" T.W. lipping. All exposed T.W. sections to be melamine and internal surfaces to have polished as directed. Item to include plywood boxing, all necessary hardware and fittings in liquor finish,lipping to all edges etc. complete in all respects.				
13	<b>Wooden box covering to cover electrical D.B Board / electrical Panel</b>	35	SFT		
	P/F Wooden Cupbord to cover electrical D.B Board / Panel by 18 mm ply wood finished by 1 mm laminate the item include all hardware at fitting as per design of consultant. All inside wooden expose surface are to be finished by providing 0.75 / 0.80 mm thick laminate Liner / Inner Sheet of Durian make.				
14	<b>Pantry Storage below pantry platform</b>	0	SFT		
	P/F Wooden frame with wooden shutter below pantry platform by 18 mm ply wood finished by 1 mm laminate the item include all hardware at fitting as per design of consultant. All inside wooden expose surface are to be finished by providing 0.75 / 0.80 mm thick laminate Liner / Inner Sheet of Durian make.				
15	<b>Notice Board</b>	20	SFT		
	Providing & fixing notice board on brick wall made from 12mm thick soft board with approved colour of tapestry @ Rs. 100/- per meter on it. This will be fixed on wall with stainless steel mirror screw. The framing of soft board will be done with 1/2" x 3/4" CP teak wood section. The same framing will be finished by liquor polish etc. complete as per direction of Architect.				
16	<b>Wall Paneling</b>				
16.1	<b>Wooden paneling / cladding on B.M. Walls / R.C.C. columns or beam using 6mm thick M.R. grade plywood to be finished with 1 mm thick approved make &amp; approved shade laminate.</b>	200	SFT		
	Providing & fixing laminate paneling on RCC column. Paneling shall be done on necessary wooden framing with 12mm thick approved make MR grade Plywood and to be finished with 1mm thick laminate of approved make & shade.				
16.2	<b>Wooden wall paneling patta of 3" Ht at bottom of ceiling finished by 1 mm thick. laminate of matching color.</b>	0	RFT		
	Providing & fixing laminate patta paneling of minimum 3" ht on peripheral banking hall's / E-Lobby's / ATM's RCC columns / walls at bottom of ceiling to be made out of 12mm thick MR Grade approved make plywood. Paneling will be finished 1mm thick laminate of approved make, color & shade. Exposed surface will be liquor polished. The entire item will be carried out as per direction of Architect.				

16.3	<b>Plywood paneling Near Rolling shutter / Entrance Door</b>	0	SFT		
	Providing & fixing plywood paneling on Rolling shutter. Paneling shall be done on necessary wooden framing with 12mm thick plywood of MR grade UF plywood of approved make and finished with 1mm thick laminate of approved make & shed with inner surface will be with synthetic enamel paint of approved color. The entire item will be carried out as per direction Architect.				
16.4	<b>Aluminum Composite Wall Paneling For Branch's / E-Lobby's Inside / Outside Walls.</b>	80	SFT		
	Providing and fixing in position Aluminium composite wall panel Boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alu bond Exterior Grade 3 mm thick with composite of (0.5mm-3mm- 0.5mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow Corning 789) masking tape, necessary scaffolding etc. as req. Zindal make as detailed in drawing no.(11)complete in all respects.				
16.5	<b>Trap door for rolling shutter (in Wooden shutter &amp; ACP finishing)</b>	20	SFT		
	Providing/ fixing trap door for rolling shutter made out of 2"x1 ½" c.p.t.w. frame work covered with 9mm thick commercial ply from bottom side for shutter & 2"x2" c.p.t. wood outer frame with vertical supports up to R.C.C slab ,all the exposed surface shall be finish with approved make/color 1.00mm thick laminated and 3 coats of ENAMEL paint to inside including necessary approved make/ design brass hinges, concealed powder coated brass handles, brass stopper, brass lock, carting away debris out of compound, cleaning etc. complete as per the instructions of architect.				
17	<b>Providing &amp; Applying of Paint</b>				
17.1	<b>Providing Asian / Nerolac make texture paint on R.C.C. column / B.M. walls cladding all as per directed.</b>	0	SFT		
	Providing & applying Asian / Nerolac make texture paint on RCC columns / B.M. Walls Paneling shall be done with 2" X1/2" of steam beach wood decorative beading / moulding shall be provided at all around top / bottom & sides instructions with laquor polished.				
17.2	<b>Birla White Putty on Bank / E-Lobby / ATM's Internal walls &amp; ceiling.</b>	0	Sft		
	Providing, laying & leveling of Birla Putty lapi on existing walls evenly to give approved uniform surface for applying plastic paint. The item also includes one coat of primer and two coats of Birla putty lapi etc.complete as per requirement.				
17.3	<b>Distemper Paint on Strong room / Record Room / UPS Room / All utility area's walls &amp; Ceiling.</b>	0	SFT		
	Providing & applying distemper paint of including rubbing cleaning leveling the surfaces with putty with necessary scaffolding minimum 3 to 4 coats and scarping the existing white wash/paint etc. complete as per direction by Architect. This item also includes one coat of primer and two coats of putty / lapi etc. The rate includes scaffolding or Zula works.				
17.4	<b>Acrylic Emulsion Paint on Branch / E-Lobby / ATM's Internal walls.</b>	0	SFT		

	Providing & applying acrylic emulsion paint of approved shade and manufacture on walls applied evenly to give approved uniform matt finish etc. complete as per I.S. specification including scaffolding . (ICI) Dulux (valvet touch). Asin (Royal touch) .nerolac make, minimum 3 to 4 cost and scarping the existing white wash/paint etc. complete as per direction by Architect . this item also includes one cost of primer and two coats of putty lapi etc. complete as per requirement.				
17.5	<b>Enamel Paint</b>	650	Sft		
	Providing & applying one coat of primer and three coat of synthetic enamel paint of ICI dulux/Nerolac/Asian make & tint as per manufactures specification with brush including rubbing cleaning leveling the surfaces with putty with necessary scaffolding.				
17.6	<b>P/A Exterior Emulsion paint on exterior wall :-</b>	0	Sft		
	Providing & applying one coat of primer and three coat of exterior emulsion paint of ICI Dulux / Nerolac/ Asian make & tint as per manufactures specifications with brush including rubbing cleaning leveling the surfaces with necessary scaffolding works.				
18	<b>Wall Paper</b>	0	Sft		
	Providing & fixing canvas base pvc wall paper of approved pattern & design for chief manager cabin wall with anti bacterial adhesive bartoline with making proper surface of wall by POP etc. The basic cost of wall paper @ Rs. 100/- per SFT of approved make in roll form. This item will be carried out as per instructions given by Architects.				
19	<b>Roller Blinds</b>	50	SFT		
	Providing & Fixing Roller Blinds of with 5mm high x 50mm and 100mm wide 1.2mm thick walls of aluminum alloy head rail with 3.5.1 planetary reduction gear box (end control unit) with plastic tilting chain, tilt rod runners with firm and gear mechanism with 180 degree rotating louvers with approved shades by Architect/Consultant protected by dust guard. Fabric protector of VISTA LEVOLOR make with matching balance of same fabric on channel. The measurement shall be considered as per plan area of the window/ opening/partition only.				
20	<b>S.S. SOFA (3 Seater) :-</b>	0	No		
	Fabricating, supplying 3 seater S.S Cushion sofa in shape & size as directed by Consultant.Made up from S.S structure as decorative frame and inner structure of S.S pipe & cushion with foam sheet as per design & direction of Consultant.				
21	<b>R.C.C. works for safe embedding including fixing of M.S. collapsible gate</b>	0	JOB		
	Providing & casting R.C.C. embedding work for safe using M20 grade concrete and doubly reinforcement in top, bottom & sides, finished by 15mm thick cement plaster. The R.C.C. embedding work is to be done at about 2' height or as suggested by architect. The front side of R.C.C. embedding is to be provided by M.S. collapsible gate with enamelpainting on both sides.				
22	<b>M.S. Collapsible Gate</b>	36	SFT		

	Providing & fixing of M.S. collapsible gate at entrance door. The item includes of enamel paint on bothside of gate.				
23	<b>P/F M.S. Grill for all windows / ventilations using 12mm Thick M.S. square bar &amp; 75mm c/c of asian pipe / national pipe make.</b>	0	SFT		
	P/F M.S. Grill for all windows / ventilations using 12mm Thick M.S. square bar & 100 mm c/c of (asian pipe / national pipe make.) by framing as per individual window unit dimensions (LXH) & to be fixed by 5mm thick M.S. Patti frame all around. he item includes one coat of anti corrosive pain & two coat of enamel paint all as per design & directed by Architect.				
24	<b>Machine Grouting for Cash Deposit &amp; ATM Machine.</b>	0	JOB		
25	<b>Mirror for Strong Room</b>	0	NO		
	Providing fixing & supplying mirror of size 2'-0" x 5'-0" with necessary plywood base with 5mm thick approved quality mirror and shelf and wood framing with liquor polish etc. complete for Safe Deposit Vault as per design and direction of Architect.				
26	<b>Stool for Strong Room</b>	0	JOB		
	Providing fixing & supplying wooden dressing stool of size 1'-6" x 1'-6" for Safe Deposit Vault with required gadi with required thickness u foam, dunlop etc. and finished with 1mm thick laminate of approved color and shade as per design and direction of Architect.				
27	<b>M.S. Rolling Shutter for Branch &amp; E-Lobby Entry</b>	120	SFT		
	Providing & Fixing of M.S. Rolling Shutter made out of foldable sheet for Branch & E-Lobby Entry with complete locking arrangement. The job is including applying of 2 coat of anti corrosion paint (Red oxide) and 2 coat of oil paint in black color on all sides. the job is including all charges like labor for installations, loading, unloading, transportations & taxes other than GST				
A	<b>TOTAL AMOUNT OF INTERIOR FURNISHING WORKS EXCLUDING G.S.T. (NOTE :- THIS AMOUNT WILL BE CONSIDERED FOR COMPARATIVE FOR ALL PARTICIPATED BIDS)</b>				
B	<b>ADD S.G.S.T. @ 9% ON A</b>				
C	<b>ADD C.G.S.T. @ 9% ON A</b>				
D	<b>TOTAL G.S.T. = B + C</b>				
E	<b>TOTAL ESTIMATE OF INTERIOR FURNISHING WORKS INCLUDING G.S.T. = A + D</b>				

**BOQ OF EXISTING FURNISHING (RENOVATION) WORKS FOR  
OF UCO BANK SATELLITE BRANCH & ATM (UNDER AHMEDABAD ZONAL OFFICE)**

SR. NO.	DESCRIPTION	QTY.	UNIT	RATE IN RS.	AMOUNT	IN RS.	Remarks
	<b>INSTRUCTIONS :- DO ALL AS PER THE INSTRUCTIONS &amp; UNDER GUIDANCE OF ARCHITECT. (PLEASE ASK TO ARCHITECT IF ANY QUERY BEFORE QUOTE THE RATE) THE CONTRACTOR IS REQUESTED TO FIRST VISIT THE EXISTING OLD BRANCH &amp; ENSURE THE EXISTING CONDITION OF FURNITURE BEFORE QUOTE THE RATE. NO EXCUSES WILL BE ALLOWED THAN AFTER QUOTE THE RATE.</b>						
29	Renovation of existing branch furniture by Re-Lamination by removal of existing old laminate from wooden partitions, wall paneling, storage, work stations, cash counters, writing desk, suggestion box, electrical D.B. board, wooden shutters etc. & Providing New 1mm Thick approved Shade & Approved make laminate (As per Bank's Standard Manual) by fixing of 8mm thick of approved make exterior grade MDF on old ply. Note :- Please refer bank Slandered Manual first for the caption works. Please follow the process mentioned below.						
	Use Cutter Machine / Grinder Machine & makes patch works / smoothening of works using the machines on the existing laminate surfaces for making the surface ruff for better gripping of 8mm thick Exterior Grade MDF.						
	Providing & fixing of 8 mm thick approved make exterior grade MDF on that ruff surface using nailing & approved make adhesive like Fevicol, Blue Coat etc.						
	Providing & Fixing of 1 mm thick approved make & shade laminate on the MDF using approve make laminate like Fevicol / Blue Coat etc by proper cutting, finishing & pacing in the manner that no bubbles / air gape should accurse between ply & laminate bonding.						
	The item rate Includes materials, labor, transportations, loading, unloading, wastage, profit of contractor etc.						
29.1	Re-Lamination Process as mention above for all existing partitions, wall paneling, storage, Writing Desk, Electrical cup board, Shutters Etc.	850	SFT				
30	SAME AS ABOVE FOR MANAGER, OFFICER & CLERK, CASH COUNTER, CASH SORTING TABLE :-						
30.1	Branch Manager Table (Including Side Storage Unit) (Approx Size of table :- 6'-3" Length X 2'-6" Width X 2'-6" Height & side storage unit of 'size :-3'6" Length X 1'-3" Width X 2'-6" Height )	1	NO				
30.2	Officer Table (Including Side Storage Unit) (Approx Size of table :- 5'-6" Length X 2'-6" Width X 2'-6" Height & side storage unit of size :- 3' Length X 1'-3" Width X 2'-6" Height )	2	NO				

Note :- Please refer bank Slandered Manual first for the caption works

A	<b>TOTAL AMOUNT OF INTERIOR FURNISHING WORKS EXCLUDING G.S.T. (NOTE :- THIS AMOUNT WILL BE CONSIDERED FOR COMPARATIVE FOR ALL PARTICIPATED BIDS)</b>	
B	ADD S.G.S.T. @ 9% ON A	
C	ADD C.G.S.T. @ 9% ON A	
D	TOTAL G.S.T. = B + C	
E	<b>TOTAL ESTIMATE OF EXISTING FURNISHING (RENOVATION) WORKS <u>INCLUDING G.S.T.</u> = A + D</b>	