

**Bill of Quantities for : Proposed Furnishing work for CONFERENCE ROOM, at Third floor,  
UCO Bhavan, Ashram Road, Ahmedabad for UCO Bank, Z. O. Ahmedabad**

NO.	DESCRIPTION	QTY	UNITS	RATE	AMOUNT
-----	-------------	-----	-------	------	--------

**1 FULL HEIGHT PARTITION**

Providing & fixing new wooden partitions (approximate 9'-0" height) made out of 2" x 1" x 1mm thick aluminum section frame work @ 1'-9" to 2'-0" c/c in both ways covered with 6mm thick MR grade UF plywood with proper joinery etc. The aluminum section members of partition shall be rigidly fixed to the existing flooring, ceiling, beam, slab, side walls. Door frames made out of 3" x 1½" hard wood frame in laquore polish and shutters made out of 4" x 1½" wood frames for verticals and 6" x 1½" frame for locking and bottom levels complete with 6mm thick MR grade UF plywood on either sides, 3 nos. of stainless steel hinges, handles, dead locks, door stoppers, heavy duty door closer etc. complete as per design and details of Architect. Necessary openings in the partition shall be provided for AC grills, electrical conduits and switches, data cabling etc. and finished with 1mm thick laminate on both side complete with wooden steam beech molding in laquore polish finish and as per the design and pattern given. (Ht. of item also includes one coat of primer and two coats of putty/lapi etc. complete as per requirements. ernate corner vertical members of the partition shall be fixed necessary bracket/supports at RCC levels).

- |    |   |     |     |
|----|---|-----|-----|
| A) | For Conference room etc. complete as per design & direction of Architect.   | 100 | SFT |
| B) | Existing partition used with both side 6mm th. Plywood of approved make & one side 1mm th. Laminate of approved color & shade and make other side ply 6mm plywood of approved make only for making surface for veneer paneling. The entire item will be carried out as per design & direction of Architect. | 325 | SFT |
| C) | Do item no. 1 but Only extra rate difference for veneer paneling on wooden partition with laquore polish etc. complete as per direction.<br><b>(Basic cost of veneer @ Rs. 150/- per SFT)</b>   | 400 | SFT |

## 2 CONFERENCE ROOM TABLE

- |   |   |    |
|---|---|----|
| Providing & fixing Conference room table(23'-0" X 7'-0" for 20-22 persons) made out of 19mm thick MR grade approved make plywood with top & bottom structure with 38mm thick on outer periphery. Base support made out of 12mm thick plywood of approved make with hard wood support etc. as per design and drawing. All visible surface is like sides of base etc. finished with laminate of approved make of approved shade and textures. <b>Top shall be provided with 1mm thick core laminate as per design.</b> All the exposed surface of beading, frame shall be duly laquore polished matching to laminate). The <b>inner surface of table will have 0.8 mm thick liner balance laminate of approved make, shade &amp; color.</b> The entire table will be made as per direction & design of Architect. - 1 No. Table | 1 | NO |
|---|---|----|

## 3 ALUMINUM WINDOWS

- |   |     |     |
|---|-----|-----|
| Providing new Aluminium powder coated sliding windows with 14 SWG 2½" X 1½" box frame around and other section of 16 SWG of Jindal make. In proper line and level with all accessories like locking arrangement, rollers, handles, hinges, ball bearings, 5mm thick glass with necessary beading etc. The window shall be two track and should have proper pipe framing and gutter type hollow bottom for avoiding rain water. If required the window will have a gap for fixing of A. C. machine, which shall be covered with the 5mm fixed glass.   |     |     |
| All aluminum sections used in windows should have minimum weight of 16 guage Imported ball bearings must be used in shutter bottom section and concealed type spring lock for locking and handling used. All the gaskets must be used of good quality PVC or EPDM rubber only. The entire window should be finished in 55 to 65 microns powder coating by seven tank process. This job includes applying required coats of silicon silent for weather protection etc. complete as per direction of Architect. This item also includes removing of existing wooden window with frame, shutters & grills etc. complete as directed. | 200 | SFT |

#### 4 GYPSUM BOARD FALSE CEILING WITH PAINT

In split level & design providing & fixing Gypsum board false ceiling and false beam with plain gypsum boards sheets of 12.5mm thick weight 12Kgs/sq.mt. and 1300 wide and 1800 length screwed by dry well uncrown to maintain supporting of ceiling section of 80 x 26 x 0.5mm thick at 1'-6" interval. There shall be per meter channel fixed to vertical face of wall of beam of size 20 x 27 30mm at 4'-0" distance to receive and of GL ceiling sections and the other edges of gypsum board. The GI section are to fixed intermediate channels of size 15mm x 9mm thick by connecting clips of 2.6mm dia.

The intermediate channels are hung from the soft fit clear by strap hunger channel of India gypsum make. The rate shall include all scaffolding and support arrangements breakage of RCC slab of cleats cut puts and openings for light fitting. No deduction shall be made for output opening etc. All the material should be of Indian Gypsum made. Provision of additional gypsum boards of 12.5mm thick to create bands, steps & patterns. Provision of the additional frame work of per meter channel around light fixtures & A.C. grills. **The measurement shall be considered as per the plan area of the premises.** (No vertical patta etc. consider separately.) Providing & applying Plastic paint of approved shade and manufacturer on walls applied evenly to give approved uniform matt finish etc. complete as per I. S. specifications including scaffolding. (ICI Dulux (Valvet Touch), Asian (Royal Touch), Nerolac) make, minimum 3 to 4 coats and scarping the existing white wash/paint etc. complete as per direction by Architect. This item also includes one coat of primer and two coats of putty/lapi etc. complete as per requirements.

550 SFT

#### 5 WOODEN LAMINATE PANELING

Providing & fixing laminate paneling on RCC column/wall etc. to be made out of 1" x 1" hard wood framing for leveling 1t 2'-0" c/c in both ways with 12mm thick MR Grade UF plywood of approved make. Paneling will be finished 1mm thick laminate of approved color & shade. If necessary 2" X 2" decorative beading/moulding will be provided at top & bottom or as per instructions with liquor polished. The entire item will be carried out as per direction of Architect.

100 SFT

#### 6 ROLLER BLINDS

Providing & Fixing roller Blinds of Dustguard Classic range with 5mm high x 50mm and 100mm wide 1.2mm thick walls of alluminium alloy head rail with 3.5.1 planetary reduction gear box (end control unit) with plastic tilting chain, tilt rod runners with firm and gear mechanism with 180 degree rotating louvers with approved shades by Architect/Consultant protected by dust guard. Fabric protector of ADORN make with matching balance of same fabric on channel. The measurement shall be considered as per plan area of the window/ opening/partition only and measurements of Air conditioners will be deducted.

200 SFT

**7 CONFERENCE ROOM CHAIR**

Providing & supplying ISI make approved quality & design 22 NOS  
 Revolving, Tilting, Medium Back Conference room Chairs as per  
 company specifications and approved as per instructions of the  
 Architects.

**8 WOODEN FLOORING**

Providing & fixing new wooden flooring of 8mm thick AC-3 of 550 SFT  
 approved make with 1288mm x 196mm size (4'-3"x 8") with 2mm  
 thick Armour and 0.5mm thick film underlay at bottom with dock lock  
 joints facility – class 31/23 etc. This item also include the all the  
 accessories, beading etc. and leveling with POP/cement if required  
 as per direction of Architect/Bank.

**9 WOODEN STORAGE CABINATE FULL HEIGHT**

Providing & fixing low height/full height storage cabinate made out 50 SFT  
 of 19mm thick MR grade UF plywood of approved make top,  
 sides, rear, shelves and front doors with steam beech beading to  
 exposed edges. The units shall be finished with laminate of  
 approved make laminate of approved colour and shed on front  
 shutter, side and top. The storage cabinate will have necessary  
 shelves as per requirement. All the exposed wooden surfaces shall  
 be duly laquore polished (matching with the laminate). The shutters  
 shall be provided with Ebco/Godrej make multipurpose locks, SS  
 hinges, handles, stopper inner side, magnet lock of approved  
 quality. The side cabinate will have openable shuuter with required  
 size with approved quality etc. The inner surface of storage cabinate  
 with shutter will have 0.8mm th. balance laminate/liner of approved  
 make etc. complete as per direction of Architect. Up to 4'-0" & 7'-0"  
 height.

**10 PLASTIC PAINT ON WALLS**

Providing & applying Acrylic Emulsion Luster paint of approved 200 SFT  
 shade and manufacturer on walls applied evenly to give approved  
 uniform matt finish etc. complete as per I. S. specifications including  
 scaffolding. (ICI Dulux (Velvet Touch), Asian (Royal Touch),  
 Nerolac) make, minimum 3 to 4 coats and scarping the existing  
 white wash/paint etc. complete as per direction by Architect. This  
 item also includes one coat of primer and two coats of putty/lapi etc.  
 complete as per requirements as per direction.

**MINERAL FIBER TILES SILLHOUTTEE TYPE GRID****11 CEILING**

Providing & fixing of Mineral Fiber false ceiling sillhouttee type of  
 "Armstrong" make tiles, with hot dipped galvanized steel grid work,  
 surface chemically cleaned capping pre-finished in backed polyester  
 paint, Main Tees of size 33 (H) X 24mm every 1.2 M centre to  
 centre, rotary stitched Cross Tee at 0.60 M centre to centre to form  
 a grid of 600mm X 600mm and suspending the grid from RCC roof  
 using 2mm G. I. rod and 6mm nylon rawl plug at every 1200mm  
 intervals and laying "Armstrong" New NDF mineral fiber Acoustic  
 ceiling tiles.

New NDF Tegular edge 15mm thick of size 595 X 595mm Tiles are 300 SFT having fire rating of 60 minutes as per BS47G/23 of 1987. Light Reflection > 75 %, Noise Reduction Coefficient (NRC) of 0.55 to 0.60, Sound Attenuation of 32 db, K = 0.52-0.57 W/mk. Humidity Resistance (RH value) up to 99% at 50'C. The tile comes pre-painted with three coats of white on facing side and one coat primer on back side. The above ceiling will be completed as per direction of Architect/ Bank. The measurement shall be as per plan area of the premises. This item will be carried out as per matching to the existing pattern mineral fiber false ceiling.

<b>TOTAL OF PART " I to VI " FURNITURE WORK</b>	<b>Rs.</b>	
---	------------	--

**ADD FOR GST @ \_\_\_\_ % ON RS.** **(+)** **Rs.**

**FINAL TOTAL OF FURNITURE WORK** **Rs.** \_\_\_\_\_

**Rupees**

**Name of Contractor with Seal & Signature**

**Date :**

**Place :**