

B.O.Q FOR AC FITTING WORK OF UCO BANK , KEONJHAR BRANCH .

SL.NO.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
	I.SPLIT A.C FITTING				
1.1	Supply of 1.5 TR Hi-wall Split AC (3 star) units including outdoor condensing unit, with Copper coil condenser, Multifunction cordless remote control with other accessories as required. Hi-wall split Air conditioner fitted with rotary type compressor. <u>The rate shall include 3.0 mtr. of refregerent pipe & electrical cabelling for each machine.</u> All machines shall be white in color. MACHINES SHALL HAVE LATEST STAR BAND VALIDITY I.E. 2018	No.	3.00		
1.2	Supply of 1.0 TR Hi-wall Split AC (3 star) units including outdoor condensing unit, with Copper coil condenser, Multifunction cordless remote control with other accessories as required. Hi-wall split Air conditioner fitted with rotary type compressor. <u>The rate shall include 3.0 mtr. of refregerent pipe & electrical cabelling for each machine.</u> All machines shall be white in color. MACHINES SHALL HAVE LATEST STAR BAND VALIDITY I.E. 2018	No.	1.00		
2.0	Carrying out copper refrigerant piping (Liquid line & Suction line -1/2''&1/4'') between indoor and out door units complete with valves, fitting, supports, clamps with insulation & Cabling etc as required.(Beyond 3.0 R.Mtr. for each Split A.C.)	Rmt	10.00		
3.0	Supply and fixing of M.S stand wall/ floor mounting brackets suitable for holding the outdoor units structure made of 40x40x5mm M.S angles for installation of outdoor unit with anti-vibration pad including grouting on wall /floor etc as may be required depending upon site condition and as per the instruction. Grouting to be done by cutting necessary holes and grouting with M-12 anchor fasteners/ cement concrete 1:2:4 and making good the damages with similar finish, two coats of synthetic enamel paint over a coat of metal primer.	No.	4.00		



SL.NO.	DESCRIPTION OF ITEMS	UNIT	QUANTIT Y	RATE	AMOUNT
4.0	Condensate Drain piping with 40 mm nominal dia Schedule-80 Rigid PVC pipes (Minimum 4 mm wall thickness) with U traps having provision for periodical cleaning.	Rmt	10.00		
5.0	Providing and fixing wall mounting 4KVA automatic stabliser of ELPOWER/Sakti make/V-Guard (Input Voltage- 130V-280V, Output Voltage-230V) as per direction of engineering in charge including all labour and material.	No.	4.00		
6.0	Standard Installation and testing of Hi-wall Split type machines including indoor & outdoor machine erection, first Oil & Gas charging, installation & commissioning Including top and plug, vacucumissing, nitrogen pressure testing (as applicable).				
6.1	1.5 TR Hi-Wall Split AC	No.	3.00		
6.2	1.0 TR Hi-Wall Split AC	No.	1.00		
TOTAL				Rs.	

